

**Public Interest Energy Research (PIER) Program
FINAL PROJECT REPORT**

**APPLICATION OF HYDROGEN
ASSISTED LEAN OPERATION TO
BIOGAS FUELED RECIPROCATING
ENGINES (BioHALO)**

Prepared for: California Energy Commission
Prepared by: TIAX LLC



Innovation since 1886

MAY 2012
CEC-500-2012-064

Prepared by:

Primary Author(s):
Robert P. Wilson

TIAX LLC
Cambridge, MA 02140

Contract Number: PIR-02-001 WA 02-1009-05



Prepared for:

California Energy Commission

Valentino Tiangco
Contract Manager

Gerald Braun
Project Manager

Linda Spiegel
Office Manager
Energy Generation Research Office

Laurie ten Hope
Deputy Director
RESEARCH AND DEVELOPMENT DIVISION

Robert P. Oglesby
Executive Director

DISCLAIMER

This report was prepared as the result of work sponsored by the California Energy Commission. It does not necessarily represent the views of the Energy Commission, its employees or the State of California. The Energy Commission, the State of California, its employees, contractors and subcontractors make no warrant, express or implied, and assume no legal liability for the information in this report; nor does any party represent that the uses of this information will not infringe upon privately owned rights. This report has not been approved or disapproved by the California Energy Commission nor has the California Energy Commission passed upon the accuracy or adequacy of the information in this report.

Preface

The California Energy Commission's Public Interest Energy Research (PIER) Program supports public interest energy research and development that will help improve the quality of life in California by bringing environmentally safe, affordable, and reliable energy services and products to the marketplace.

The PIER Program conducts public interest research, development, and demonstration (RD&D) projects to benefit California.

The PIER Program strives to conduct the most promising public interest energy research by partnering with RD&D entities, including individuals, businesses, utilities, and public or private research institutions.

PIER funding efforts are focused on the following RD&D program areas:

- Buildings End-Use Energy Efficiency
- Energy Innovations Small Grants
- Energy-Related Environmental Research
- Energy Systems Integration
- Environmentally Preferred Advanced Generation
- Industrial/Agricultural/Water End-Use Energy Efficiency
- Renewable Energy Technologies
- Transportation

Application of Hydrogen Assisted Lean Operation to Biogas-Fueled Reciprocating Engines (BioHALO) is the final report for the BioHALO project (Grant Number PIR-02-001) conducted by TIAX LLC. The information from this project contributes to PIER's Renewable Energy Technologies Program.

For more information about the PIER Program, please visit the Energy Commission's website at www.energy.ca.gov/research/ or contact the Energy Commission at 916-327-1551.

When the source of a table, figure or photo is not otherwise credited, it is the work of the author of the report.

Please cite this report as follows:

Robert P. Wilson. 2009 *Application of Hydrogen Assisted Lean Operation to Biogas-Fueled Reciprocating Engines (BioHALO)*. California Energy Commission, Energy Technologies Program. CEC-500-2012-064.

TABLE OF CONTENTS

ABSTRACT	IX
EXECUTIVE SUMMARY	1
1. BACKGROUND AND OBJECTIVES	3
1.1 BACKGROUND -- CURRENT LANDFILL TECHNOLOGY	3
1.2 OVERVIEW OF THE BIOHALO APPROACH	6
1.3 OBJECTIVES	6
1.4 BENEFITS OF BIOHALO	8
2. BIOHALO PROCESS DESCRIPTION AND TECHNICAL ISSUES ADDRESSED	11
2.1 DESCRIPTION OF BIOHALO PROCESS	11
2.2 TECHNICAL ISSUES ADDRESSED	13
2.3 NOX EMISSIONS FROM INTERNAL COMBUSTION ENGINES	14
2.3.1 Engine-Out Emissions Level Is Critical for Landfill Gas Engines	15
2.3.2 Lean-Burn Provides Ultra-Low Engine-Out NO _x and High Efficiency	15
2.3.3 Lean-Burn – Technical Challenges	16
2.3.4 Hydrogen Assisted Operation Addresses the Central Challenges of Lean-Burn	17
2.4 HYDROGEN PRODUCTION AND REFORMERS	19
3. TECHNICAL APPROACH	23
3.1 TECHNICAL APPROACH BASED ON TIAX’S HALO TECHNOLOGY	23
3.2 TECHNICAL APPROACH	24
3.2.1 Task 2.1 – Engine/Generator Installation	24
3.2.2 Task 2.2 – Engine Scoping Tests and Modeling	25
3.2.3 Task 2.3 – Conceptual Process Optimization	26
3.2.4 Task 2.4 – BioHALO System Conceptual Design	26
3.2.5 Task 2.5 – BioHALO System Detailed Design	27
3.2.6 Task 2.6 – Prototype BioHALO Reformer and Engine Interface Fabrication	27
3.2.7 Task 2.7 – Prototype Testing in the Plant	27
3.2.8 Task 2.8 – Assemble BioHALO System on the In-Field Test Engine/Generator	28
3.2.9 Task 2.9 – Field Demonstration and Performance Testing	28
3.3 PROCESS MODELING	28
4. RESULTS OF TEST ENGINE INSTALLATION AND COMMISSIONING AT TIAX	29
5. RESULTS OF BIOHALO SCOPING TESTS (TASK 2.2)	35
5.1 SUMMARY OF SCOPING TEST RESULTS	35
5.2 SCOPING TEST PROGRAM OVERVIEW	35
5.2.1 Rationale for Testing	35

5.2.2.	Test Objectives	36
5.3	ENGINE DESCRIPTION	36
5.4	TEST PLAN.....	38
5.4.1.	Test Procedures.....	38
5.4.2.	Test Measurements	43
5.4.3.	Data Analysis Procedures	44
5.4.4.	Quality Assurance Procedures Followed	44
5.5	TEST RESULTS AND DISCUSSION	45
5.5.1.	LFG/Reformat Test Results	46
5.6	CONCLUSIONS AND RECOMMENDATIONS FROM SCOPING TESTS	50
6.	RESULTS OF CONCEPTUAL BIOHALO PROCESS OPTIMIZATION	53
6.1	TASK 2.3 SUMMARY	53
6.2	TASK 2.3 APPROACH.....	53
6.3	TASK 2.3 TEST PROGRAM OVERVIEW	54
6.3.1.	Engine Description.....	54
6.3.2.	Task 2.3 Test Objectives.....	54
6.4	TASK 2.3 TEST PLAN DESCRIPTION.....	55
6.4.1.	Test Procedures.....	55
6.4.2.	Test Measurements	57
6.4.3.	Data Analysis Procedures	57
6.4.4.	Data Analysis Procedures	57
6.5	TEST RESULTS OF TASK 2.3	57
6.5.1.	Results of Higher Hydrogen Supplementation/Improved Engine Setup	59
6.5.2.	Higher Ignition Energy Test Results	61
6.5.3.	EGR Systems Test Results	68
6.5.4.	Water Injection Test Results.....	73
6.5.5.	Conceptual Process Optimization Overview	74
6.5.6.	Extended Time Period Test Run	78
6.6	REFORMER AND HEAT EXCHANGER SYSTEM OPTIMIZATION	80
6.7	RESULTS AND RECOMMENDATIONS BASED ON TASK 2.3 TEST RESULTS	84
7.	RESULTS OF BIOHALO SYSTEM CONCEPTUAL AND DETAILED DESIGN.....	85
7.1	DESIGN BASIS OF BIOHALO SYSTEM.....	86
7.1.1.	Engine Operating Parameters for Optimization of NO _x	86
7.1.2.	Design Basis for BioHALO System.....	87
7.2	SYSTEM SPECIFICATIONS OF BIOHALO SYSTEM.....	89
7.3	HEAT AND MASS BALANCE FOR BIOHALO SYSTEM.....	90
7.4	SCHEMATIC DRAWINGS AND EQUIPMENT LIST FOR BIOHALO SYSTEM.....	92
7.4.1.	Schematic and P&IDs	93
7.4.2.	Equipment List	94
7.5	START UP AND OPERATING STRATEGIES FOR BIOHALO SYSTEM	95
7.6	DETAILED DESIGN OF BIOHALO SYSTEM.....	96
7.6.1.	Assembly Drawing of BioHALO Engine-Generator Reformer System	96

7.6.2.	Illustration of Reformers (Commercially Available).....	97
7.6.3.	Heat Exchanger Subsystem Drawing.....	98
7.6.4.	Engine Installation Drawing.....	99
7.6.5.	Turbocharger Drawing.....	100
7.6.6.	Illustration of Oxidation Catalyst (Commercially Available).....	101
8.	EQUIPMENT AND PURCHASED COMPONENT SPECIFICATIONS	102
8.1	ENGINE GENERATOR SET.....	102
8.2	TURBOCHARGER AND OTHER ENGINE MODIFICATIONS FOR LEAN BURN OPERATION ON LFG.....	102
8.3	AUTO-THERMAL REFORMER.....	103
8.4	HEAT EXCHANGER MODULE.....	103
8.5	MIXING PLENUM, AIR BLOWER, AND BURNER FOR START UP	103
8.6	EXHAUST OXIDATION CATALYST (REQUIRED TO MEET TARGETS FOR CO AND VOC ENGINE- OUT EMISSIONS).....	104
8.7	CONTROLS.....	104
8.8	BILL OF MATERIALS	105
8.9	DESCRIPTION OF START-UP AND OPERATING CONTROLS FUNCTIONS	105
8.9.1.	Start Up Control Sequence.....	105
8.10	MECHANICAL, PIPING, AND ELECTRICAL CONNECTIONS.....	108
9.	COMMERCIALIZATION OUTLOOK AND TECHNOLOGY TRANSFER ACTIVITIES .	122
9.1	TECHNICAL AND PERFORMANCE ATTRIBUTES OF BIOHALO.....	122
9.2	ECONOMICS OF BIOHALO.....	123
9.3	ADDRESSABLE MARKET FOR BIOHALO	124
10.	CONCLUSIONS AND RECOMMENDATIONS.....	127
	GLOSSARY	130
	APPENDIX A. COMPLETE DATA SET	131

LIST OF TABLES

Table 1-1.	Current and Proposed Waste-Gas Emission Standards for IC Engines.....	4
Table 5-1.	Ford Power Products WSG-1068 Specifications	37
Table 5-2.	Average Synthetic LFG Composition Ranges over Test Matrix.....	40
Table 5-3.	Natural Gas Composition	40
Table 5-4.	Test Matrix	40
Table 5-5.	Synthetic Reformate Composition from Reformer.....	42
Table 5-6.	Measured Engine Operating Parameters.....	43
Table 5-7.	Baseline Test Results Summary	45
Table 5-8.	Stability Scoping Testing Summary—No Reformate.....	45
Table 6-1.	Ford Power Products WSG-1068 Specifications	54

Table 6-2. Average Synthetic LFG Composition Ranges Over Test Matrix.....	55
Table 6-3. Test Matrix	55
Table 6-4. Synthetic Reformate Composition From Reformer.....	57
Table 6-5. Summary of BioHALO Setups for Task 2.3.....	58
Table 6-6. Summary of points where IMEP COV < 11%	61
Table 6-7. Smartfire Ignition System Specifications	62
Table 6-8. VimX Ignition System Specifications	64
Table 6-9. Summary of Lowest NOx Results for Higher Ignition Energy Tests	67
Table 6-10. Summary of Lowest NOx Points for EGR Tests	73
Table 6-11. Summary of Water Injection Test Points	74
Table 6-12. Summary of Low NOx Points with Acceptable Combustion Stability	77
Table 6-13. Summary of Extended Test Run	80
Table 6-14. Summary of Acceptable Reformer Parameters.....	83
Table 7-1. Heat and Mass Balances.....	92
Table 7-2. Key Components.....	94
Table 7-3. Ford Power Products WSG-1068 Specifications	95
Table 8-1. Ford Power Products WSG-1068 Specifications	102
Table 8-2. Bill of Materials	105
Table 8-3. BioHALO Control System Specifications	106
Table 9-1. Emission Benefit of the BioHALO IC Engine for LFG to Electricity Applications	123
Table 9-2. Estimated Costs for Typical LFG to Electricity Projects	124
Table 10-1. Summary of Low NOx Points With Acceptable Combustion Stability.....	129
Table A-1. Marathon Generator Conversion Efficiency	132

LIST OF FIGURES

Figure 2-1. Process Flow Schematic of the Proposed TIAX BioHALO Landfill Gas Engine.....	12
Figure 2-2. Air Requirements and Resulting Diluent for BioHALO Operation with LFG and Natural Gas for a 75 kW Engine/Generator	13
Figure 3-1. Technical Tasks Flow Chart	24
Figure 4-1. Engine exhaust temperature and load for the initial engine/generator operating period.....	31
Figure 4-2. Generator electrical power output for the initial engine/generator operating period	31
Figure 4-3. View of the synthetic landfill gas mixing system.....	32
Figure 4-4. View of the right side of the test engine/generator	32
Figure 4-5. View of the left side of the engine/generator showing the oil cooler installed	33
Figure 5-1. Engine Control Hardware.....	36
Figure 5-2. Side View of Engine/Generator	38
Figure 5-3. Synthetic LFG Mixing System with Mass Flow Meters	39
Figure 5-4. BioHALO Schematic	39

Figure 5-5. Photograph of the Reformate Injection System	42
Figure 5-6. NO _x Emissions as a Function of O ₂ in the Exhaust.....	47
Figure 5-7. NO _x as a Function of O ₂ , with Reformate Levels Identified	48
Figure 5-8. NO _x as a Function of O ₂ , with Reformate Levels Identified in g/bhp-hr.....	48
Figure 5-9. IMEP COV as a Function of Exhaust O ₂ Concentration	48
Figure 5-10. IMEP LNV as a Function of Exhaust O ₂ Concentration.....	49
Figure 5-11. NO _x as a Function of Exhaust O ₂ , Data Points where IMEP COV was less than 10%	49
Figure 5-12. NO _x as a Function of Exhaust O ₂ , Data Points where IMEP COV was less than 10%	50
Figure 5-13. Data from TIAX Hydrogen Supplemented NG Engine Work.....	51
Figure 6-1. Timeline Covered By Report	58
Figure 6-2. Photograph of Intake System	60
Figure 6-3. Comparison of Task 2.2 data to improved setup and higher hydrogen supplementation	60
Figure 6-4. Comparison of NO _x values for the additional hydrogen supplementation/improved intake.....	61
Figure 6-5. Smartfire system installed on BioHALO engine.....	63
Figure 6-6. Smartfire schematic.....	63
Figure 6-7. Labeled VimX Ignition System.....	64
Figure 6-8. Screenshot of VimX Ignition System	65
Figure 6-9. Comparison of Smartfire Coil to Ford Coil	65
Figure 6-10. Comparison of VimX Ignition System with Standard	66
Figure 6-11. Effect of High Energy Ignition System on NO _x Emissions	67
Figure 6-12. Pressure Contours for the Selected Venturi	68
Figure 6-13. Close Up of Venturi Throat.....	69
Figure 6-14. Photograph of High Pressure Loop EGR System	70
Figure 6-15. Photograph of second EGR setup	71
Figure 6-16. EGR Cooler Effectiveness.....	72
Figure 6-17. Effect of EGR on NO _x	72
Figure 6-18. Photograph of Water Spray	73
Figure 6-19. All corrected NO _x data, including water injection points, as function of Exhaust O ₂	74
Figure 6-20. Comparison of all results showing effect of hydrogen addition.....	75
Figure 6-21. Burn Time as a Function of Exhaust Concentration.....	76
Figure 6-22. Summary of points with acceptable combustion stability	77
Figure 6-23. NO _x Emissions and Excess Air during the Extended Test Run	78
Figure 6-24. Histogram of NO _x Data during Extended Time Test	79
Figure 6-25. NO _x Emissions Dependence on Exhaust O ₂	80
Figure 6-26. Intake Temperature as a Function of Boost	81
Figure 6-27. The effect of intake temperature on NO _x at low emissions points	82
Figure 6-28. The Impact of Hydrogen Supplementation.....	83
Figure 7-1. Schematic of BioHALO System.....	88

Figure 7-2. Two-Stage Heat Exchanger Concept	91
Figure 7-3. Schematic for the BioHALO Conceptual Design.....	93
Figure 7-4. Side View of Engine/Generator	95
Figure 7-5. Assembly Drawing of BioHALO System.....	97
Figure 7-6. Commercially Available Reformers from Aspen Products Group (left) and Intelligent Energy (right)	98
Figure 7-7. Heat Exchanger Module - Hot Section.....	99
Figure 7-8. Heat Exchanger Module- Exhaust Section	99
Figure 7-9. LFG Engine Converted from Ford V-10 Natural Gas Engine	100
Figure 7-10. Turbocharger	100
Figure 7-11. Compressor Map for Turbocharger for 80 kW BioHALO.....	101
Figure 7-12. Oxidation Catalyst	101

ABSTRACT

A biogas-fueled engine project was undertaken to demonstrate a new hydrogen-assisted operation technology that offers significant economic and environmental advantages over conventional NO_x engines for landfill gas to electricity applications. The project was led by TIAX, with Hess Microgen providing valuable support during the project. This innovative technology enables utilization of hydrogen-enriched landfill gas (LFG), produced on site, to shift the operating point of gas engines to low engine-out NO_x regimes which are otherwise not feasible. This technology provides an alternative to siloxane removal and selective catalytic reduction after treatment which is seen as prohibitively expensive. In the project, a Hess Microgen 75 kilowatt (kW) gas-fired engine cogeneration unit was installed at the TIAX engine test facility in Cambridge, Massachusetts. A series of scoping tests were performed on the installed engine/generator fueled with synthetic landfill gas and synthetic reformat prepared using bottled gases. The experimental setup was used to define optimum reformer and engine configuration, operating strategy, and process control that gave best emissions performance with acceptable process operation. Test results demonstrated that the gas engine could be operated for sustained periods at 100 percent excess air with engine-out NO_x emissions at 0.11 pound per megawatt-hour. Based on the optimum process configuration, the reformer and engine interface conceptual design, and detailed design was completed.

Keywords: Nitrous oxide, biogas, landfill gas, selective reduction catalyst, TIAX

EXECUTIVE SUMMARY

The biogas-fueled engine technology enables utilization of hydrogen-enriched landfill gas, produced on site, to shift the operating point of gas engines to low nitrous oxide (NO_x) regimes which are otherwise not feasible. Using this technology, there is no need for a selective catalytic reduction system which can be quite costly and requires siloxane removal to prevent poisoning. The gas engines are conventional modern engines in many respects, except they are specially fitted with an upstream fuel reformer which produces up to 10 percent hydrogen in the modified landfill gas fuel mixture. In California, there are 310 active municipal landfill sites (1999 EPA inventory), of which 20 percent have power generating applications. Installations must meet criteria pollutant standards which are 0.5 pound NO_x per megawatt-hour currently, and expected to be reduced to 0.1 pound per megawatt-hour by year 2012. There are hundreds of such reciprocating engine power-plants operating in the U.S. today on landfill gas, and the state-of-the-art low-NO_x engines emit approximately 1.2 pound NO_x per megawatt-hour. (See Section 1)

The objective of the demonstration was to prove that biogas hydrogen-assisted lean operation technology ("BioHALO") can be effective in lowering NO_x to 0.1 pound per megawatt hour by operating a retrofitted gas engine in a realistic landfill operating setting. The key accomplishments of the project can be summarized as follows: The team (1) designed, constructed, and installed a modified 75 kW, 10-cylinder Ford biogas engine at the TIAX engine test facility in preparation for the demonstration test (special engine parts and subsystems were fabricated which made the engine hydrogen-assist ready), (2) tested and optimized the BioHALO operating configuration for this engine using synthetic landfill gas and reformat gas mixed from gas cylinders and achieved low NO_x levels of 0.11 pound/megawatt-hour, (3) designed a reformer subsystem to produce hydrogen from landfill gas with required heat exchangers and process controls, (4) separately designed the interface of the reformer to the engine with required start up sequencing, (5) conducted extended duration tests at the low NO_x operating point at the TIAX test facility to demonstrate sustained operation, and (7) developed a planned path to market to commercialize the BioHALO technology.

In the project, a Hess Microgen 75 kW gas-fired engine cogeneration unit was installed at the TIAX engine test facility in Cambridge, Massachusetts. A parallel engine, reformer study was completed with a series of scoping tests performed on the installed engine/generator fueled with synthetic landfill gas. Synthetic reformat prepared using bottled gases was used in the tests. Next, the experimental setup was exercised in a series on concept optimization studies to define optimum reformer and engine configuration, operating strategy, and process control concept. The focus of these concept optimization studies was to find the process configuration and operational characteristics that give best emissions performance with acceptable process operation. These verification tests were also performed with synthetic reformat. Our definition of the optimum process configuration was adjusted based on verification test results.

Test results demonstrated that the gas engine could be operated for sustained periods at 100 percent excess air with engine-out NO_x emissions at 0.11 pound per megawatt-hour. With the optimum process configuration defined, the authors proceeded with tasks to complete the reformer and engine interface conceptual design, and detailed design.

Based on the test results and design work performed in this project, the following target performance specifications of the mature commercial embodiment of the hydrogen-assisted engine appear to be feasible with further work. If achieved, this technology will be quite competitive:

- 34-38 percent efficiency
- \$1000/kW installed cost
- Emission levels controlled to 0.1 pound per megawatt-hour NO_x
- No requirement for selective catalytic reduction

After the project was well underway, the necessary commercial partners did not provide needed matching funds (and a host landfill gas site) to build the field installation and to operate the landfill gas engine facility on an actual landfill gas as opposed to synthetic simulated gas. Nevertheless a significant number of technical advances were made, and these are summarized in this report for the benefit of future landfill gas engine development efforts that are being planned to commercialize BioHALO for landfill-gas power production.

The project was led by TIAX, with Hess Microgen providing valuable support during the project.

1.0 Background and Objectives

1.1 Background -- Current Landfill Technology

The project reported here addresses landfill gas usage for electricity in a clean and cost effective manner. Municipal solid waste landfills generate a waste gas consisting of methane, carbon dioxide, and non-methane organic compounds. Because landfill non-methane organic compounds contribute to ambient level ozone concentrations, a federal New Source Performance Standard was promulgated in 1996. This standard requires larger landfills to collect and combust their gas; perhaps more worrisome than the landfill contribution to ambient ozone, is their significant greenhouse gas emissions. Landfills are the largest emitter of methane in the United States, accounting for 35 percent of all methane emissions in 1999¹. While increased flaring of landfill gas will reduce emissions of methane, the flares generate nitrous oxide (NO_x) and carbon dioxide (CO₂). Converting the landfill gas to electricity has the added benefit of displacing central station power plant NO_x and CO₂ emissions.

The air quality management districts in California have adopted rules requiring many landfills to collect and “process” landfill gas. Most districts define “processing” as a 98 percent destruction of non-methane organic compounds. To date, most landfills have opted to simply flare their landfill gas. The California Energy Commission estimates that of the approximately 310 active municipal solid waste landfills, gas to electricity projects have been undertaken (in operation or planned) at approximately 60 of them. However many of these projects are held up by excessive NO_x emissions of the prime movers, internal combustion engines or microturbines. It is expected that rules requiring collection and destruction of landfill gas will be more widely applicable in the future. At the same time, there is increasing pressure to reduce criteria pollutant emissions from landfill gas prime movers.

The ideal landfill gas prime mover should be efficient, have minimal NO_x emissions, and be reasonably affordable. Higher efficiency units displace more fossil fuel generated electricity for a given amount of landfill gas. Since electricity generated at the landfill displaces central power plant electricity, criteria pollutant emissions (NO_x, CO, volatile organic compound [VOC], particulates [PM₁₀]) should be equivalent to or less than central station power plants on a pound/megawatt-hour (lb/MWh) basis. Finally, relatively low installed costs will result in more rapid and widespread conversion of landfill gas to electricity.

At present, there are two main options for conversion of landfill gas to electricity: the reciprocating internal combustion (IC) engine and the microturbine. The IC engine, because of its relatively high efficiency (28 to 38 percent) and low cost, is more prevalent. However, landfill-gas-fired IC engines suffer from relatively high NO_x emissions. Microturbines can emit less NO_x but are much less efficient (~23 percent) and up to three times more expensive. For fossil fuel applications, post-combustion catalytic reduction makes the IC engine NO_x on a

¹ U.S. Department of State, U.S. Climate Action Report 2002, Washington, D.C., May 2002.

lb/MWh basis equivalent to that from a microturbine. In fact, the California Air Resources Board (ARB) guidance document recommends identical best available control technology (BACT) NO_x levels for fossil-fuel-fired IC engines and microturbines², which are currently regulated at 0.07 lb NO_x per MWh.

Fossil fuel fired IC engines achieve their lowest achievable NO_x levels with either of two approaches: lean burn operation with ammonia-based selective catalytic reduction (SCR) or rich burn operation with a three-way catalyst (TWC). The lean burn approach is more efficient and typically yields lower NO_x levels than the rich burn plus three-way catalyst approach (0.21 lb/MWh vs. 0.45 lb/MWh). However, the SCR system is considerably more expensive.

Table 1-1. Current and Proposed Waste-Gas Emission Standards for IC Engines

	IC Engine lb/MWh		
	NO _x	VOC	CO
September 2001 (Current)	1.9	1.9	7.8
January 2008 (Proposed)	0.5	1.0	6.0
January 2013 (Proposed)	0.07	0.02	0.10

Table 1-1 shows the ARB-recommended BACT levels for waste-gas-fired units as of September 2001. In 2007, ARB proposed in their 10-19-2006 Rulemaking a NO_x level of 0.5 lb/MWh for certifying waste gas fueled IC Engines. The NO_x BACT level for waste-gas-fired IC engines proposed for January 2008 is seven times higher than that for fossil-fuel-fired IC engines (natural gas). The Air Resources Board has recommended the higher landfill gas fired IC engine NO_x levels as BACT for January 2008 because catalytic reduction techniques (TWC and SCR) are not presently feasible for waste-gas-fired engines. The catalysts in SCR and TWC systems are very sensitive to the presence of chlorine and chlorides, which react with both the ammonia added to the exhaust stream to form ammonium chloride and with the vanadium oxide in the catalyst, to form inactive vanadium chlorides³. In addition, siloxanes present in landfill gas (LFG) must be removed to prevent catalyst poisoning. Thus, the only NO_x control technique available for IC engines firing waste gas is lean burn combustion.

The lowest NO_x level from landfill-gas-fired IC engines has been achieved with a large (3 MW) lean burn Caterpillar engine equipped with a prechamber. Based on publicly available NO_x source test data, this engine emits between 0.4 and 0.6 grams per break horsepower-hour

² *Guidance for the Permitting of Electrical Generation Technologies*, California Air Resources Board, September 2001.

³ Chen, J. P., Buzanowski, M. A., Yang, R. T., and Cichanowicz, J. E., *J. Air Waste Manage. Assoc.* 1990, 40, 1403-9.

(g/bhp-hr⁴). The engine efficiency is approximately 36.7 percent, and it operates at twice the theoretical amount of air (lambda, the ratio of the actual amount of combustion air to the stoichiometric amount required to completely combust the fuel charge, of 2). The prechamber design allows for overall fuel lean combustion because the fuel is ignited with only a portion of the air in the prechamber. A lambda of 2 is close to the lean limit for prechamber engines, and therefore a NO_x level of 0.4 g/bhp-hr represents a NO_x emissions limit (barrier) for current technology landfill-gas-fired IC engines. Operationally, these engines suffer from heat losses due to the prechamber's high surface to volume ratio and the convective losses as the hot gases flow at high velocity through an orifice into the cylinder. These heat losses reduce cycle efficiency by three to four percentage points. Prechambers are also a high maintenance component.

Although achieving 0.4 g/bhp-hr (1.24 lb/MWh or 0.12 pounds per million British thermal unit (lb/MMBtu) at a heat rate of 10,600 Btu/kWh) is commendable for a waste gas fired IC engine, it is still significantly higher than the NO_x emission rate from a central station power plant. Senate Bill 1298 (2000, Bowen) was intended to protect the environment should a significant number of distributed generation units be installed. SB 1298 requires that the BACT levels for distributed generation units must be reduced to the level of a central station power plant equipped with BACT at the earliest practicable date. ARB has defined BACT for central station power plants as 0.06 lb/MWh. The ARB standard for natural gas fueled IC Engines as of year 2007 is 0.07 lb/MWh. This represents a 95 percent reduction over what is currently achievable with a landfill gas fired IC engine and/or microturbine. Clearly, a significant barrier for landfill gas to electricity projects is the increasing downward pressure on emissions beyond what is currently possible. Because the market size is limited, there is little financial incentive for engine manufacturers and pollution control equipment vendors to address the waste gas fired IC engine NO_x barrier.

This project leveraged the inherent high efficiency and low cost of lean burn IC engines by dramatically reducing NO_x emissions from the achieved-in-practice level of 0.4 g/bhp-hr (1.24 lb/MWh or 0.12 lb/MMBtu) to 0.035 g/bhp-hr (0.11 lb/MWh or 0.011 lb/MMBtu). A best effort was made to achieve a 95 percent reduction down to the central station power plant level of 0.02 g/bhp-hr (0.06 lb/MWh). Some landfill applications will be suitable for combined heat and power (CHP) projects since hot water will be generated from the sensible heat in the engine exhaust. To encourage CHP projects, ARB has recommended that the process heat used be added to the power output in the denominator of the NO_x emission factor calculation. For our BioHALO technology, taking credit for the 160,800 Btu/hr of hot water reduces the NO_x from 0.11 lb/MWhr to 0.06 lb/MWh, identical to the BACT level for central station power plants.

The primary biomass resource the researchers' technology addresses is LFG. While this resource at existing closed landfills has a 20- to 30-year lifetime, LFG will continue to be available from active landfills for a more extended period. However, as more of the organic

⁴ Srinivasan, K.K., et al. "The Advanced Injection Low Pilot Ignited Natural Gas Engine," *J. Eng. Gas Turbines and Power*, Vol. 128, p. 213, Jan 2006.

content of municipal waste is diverted from landfilling in response to state and local mandates, the quantity of LFG continuing to be produced will gradually decline. This represents a main strength of the BioHALO technology approach. Following this project, assuming TIAX teams with a landfill-to-power supplier, the authors expect to be able to demonstrate the BioHALO technology in the field within two years and commercialize the process shortly thereafter. Thus, the technology will be available while the LFG resource is still plentiful and will allow further exploitation of the resource using the most efficient and lowest cost means of generating electricity from LFG, the reciprocating IC engine-driven generator. The BioHALO technology can also be used with anaerobic digester gas at sewage and wastewater treatment plants, a biomass resource with longer lifetime, but presently produced in less significant quantities than LFG.

1.2 Overview of the BioHALO Approach

Reciprocating IC engines fueled with LFG have relatively high engine-out NO_x emissions. The common approach to reducing high engine-out emissions from natural gas or propane fueled engines is to employ post-combustion catalytic NO_x reduction. However, the use of catalysts is not feasible with LFG-fueled engines because LFG contains catalyst-inhibiting contaminants. Thus, it is necessary to reduce LFG engine emissions through in-cylinder combustion modifications. One of the best in-cylinder modifications is to employ lean combustion, (i.e., operate at high air-fuel ratios). However, there is a limit to how lean the engine can be operated imposed by the lean limit of stable combustion. This limit can be extended, though, by adding hydrogen to the fuel mixture. Thus, by employing BioHALO (hydrogen assisted lean operation), stable operation at very lean air-fuel ratios is possible, with attendant very low NO_x emissions. This was the basis of the technology to be developed and demonstrated in this project.

Fractional hydrogen substitution in spark-ignited engines burning natural gas, liquefied petroleum gas or gasoline has been investigated by a number of researchers and has been demonstrated to offer a number of advantages, primarily as a result of increased laminar flame speeds. The primary advantage, as noted above, is the ability to offer stable combustion at much higher air to fuel (A/F) ratio, with associated substantial reductions on engine NO_x emissions. Researchers' own engine modeling predictions and engine testing results show that 90 percent NO_x emission reductions from the 0.4 g/bhp-hr BACT levels noted above are in fact achievable. The economic projections show that an engine/ generator equipped with the BioHALO technology will be able to be installed at a capital cost of less than \$1,000/kW and have a simple payback of two to three years. Thus, the technology will be competitive.

1.3 Objectives

The technical performance objectives of this project were:

- Develop and demonstrate a landfill gas autothermal reformer with a 70 percent conversion efficiency. Conversion efficiency is defined as (H₂+CO) produced/CH₄ input to the reformer.
- Use the landfill gas reformat to reduce IC engine NO_x emissions to 0.032 g/bhp-hr (0.10 lb/MWh) without the CHP credit. With the CHP credit, NO_x emissions will be 0.02 g/bhp-hr (0.06 lb/MWh).
- Make a best effort to achieve the central station power plant best available control technology NO_x level of 0.032 g/bhp-hr (0.1 lb/MWh) without the CHP credit.

The economic performance objectives of this project were:

- At production volumes of approximately 100 units per year, a reformer capital cost of \$300/kW (where kW is H₂ + CO thermal equivalent on an lower heating value (LHV) basis).
- Installed capital cost of commercial system less than \$1000 kW.
- Simple payback period less than three years.

Table 1-2 lists the agreement targets, most desirable goals, and estimated project performance objectives. For NO_x emissions, the 0.032 g/bhp-hr target is shown converted to lb/MMBtu units. The VOC and CO goals include the use of an oxidation catalyst operating at approximately 85 percent efficiency. Oxidation catalysts are not prone to the poisoning that preclude the use of three-way and SCR NO_x catalysts with landfill gas. The economic targets are for a 75 kW BioHALO IC engine system as described in Section 8 and Section 9. As can be seen, the BioHALO IC engine surpasses the stretch goal for affordability.

Table 1-2. Comparison of Agreement Targets and Stretch Goals to the Project Objectives

Target Parameter	Units	Agreement Target	Stretch Goal	Project
Air Emissions ^a				
NO _x	lb/MMBtu	0.01	0.0005	0.01
VOC	lb/MMBtu	0.007	0.001	0.007
CO	lb/MMBtu	0.10	0.002	0.09
Affordability ^b	\$/kWh	<0.06	<0.04	<0.03
Capital Cost ^c	\$/kW	<1,000	<500	900
Heat Rate ^d	Btu/kWh	<11,000	<8,000	10,000 6,017
Lifetime	Hr	>5,000	>10,000	>5,000
Capacity Factor	%	>90	>95	>90

^a Converted NO_x goal (0.032 g/bhp-hr; 0.10 lb/MWh) to lb/MMBtu with heatrate of 10,000 Btu/kWh.

VOC and CO values assume the use of an oxidation catalyst at approximately 85% efficiency.

^b Assumes a 71 kW engine with 80% annual capacity factor. ^c Includes installation.

^d Improved Heatrate value (6,017) includes credit for cogenerated hot water used by plant (CHP).

In the project, researchers installed a Hess Microgen 75 kW cogeneration unit at the TIAX engine test facility in Cambridge, MA. Researchers next completed a parallel engine and reformer study with a series of scoping tests. The scoping tests were performed on the installed engine/ generator fueled with synthetic LFG. Synthetic reformat prepared using bottled gases was used in the tests. Next, the experimental setup was exercised in a series on concept optimization studies to define optimum reformer and engine configuration, operating strategy, and process control concept. The focus of these concept optimization studies was to find the process configuration and operational characteristics that gave best emissions performance with acceptable process operation. These verification tests were performed with synthetic reformat. The authors definition of the optimum process configuration was adjusted based on verification test results. With the optimum process configuration defined, the reformer and engine interface conceptual design, and detailed design were completed.

The BioHALO IC engine surpassed the stretch goal for efficiency if the combined heat and power (CHP) credit is taken. The IC engine/generator provided by Hess Microgen is a cogeneration unit. The proposed project will provide only a portion of the hot water required by the demonstration host site, so if successful, larger units could be used at other future installations. Per the project proposal, a description of the CHP heatrate calculation is provided in the following:

- Engine Heat Rate = 10,000 Btu/kWh
- Engine Output = 71 kW
- Engine Firing Rate = (10,000 Btu/kWh) * (71 kW) = 710,000 Btu/hr
- Engine Exhaust Flowrate = 1,340 lb/hr
- Engine Exhaust Temperature = 572°F
- Heat Exchanger Exit Temperature = 72°F
- Energy Recovered = (1,340 lb/hr)*(0.24 Btu/lb-°F)*(572-72)°F
= (160,800 Btu/hr)/(3,412 Btu/kWh)
= 47 kW
- CHP Efficiency = (710,000 Btu/hr) / (71 kW + 47 kW) = 6,017 Btu/kWh

1.4 Benefits of BioHALO

BioHALO benefits apply not only to landfill gas resources used for biogas-to-electricity, but also apply broadly to all forms of biomass-to-energy in California. Based on the Energy Commission Report *Biomass in California: Challenges, Opportunities, and Potential for Sustainable Management*

and Development (June 2005), the three primary sources of biomass for energy are agriculture, forestry, and municipal wastes. Of the 81 million gross tons of biomass produced annually, it is feasible to collect and use about 32 million tons for renewable electricity, biofuels, and biobased products. This is in addition to landfill biogas and wastewater treatment biogas. Currently, only about 5 million tons per year (16%) is used, in part because of the need for lower NO_x engine-generator technology such as BioHALO. Biomass currently provides an estimated 975 MW of generating capacity in California (2%) alone, of which 305 MW is landfill gas generation capacity (in place and planned). As reported by EPA and DOE, several other states have significant landfill gas and other biomass-derived syngas to electricity potential. The benefits of BioHALO could be extended to anaerobic digestion of dairy waste, food waste, waste water and other organic waste. Producer gas from thermal gasification of biomass is another source for BioHALO engine technology applications. Clearly there is enough resource to multiply this figure by a factor of five, and the BioHALO technology when commercialized could speed up the installation of the additional 5000 MW (for illustration think of 2500 BioHALO engines, each 2000 kW). This is not beyond the realm of feasibility because GE Jenbacher recently announced a single landfill installation in Europe with 60 engines (bringing the engine total to 560 engines sold) in *Diesel & Gas Turbine Worldwide* (January 2007).

Landfill operators need the type of technology we are proposing to develop and demonstrate to give them a near-term, cost-effective option to continuing to flaring LFG. The authors proposed technology can be readily integrated into the workhorse process for generating electricity from LFG and overcomes the major public objection to this approach, high NO_x emissions. Our approach is unique in that it makes use of the LFG already in place to achieve the NO_x reduction benefit achieved.

Just from landfill applications, the public benefits to be provided in California if the technology is successful and are incorporated into commercial IC engine driven generators include displacement of central station power, or creation of new generating capacity at lower cost, with annual public savings of \$12M in power costs (based on a cost savings of \$0.06/kW-hr); reduction in total greenhouse gas loading to the state of 0.9 Million tons/yr of CO₂ equivalent, with annual cost equivalent savings (at \$25/ton GHG) of \$22M; and reduction in NO_x emissions from landfills previously using higher emission IC engines or turbines, or using flaring. These benefits could be realized within a year of project completion, with no additional public funding required. Considering all other biomass fuel sources the above numbers are tripled.

2.0 BioHALO Process Description and Technical Issues Addressed

2.1 Description of BioHALO Process

Despite its technical success, the HALO concept for ordinary natural gas IC engines (not LFG) has not found a viable commercial application in fossil-fuel-fired engines because three-way catalysts are also relatively inexpensive and provide low enough NO_x emissions to meet current BACT requirements. Because SCR catalysts are not an affordable option for LFG engines, the proposal team believes that BioHALO is the least cost, lowest emitting, and fastest to market approach for LFG to electricity projects. However, there have been no demonstration projects for the BioHALO concept on landfill gas. A demonstration is the next necessary step to providing BioHALO as a viable near term NO_x control option for LFG fired IC engines.

The BioHALO technology uses an autothermal reformer (ATR) to generate hydrogen and CO from the landfill gas. Specifically, the BioHALO system includes the following:

- LFG Engine typically 75 kW to 1500 kW operated at 100% excess air (10% O₂ in exhaust) with high energy ignition system.
- Engine turbocharged to at least 0.5 bar intake manifold above atmospheric, and aftercooled to maximum intake manifold temperature 40°C.
- Landfill gas reformer sized to supply hydrogen at 10% of the methane flow rate by energy (33% by volume H₂ in total H₂ plus CH₄). This implies that approximately 15% of the LFG flow is diverted to the reformer to produce hydrogen. (The reformer also produces CO fuel value at 22% volume CO per volume of hydrogen; therefore the fuel value of the CO adds 26% to the H₂ fuel value).
- System efficiency accounting for reformer thermal management must be within 2% of baseline without BioHALO.
- Auto-thermal reformer operating at equivalence ratio 3:1 (200% excess fuel). This reformer can be designed around a low cost catalyst similar to an automotive three-way catalyst, and is slightly exothermic (adiabatic temperature rise of about 200°C between inlet and outlet). For catalyst light off, the inlet gases must be at 600°C.
- *Need to cool down the reformat fuel gases:* The reformat gas (H₂, CO and inerts) exits the reformer at about 800°C and must be cooled down to about 140°C before remixing with the 85% main stream of LFG fuel. Otherwise air breathing would be impacted and engine power would suffer.
- *Need for preheat and sources of preheat:* Three gas inlet streams must be preheated in order to enter the reformer at 600°C (about 1100°F); the LFG itself, the water vapor (steam) required, and the air supply to the reformer.
- The exhaust gas exits the turbocharger intercooler at about 550°F (250°C) and still contains about 14% of the original fuel energy. Therefore exhaust gas can be used to (a) preheat

water to 100°C before creating steam for the reformer, (b) partially preheat the air to the reformer, say up to 200°C, and (c) preheat the LFG slipstream up to 200°C.

- Hot reformat gas must be cooled and intake gases are available to provide cooling. The design assumes that a counter-flow heat exchanger is used.
- *Need LFG Burner for start up:* A small burner provides steam and preheats the reformer catalyst to light-off temperature

As shown in Figure 2-1, the reformat gas (H_2 , CO , CO_2 , and N_2) will be injected into the combustion air upstream of the turbocharger. For natural gas, existing TIAX data indicate that the NO_x target can be achieved at a lambda of 2.1 (see Figure 2-2). For stable operation at this high lambda, approximately 10-15 percentage of the fuel (LHV basis) must be reformat. For the landfill gas application, the same percent fuel must come from the reformat, but the lambda can be reduced to approximately 1.8 because of the large amount of diluent provided by the landfill gas itself.




Figure 2-1. Process Flow Schematic of the Proposed TIAX BioHALO Landfill Gas Engine

The main technical advances that are expected if the proposed technology is commercialized are twofold. First, testing the BioHALO concept on an LFG IC engine in the field will definitively show whether reciprocating IC engines can/should be installed at landfills in the future. The other contribution from this project was advancement of knowledge in LFG reforming. Technical advancements made now in the low-cost production of hydrogen from LFG will be very advantageous in the future when fuel cell technology becomes economically competitive. One can envision LFG reformers providing reformat to IC engines generating electricity and providing hydrogen to fuel cell-powered garbage trucks.

2.2 Technical Issues Addressed

These challenges that were addressed in this project are listed below:

- To achieve the target levels of NO_x, the LFG engine had to be operated considerably lean. Natural gas engines have to be operated at a lambda of 2.1 to achieve the target levels of NO_x emissions. By itself, at this level of dilution, stable combustion will not be supported. However, augmented by hydrogen, at nominally 10 percent of the total heat input to the engine, the engine can be operated at a lambda of 2.1. A key risk to this technology was the ability of the engine to run with LFG at this high level of dilution. Our preliminary modeling efforts showed that for a nominal hydrogen input of 7 percent, the same level of dilution can be achieved with LFG, but for a lower lambda (around lambda = 1.8). As shown in Figure 2-2, the model results indicated that for a hydrogen input of 6.75 percent, the same amount of diluent is required to sustain stable combustion and achieve the target NO_x, however, the amount of air required is significantly smaller. This is possible because of the large amount of CO₂ present in the LFG that acts as a diluent. Actual scoping tests that were performed during tasks 2.2 and 2.3 of this project confirmed the operability of the engine with LFG at high levels of dilution.




Figure 2-2. Air Requirements and Resulting Diluent for BioHALO, Operation With LFG and Natural Gas for a 75 kW Engine/Generator

- The very wide flammability limit of hydrogen, which is being taken advantage of in the HALO concept, also posed some inherent safety risks. One important consideration is the danger of pre-ignition of the hydrogen-LFG-air mixture in the intake manifold of the engine. Temperature and other activated components within the manifold could trigger the pre-ignition of the fuel mixture. However, previous studies by TIAX have shown that, at the high levels of dilution (see Item 1 above), the probability of pre-ignition of the fuel mixture is very low. The testing protocol used in this project established a safe operating envelope, mainly through the modeling efforts.

- Another important factor that is key to successful commercialization of BioHALO is the ATR to produce hydrogen-rich reformat from LFG. As is well known, LFG contains small amounts of sulfur and siloxane that can prove to be deleterious to reformer catalysts. This has been a common problem to the application of this technology since costly gas clean-up systems are required upstream of the reactor.
- Another factor that posed significant challenge to the program is also related to the operation of the ATR. The design had to provide preheat so that the large amounts of CO₂ in the LFG would still allow the ATR to achieve optimal temperature. The ATR system was designed to preheat the air with the exhaust from the LFG engine, thereby also increasing the overall efficiency of the system. The ATR design is flexible enough to allow for additional heat recovery to raise the inlet temperature of the ATR reactants. Waste heat from the LFG engine exhaust was also used to preheat the reactants that are needed for complete conversion to hydrogen and CO in the ATR.

The technical goal of the project was to demonstrate the feasibility of the BioHALO system as applied to landfill gas. To overcome the barrier to continued IC engine use in LFG to electricity projects, the authors have developed and demonstrated the use of hydrogen assisted lean operation (BioHALO) with simulated hydrogen production from LFG using autothermal reformer technology (BioHALO). This technology relies on the ability of hydrogen to extend the flammability limit for the stable combustion of methane to leaner air/fuel (A/F) ratios. Thus, while current technology operates at the lean flammability limit to achieve the above NO_x emission levels, the BioHALO technology will allow even leaner operation to achieve a significant further NO_x reduction. In this approach, a portion of the LFG fuel supply for the engine was fed to an onsite autothermal reformer that will produce a hydrogen-rich reformat, which will be combined with the engine combustion air, thereby allowing hydrogen to enrich the air/fuel charge.

2.3 NO_x Emissions From Internal Combustion Engines

The project addressed several challenging issues related to power generation from landfill gas (LFG) or other biogas. Operating an internal combustion engine (ICE) on LFG precludes conventional emission control approaches because of contaminants in the gas that would poison catalysts. Very lean engine operation is one technique for achieving low NO_x emissions; however, the low flame speed of methane limits the extent of lean operation.

The project resulted in the operation of an IC engine on LFG with very low emissions. The engine was operated on biogas in the Hydrogen-Assisted Lean Operation (BioHALO) configuration with onsite hydrogen generation. This section describes the challenges associated with emission reductions from IC engines and hydrogen production from LFG. BioHALO is directed at the central challenge of ultra-lean burn engines – repeatable, controlled, and complete combustion at very lean mixture ratios.

2.3.1. Engine-Out Emissions Level Is Critical for Landfill Gas Engines

Engine operating conditions and the extent of emission controls govern NO_x emissions from gaseous-fueled engines. These emission levels affect where engines can be permitted for continuous operation. The authors' review of natural gas engine emissions and the recently published California Air Resources Board (ARB) Best Available Control Technology (BACT) Guidance Document, combined with interviews of engine distributors, shows that market potential of LFG engines for power generation is limited by their ability to achieve low NO_x emissions.

Table 2-1 shows different configurations for IC engines and how the emissions are affected by emission controls. Both three-way catalyst (TWC) and selective catalytic reduction (SCR) can achieve very low NO_x emissions. However, operating engines on LFG presents additional challenges. LFG has a lower energy content than natural gas, and it contains contaminants such as chlorinated hydrocarbons, sulfur compounds, and siloxanes (silicon compounds). These components tend to make conventional emission control approaches impractical. Sulfur, siloxanes, and chlorinated compounds will affect both the performance effectiveness and the life of both TWC and SCR catalysts. Since removing contaminants from LFG is costly and generates waste disposal problems, engine modifications appear to be the optimal approach for achieving low emissions from LFG engines.

Table 2-1. Effect of Emission Controls on NO_x Emissions From IC Engines

Engine Operation	Emission Control	Impact on Emissions	NO _x (g/bhp-hr)
Stoichiometric	None	Highest NO _x emissions	8
Stoichiometric	Three-way catalyst	NO _x reacts with CO and HC on catalyst	0.15
Lean burn, prechamber	None	Lower combustion temperatures, less NO _x	0.4
Lean burn	SCR (not feasible for LFG)	NO _x reacts on SCR catalyst in the presence of injected ammonia	0.05 to 0.15
Lean burn with hydrogen	None	Hydrogen in fuel extends lean operating limit	0.032 to 0.10

2.3.2. Lean-Burn Provides Ultra-Low Engine-Out NO_x and High Efficiency

The concept of ultra-lean-burn IC engines is one that engine manufacturers have been pursuing for a long time. It is well-known and documented that lean-burn operation offers several valuable advantages, such as increased ratio of specific heats over the expansion stroke, less dissociation, reduced cooling losses, and reduced throttling losses. Over the years it has been well-documented that lean burn reduces NO_x and CO emissions while increasing engine thermal efficiency.

The formation of NO_x emissions in spark ignition engines is primarily controlled by two parameters: in-cylinder peak gas temperature and in-cylinder oxygen concentration. Both of

these parameters are affected by the air-fuel (A/F) ratio. For any fixed engine power setting, the in-cylinder gas temperature peaks at a slightly rich A/F-ratio (fuel equivalence ratio, $\phi \approx 1.1$). However at rich conditions the oxygen concentration is low, resulting in low NO_x emissions. As the A/F-ratio is progressively made leaner, the oxygen concentration increases and the in-cylinder peak gas temperature falls off. Initially, the increasing oxygen concentration offsets the falling gas temperature resulting in maximum NO_x emissions at an A/F-ratio slightly lean of stoichiometric ($\phi \approx 0.9$). As the A/F ratio becomes leaner ($\phi < 0.9$), the temperature effect dominates over the stoichiometry effect and NO_x emissions decrease to very low levels at ultra-lean mixtures ($\phi < 0.5$).

2.3.3. Lean-Burn — Technical Challenges

A critical challenge in realizing practical lean-burn systems is that as the A/F ratio is increased, combustion becomes unstable before NO_x and CO emissions are reduced significantly. Consequently, to be successful, sufficiently lean conditions must be achieved (equivalence ratio less than 0.5) such that stable combustion occurs with engine-out NO_x and CO emissions at the very low levels necessary for the intended applications. Over the years, the ultra-lean-burn problem has been widely studied and reported in the literature. As a result, a number of approaches to achieve ultra-lean-burn have been suggested.

Historically, lean-burn has been pursued by increasing the level of turbulence in the combustion chamber (typically by mechanical vortex generators in the intake port and/or piston). The idea is to accelerate the burn rate through turbulence (increased thermal and mass diffusion and increased flame area by flame wrinkling and stretch) and thereby extend the lean limit for stable combustion. A problem with the high turbulence approach, however, is that the initial flame kernel generated by the ignition spark can be quenched by the increased thermal diffusivity and flame stretch, resulting in misfires. Therefore, special high-energy ignition sources are typically required to generate a relatively large initial flame. Unfortunately, high-energy ignition systems tend to aggravate spark plug erosion, resulting in more frequent spark plug replacement and higher maintenance costs. Moderate lean-burn has been successfully demonstrated with high turbulence/high energy ignition concepts. However, when one approaches ultra-lean operation (which is required for near-zero engine-out NO_x emissions), partial burn and misfires are frequently encountered, resulting in excessive emissions of unburned hydrocarbons and poor thermal efficiency.

An alternative approach that has been pursued by many engine manufacturers is to use two combustion chambers. One called a torch chamber, jet cell™, or pre-chamber, contains a near-stoichiometric (or even rich) mixture that is ignited by conventional spark ignition. This pre-chamber is connected via a short passage to the other main chamber that contains the bulk, lean mixture. As a result of combustion generated pressure rise in the pre-chamber, a jet plume of hot burning gas is injected into the main chamber lean mixture. This hot jet serves as a powerful ignition source and turbulence generator, promoting fast burn of the lean bulk charge.

Prechamber systems can achieve very lean overall operation ($\phi \approx 0.5$). However, the prechamber technology has inherently higher NO_x than a homogeneous charge lean configuration. While the rich zone in the prechamber enables overall lean combustion, it is a

hot, near-stoichiometric zone that promotes NO_x formation. As a consequence, emissions from lean-burn engines with prechambers are typically no lower than 0.4 g/bhp-hr because the prechamber results in NO_x formation.

2.3.4. Hydrogen Assisted Operation Addresses the Central Challenges of Lean-burn

An effective alternative approach to accelerate the burn rate of ultra lean mixtures and thereby extend the lean operating limit is to utilize hydrogen as a supplement to conventional fossil hydrocarbon fuels. Fractional hydrogen substitution in spark ignited engines burning natural gas, liquefied petroleum gas, or gasoline has been investigated by a number of researchers^{5,6,7,8,9,10,11,12,13,14} and have been demonstrated to offer a number of advantages, primarily as a result of increased laminar flame speeds. Key advantages include;

- Operation at very lean mixtures.
- Enhanced combustion stability.
- Increased thermal efficiency.
- Potential for ultra-low NO_x emissions but increased HC emissions, depending on equivalence ratio.

⁵ Apostolescu, N., and Chiriac, R., "A Study of Hydrogen-Enriched Gasoline in a Spark Ignition Engine," SAE Paper No. 960603, in *Advances in Engine Combustion and Flow Diagnostics*, SP1157, 1996.

⁶ Rauckis, M. J., and McLean, W. J., "The Effect of Hydrogen Addition on Ignition Delays and Flame Propagation in Spark Ignition Engines," *Combustion Science and Technology*, 19, pp. 207-216, 1979.

⁷ Houseman, J., and Hoehn, F. W., "A Two-Charge Engine Concept: Hydrogen Enrichment," SAE Paper No. 741169, 1974.

⁸ Stebar, R. F., and Parks, F. B., "Emission Control with Lean Operation Using Hydrogen-Supplemented Fuel," SAE Paper No. 740187, 1974.

⁹ Lucas, G. G., and Richards, W. L., "The Hydrogen / Petrol Engine - The Means to Give Good Part Load Fuel Economy," SAE Paper No. 820315, 1982.

¹⁰ Newkirk, M. S., and Abel, J. L., "The Boston Reformed Fuel Car," SAE Paper No. 720670, 1972.

¹¹ Jamal, Y., and Wyszynski, M. L., "On-Board Generation of Hydrogen-Rich Gaseous Fuels," *International Journal of Hydrogen Energy*, 19, No. 7, pp. 557-572, 1994.

¹² Swain, M. R., Yusuf, M. J., Dulger, Z., and Swain, M. N., "The Effects of Hydrogen Addition on Natural Gas Engine Operation," 1993 SAE Transactions, Section 4, Paper No. 932775, 1993.

¹³ Timoney, D. J., and Wilson, R. P., "Use Of Supplemental Hydrogen In Spark Ignition Engines: Simulation of Impact on Performance & Emissions," ISATA Technical Paper No. 98EL016, 1998.

¹⁴ Timoney, D. J., Linna, J. R., and Wilson, R. P., "Some Measured And Simulated Effects Of Supplemental Hydrogen In A Gasoline Engine," ISATA Technical Paper No. 00ELE036, 2000.

Negative influences arise from reduced volumetric efficiency (due to displacement of air) and decreased maximum power output.

LFG engines with prechambers can achieve NO_x levels of 0.4 g/bhp-hr if the engine is operated at a relative air/fuel ratio (lambda) of 2. The lean limit for natural gas combustion with a homogeneous charge engine typically occurs at a lambda of 1.6 ($\phi \approx 0.6$), which is not lean enough for NO_x emissions to reach ultra low levels. Since the homogeneous charge BioHALO approach eliminates the hot, near stoichiometric NO_x promoting prechamber, the homogenous charge BioHALO engine can achieve lower NO_x emissions at an equivalent lambda. Based on our testing of a simulated reformat/LFG fueled engine (see Chapter 6), a lambda of 2 will achieve 0.035 g/bhp-hr (0.011 lb/MMBtu). In the future, perhaps a slightly leaner engine configuration will result in NO_x levels of 0.02 g/bhp-hr that is as low as the levels from new central station power plants equipped with BACT.

A comparison between emissions from a prechamber and homogeneous charge engine is illustrated in Figure 2-3. The addition of hydrogen allows the homogeneous charge engine to operate without misfire at lambda values up to 2.5 where NO_x is virtually eliminated. The authors' modeling results show that NO_x levels drop rapidly as the engine runs leaner. The lean operation is enabled with the addition of hydrogen. The higher flame speed of hydrogen allows the initial combustion in the cylinder to propagate faster and allows for engine operation without misfire. The authors' modeling combined with laboratory engine testing indicates that 6.75 percent of the total heat input from hydrogen allows for lean operation to a lambda of 2.




Figure 2-3. Emissions From IC Engines Vary With Air/Fuel Ratio

A critical challenge in the practical development of systems to provide hydrogen as fuel additive is supplying hydrogen. On-site storage of hydrogen is generally costly, not only the cost of hydrogen itself but also the cost of the special storage device. In addition, there exists no

pipeline distribution infrastructure for hydrogen supply to engines. Therefore, on-site production of hydrogen or a hydrogen-containing gas is considered to have the greatest potential for commercialization. However, like any other component, an on-site system for hydrogen production must meet a number of requirements to be commercially viable.

Requirements include:

- **Safety.** Components and systems need to be inherently safe and new or substitute components must not add further safety risks. Hydrogen calls for special consideration due to wide flammability limits, low net ignition energy in air, high flame speed, high heating value, and intrinsic propensity to leak.
- **Low Cost.** The reciprocating engine market is mature and very competitive. New concepts must be lower cost than competing technologies that meet the same objectives.
- **Size and Weight.** Added size and weight must be minimized. The industry is striving for higher output from smaller packages that will allow them to cut cost and lower unit prices.
- **Reliability.** Reliability is critical for keeping maintenance costs at a minimum. The average period of unit replacement for reciprocating engine generator sets falls in the 2-10 year range, and the trend is to require as many components and sub-systems as possible to last the service life of the engine without maintenance.

On-site fuel reforming using an auto-thermal reformer to produce a hydrogen-rich gaseous fuel stream has emerged as an attractive approach with a high probability of meeting these requirements. The auto-thermal reactor is an inherently simple device with no moving parts and does not require maintenance. It is easy to manufacture, uses conventional materials, and does not require close tolerance internal components. When integrated with the engine's fuel system, it would enjoy the same degree of safety as a modern fuel injection system – there is one connection to the fuel line, and the reactor outlet is ducted directly to the intake system.


2.4 Hydrogen Production and Reformers

A variety of reformer technologies have been used to convert hydrocarbons to hydrogen. These include steam reformers, partial oxidation with oxygen or air, and catalytic autothermal reforming. Steam reformers generally produce more moles of hydrogen per mole of hydrocarbon; however, they are difficult to design for small-scale applications, and the reforming catalysts are easily poisoned by sulfur, siloxanes, and other contaminants in the LFG. Catalytic autothermal reformers (ATRs), using the H₂fuel catalyst technology, are sulfur-tolerant and operate with a high hydrogen yield because of the integrated preheat of the reformer.

Autothermal reformers combine the heat effects of the partial oxidation and steam reforming reactions by feeding the fuel, water, and an oxidant such as air together into the reformer. This process is carried out in the presence of a catalyst, which controls the reaction pathways and thereby determines the relative extents of the oxidation and steam reforming reactions. The

presence of steam and the use of an appropriate catalyst provide benefits, such as lower temperature operation and greater product selectivity to favor the formation of H₂ and CO, while inhibiting the formation of coke.

The initial oxidation reaction results in heat generation and high temperatures. The heat generated from the oxidation reaction is then used to steam-reform the remaining fuel by injecting an appropriate amount of steam into this gas mixture. The oxidation step in air may be conducted with or without a catalyst. The overall autothermal reforming reaction can be expressed as:




Where χ is the oxygen-to-fuel molar ratio and y is the number of moles of CO₂ that reacts with H₂ to produce CO and H₂O due to the reverse water gas shift (WGS) reaction.

This χ ratio is a very important parameter because it determines:


- The amount of water required to convert the carbon to carbon oxides.
- The hydrogen yield (moles).
- The concentration (mol%) of hydrogen in the products.
- The heat of reaction.

This reaction is endothermic at low values of χ , and exothermic at high values of χ . At an intermediate value (χ_o), the heat of reaction is zero.


For autothermal reforming of methane, $n=1$, $m=4$, $p=0$, and the overall reaction is given by:




When $\chi = 0.5$ and $y=0$ (pure steam reforming)



If $y=0.5$, then



If $y=1$ (pure partial oxidation or "POx"), then



For each of these cases, the reformat gas has the composition given in Table 2-2.

Table 2-2. Product Gas Composition from Reformers

Reformer Products	mol %, dry, $\chi = 0.5$		
	Pure Steam Reforming $y=0$	$y=0.5$	Pure POx $y=1$
H ₂	51.0	46.5	41.0
CO	trace	9.3	20.5
CO ₂	17.0	9.3	—
N ₂	32.0	34.9	38.5
Total	100.0	100.0	100.0

Pure steam reforming ($y=0$) gives the highest H₂ yield, and pure partial oxidation reforming ($y=1$) gives the lowest. Regardless of the type of reformer, the initial product invariably contains at least a trace of carbon monoxide, i.e., $y>0$. The bulk of the CO can be converted to additional hydrogen via a separate WGS reaction that is typically done for hydrogen production systems. For the BioHALO system, the WGS can be eliminated because CO also burns with a high flame speed and helps support lean operation.

The effect of air and operating temperatures is illustrated in Figure 2-4. (For LFG, $\chi=2$ corresponds to a reformer operation stoichiometric air fuel ratio [$\lambda=1$]). At low lambda values solid carbon or coke can form and the conversion of methane is low. Higher methane conversions can be achieved by operating at a leaner condition; however as more air is added to the reformer, more CO₂ and less hydrogen are produced. An alternative is to preheat the fuel, air, and steam, which, when added to the reformer at elevated temperatures, provides higher methane conversions. The analysis shown in Figure 2-4 is for LFG.




Figure 2-4. The Maximum Conversion of LFG to H₂ + CO Occurs at a Stoichiometric Ratio of 0.38

Catalytic autothermal reforming is a steam-induced microthermal catalyzed reactive process, whereas partial oxidation reforming is a macro-thermal reactive process.

Catalytic autothermal reforming systems have a number of advantages. Use of an appropriate catalyst allows lower-temperature reforming and greater product selectivity. Other benefits include higher system efficiency, lower levels of carbon monoxide produced in the reformer, and a wider variety of construction and fabrication options. The combination of water injection and catalyst selectivity means less coke formation, a significant advantage in hydrocarbon processing.

A potential supplier of a reformer, H₂fuel, LLC, has developed a new class of catalyst materials for the autothermal reforming process. The catalyst consists of a substrate and a promoter, in which it is thought that the substrate participates in the oxidation of the carbon, while the promoter dehydrogenates the hydrocarbon. This catalytic activity has been found in various combinations of materials with certain characteristic properties needed for either the substrate or promoter.

The difficulty of converting hydrocarbons to hydrogen is that the hydrogen and oxygen bond at moderate temperatures. Under thermal equilibrium conditions, the reaction product will therefore be rich in water and poor in hydrogen. Argonne National Laboratory (ANL), H₂fuel's R&D partner, has discovered that to get a hydrogen-rich gas one would have to find a catalyst that can "dehydrogenate" the hydrocarbon molecule and then selectively oxidize the carbon chain. Thus, the catalyst must be bifunctional.

To dehydrogenate a hydrocarbon molecule, one can use metals that dissolve hydrogen such as platinum, nickel, or any Group VII metal. Nickel is the least preferred because an oxidation product thereof, NiO₄, is poisonous. To selectively oxidize the carbon chain, H₂fuel and ANL have found a source of ionic oxygen proves to be quite effective. Ionic oxygen apparently reacts with the double bonds of a dehydrogenated hydrocarbon to form oxygen-carbon bonds. Sources of ionic oxygen are oxides crystallizing in the fluorite or perovskite structure and include ZrO₂, CeO₂, Bi₂O₃, BiVO₄, LaGaO₃. By combining such oxides with a hydrogen/air mixture over it, H₂fuel and ANL discovered it is possible to obtain hydrogen-rich gas from aliphatic as well as aromatic hydrocarbons.

If, for example, ceria is the oxide ion conducting material and platinum is the hydrogen dissolving metal, a cermet containing the catalyst can be prepared using a solid-state method. The starting powder is a high surface area (about 32 m²/g) doped ceria (Ce_{0.8}Gd_{0.2}O_{1.9}) and a second phase powder is either a metal like Pt or an oxide like CO₂O₃ which is reduced in-situ in the reactor to cobalt metal with such a catalyst, the exothermic reforming reaction can be conducted in the range of 500°C to about 750°C. This is considerably lower than the 1,000°C temperatures required for steam reformers, allowing the reactor to be smaller, and the product gas to contain higher concentrations of hydrogen and less carbon monoxide.

3.0 Technical Approach

3.1 Technical Approach Based on TIAX's HALO Technology

Because of their low cost and widespread availability, the internal combustion (IC) engine has been the prime mover of choice for landfill gas to electricity projects. Unfortunately, IC engines suffer from high engine-out NO_x levels, and impurities in the landfill gas preclude the use of post-combustion catalytic reduction techniques. The only NO_x reduction technique currently available for LFG IC engines is lean-burn operation. At present, the lowest emitting LFG fired IC engines operate in lean burn-mode and are equipped with prechambers to initiate combustion; NO_x emissions range from 0.4 to 0.6 gm/bhp-hr. A 95 percent reduction in NO_x is required to meet the new distributed generation target equivalent to central station power plant emissions.

One NO_x reduction technique ideally suited to LFG applications is hydrogen assisted lean operation (HALO). Because hydrogen has wide limits of flammability, it allows combustion at ultra-fuel lean-conditions, drastically reducing NO_x emissions. HALO for natural gas-fired engines is a well-documented idea that has been studied by numerous groups, including TIAX over the past 25 years^{15,16,17,18}. Modeling and engine testing performed by TIAX for two separate commercial clients has shown that, for natural gas engines, the lean limit can be extended from a relative air/fuel ratio, lambda of 1.6 to a lambda of over 2.5 by replacing a small percentage of the natural gas with hydrogen. For lambda values greater than 2.2, the NO_x is virtually zero.

Reformation of LFG to produce hydrogen has also been investigated^{19,20}. Most of these studies have focused on the operation of fuel cells with the LFG reformat. For fuel cell applications, significant clean up of the LFG and/or the produced hydrogen is required. Sulfur, siloxane and other contaminants in the LFG adversely affect the performance of low temperature shift catalysts that are needed to achieve a high hydrogen yield. Furthermore, separating hydrogen from the reformer product stream results in a further loss in efficiency. The authors' proposed

¹⁵ "Stoichiometric Synthesis, Exhaust, and Natural-gas Combustion Engine," U.S. Patent No. 5,947,063, 1999.

¹⁶ Andretta, D., and Dibble, R. W., "An Experimental Study of Air-Reformed Natural Gas in Spark-ignited Engines," SAE Meeting Proceedings, pp. 85-93, 1996.

¹⁷ Watson, H.C., and Milkins, E. E., "Some Problems and Benefits From the Hydrogen Fueled Spark Ignition Engine," SAE Meeting Proceedings, pp. 1170-1177, 1978.

¹⁸ Proprietary R&D by TIAX, LLC, 1998-1999.

¹⁹ Anoka Landfill Gas-Fueled Molten Carbonate Fuel Cell Project, DOE/NETL Project, (FuelCell Energy, Inc.) DE-AC21-95MC31195, 1994.

²⁰ U.S. EPA in conjunction with International Fuel Cells to study fuel cell operation on landfill gas.

technology overcomes this difficulty because it requires clean up of only a fraction of the LFG and no post processing of the resulting reformat. For the BioHALO concept, both hydrogen and CO produced by the reformer enhance the lean flammability limit of the LFG.

3.2 Technical Approach

The technical approach is outlined in Figure 3-1, with the individual tasks described in detail below. The open boxes represent tasks that were completed as part of this project. The shaded boxes represent tasks that were deferred for programmatic reasons with the consent of the energy commission after extensive discussions. The reasons that certain tasks were deferred (as shown by the shaded boxes in Figure 3-1 below) were as follows: The field installation was deferred because after the project was well underway, Hess Microgen (the gas-engine supplier) withdrew following a business restructuring, and a substitute commercial partner did not step forward to provide needed matching funds. Also, a host landfill gas site was not available to assist with the field installation and to operate the landfill gas engine facility on actual landfill gas as opposed to synthetic simulated gas. Finally funding and schedule was not available to fabricate and test a real reformer, so the testing reported here was performed using bottled gas. This is the California ARB-approved method of certifying LFG engines emissions levels.




Figure 3-1. Technical Tasks Flow Chart

3.2.1. Task 2.1 — Engine/Generator Installation

As the first task, the 75-kW natural gas engine was modified by the supplier (Hess Microgen) to operate under lean-burn conditions with LFG. Following the modification, the engine was shipped and installed on-site at TIAX. After tie-ins with the LFG fuel supply line, and the

electrical load, the generator was operated for no less than six hours to establish benchmark conditions of operation.

3.2.2. Task 2.2 — Engine Scoping Tests and Modeling

Following the installation of the engine, preliminary scoping tests were performed to establish the feasibility of the BioHALO process. The objective of this task was achieved by performing tests on the engine with synthetic-reformate gas. The synthetic reformate was prepared by mixing bottled gas to the desired composition. A limited number of tests was performed to obtain data on engine operation and emissions with LFG alone and combined with the synthetic gas. The aim of this task was three fold. The first was to establish the feasibility of the BioHALO system with an LFG-fired engine. Second, preliminary emission reduction performance and the envelope of engine operating conditions were determined. Finally, based on the preliminary operating and emissions data obtained, strategies for optimal operating conditions for the engine were developed using a computer simulation model of the engine including the on-site fuel reforming reactor. The BioHALO system model was developed using GT-Suite™, the engine simulation package made available through Gamma Technologies with features including:

- Component-based models, allowing for the creation of a library of engine parts that can then be used in various engine configurations.
- Acceptance of user-defined code (i.e., sub-models), that provides maximum flexibility for modeling advanced engine technologies.
- The C-Power interface between GT-Power and Simulink™ for studying engine control strategies.
- Steady-state and transient simulation capability.
- A completely general optimizer, which allows almost unlimited combinations of input and output parameters.

The system model for BioHALO was calibrated and validated with the data acquired in the scoping tests and was extended to predict operating conditions that gave the best NO_x emission reductions with acceptable engine operation and fuel economy. Screening of BioHALO concepts benefited from several features of this engine simulation package including: (1) the ability to rapidly screen various engine configurations, (2) Simulink support for exploring control strategies, and (3) capability to simulate both steady-state and transient operation.

Efforts in this task included two subtasks. The preliminary scoping tests with synthetic reformate were performed in Subtask 2.2.1, Scoping Tests using Synthetic Reformate. The engine model development and validation was performed in Subtask 2.2.2, Engine/ Reformer Modeling and Validation.

3.2.3. Task 2.3 — Conceptual Process Optimization

The modeling results in Task 2.2 provided a map of system operating conditions versus the target goal of NO_x reduction and engine efficiency. From these results, the authors developed conceptual candidate system arrangements. Each candidate configuration included different sets of system specifications such as:

- Choice of pressurized versus atmospheric reformer.
- Air/fuel ratio of the reformer operation.
- Reformer heat recovery and preheat.
- Water shift/water recovery.
- Turn-down ratios.
- Buffer of hydrogen-rich reformat to support transients.

Next, additional engine tests were performed to screen and analyze the proposed conceptual configurations. Building on the results, recommendations for the reformer-engine arrangements were developed to guide the design of a test plan for verification engine testing. These configuration screenings and evaluations, leading to the recommended configuration, were performed in Subtask 2.3.1, Concept Optimization.

After the recommended optimal process configuration and operating strategy were identified in the concept optimization effort, the next step was to conduct a series of verification experiments on the engine at TIAX with the recommended configurations tested. The test plan for these tests was developed, and the tests performed in Subtask 2.3.2, Verification Tests Using Synthetic Reformat. As the subtask title notes, these recommended concept verification tests were performed using synthetic reformat.

Based on the results of the verification tests, the recommended process configuration and operating strategy were modified. In this sense, Subtasks 2.3.1 and 2.3.2 were iterative in nature.

3.2.4. Task 2.4 — BioHALO System Conceptual Design

This task was the logical next-step to the previous task. In this task, the BioHALO conceptual design was completed. The conceptual design served as the pre-engineering phase and developed overall system process flow diagrams (PFDs), piping and instrumentation diagrams (P&IDs), control schematics, etc. Key system specifications such as those listed below were established:

<u>LFG-Engine</u> Target A/F ratio Reformate/LFG ratio Spark timing Intake pressure Intake temperature Duty cycle	<u>Autothermal Reformer</u> Required flowrates Acceptable reformate temperature range Reformate hydrogen concentration System pressure Duty cycle
<u>Exhaust Oxidation Catalyst (if required)</u> Exhaust temperature range Exhaust flowrate Exhaust HC and CO concentrations Conversion efficiency required Durability expectations	<u>Controls</u> Type of control algorithm required Number of control command outputs and sensor inputs needed Sensor requirements Processor requirements

As part of the conceptual design, the authors also included a preliminary manufacturing cost analysis of the selected configuration.

3.2.5. Task 2.5 — BioHALO System Detailed Design

Following the development of the conceptual design and establishment of system specifications, a detailed engineering design of the BioHALO system was developed. The engineering designs produced in this task were of sufficient detail to enable execution of equipment construction and installation. Key elements of this task included the production of:

- Process layout drawings.
- System integration details.
- Equipment fabrication drawings.
- System mechanical and electrical drawings.
- Civil construction drawings.
- Control logic schematics.

3.2.6. Task 2.6 — Prototype BioHALO Reformer and Engine Interface Fabrication

In this task, the prototype BioHALO auto-thermal reformer was to be manufactured according to specifications at the H₂fuel plant. *Due to unavoidable delays in test engine commissioning and budget constraints, this task was not completed as part of this project.*

3.2.7. Task 2.7 — Prototype Testing in the Plant

Due to unavoidable delays in test engine commissioning and budget constraints, this task was not completed as part of this project.

3.2.8. Task 2.8 — Assemble BioHALO System on the In-Field Test Engine/Generator

Due to unavoidable delays in test engine commissioning and budget constraints, this task was not completed as part of this project.

3.2.9. Task 2.9 — Field Demonstration and Performance Testing

Due to unavoidable delays in test engine commissioning and budget constraints, this task was not completed as part of this project.

3.3 Process Modeling

One of the products of Task 2.2 of the referenced grant agreement is a process modeling report. The original plans for completing the effort contained in the Work Statement for this grant agreement, as documented in the TIAX proposal to the Commission that resulted in the grant agreement, were to install the demonstration engine/ generator procured for the project at the host landfill demonstration site. Once installed at the site, original plans were to complete an initial set of scoping tests to supply data to a planned process modeling and development effort. As originally planned, this initial set of scoping tests would be quite limited in nature, given that they would be performed in a field setting that constrains the number and type of process and emissions measurements that can be taken. The envelope of engine/generator operating conditions that can be tested is similarly constrained in a field setting, as is the length of time over which effective testing can be performed. Given these constraints, the originally planned project was going to rely on process modeling using the GT-Suite™ engine simulation package to define strategies for optimal operating conditions for the engine and hydrogen-producing reformer based on the limited scoping test data obtained in the in-field testing.

As the project proceeded, however, it became clear that installing and operating the demonstration engine/ generator at the landfill host demonstration site would be too time-consuming and costly to support the initial scoping tests. Thus, it was decided instead to install the engine/ generator in the engine testing facilities at the TIAX pilot plant in Cambridge, Massachusetts, and complete the initial tests in this more laboratory-like setting. Having made this decision, it became possible to more completely instrument the test engine/ generator, thereby significantly expanding the number and type of process and emissions measurements that could be made in the initial tests. Moreover, the envelope of operating conditions that could be tested was similarly significantly expanded, and the ability to complete an initial test program over a much expanded time period became possible. With this increased testing flexibility and expanded measurement capability, the need to do process modeling to define optimal operating strategies was eliminated. Instead of having to rely on computer simulation of engine and reformer operation to explore various operating configurations and parameter settings, it was now possible to obtain actual test data to confirm the effects of these configurations and parameter settings on engine operation and emissions. Thus, the test data presented and discussed in the Synthetic Reformate Scoping Test Report, submitted on October 28, 2005, was used in the BioHALO process development effort in lieu of process modeling data that was originally planned.

4.0 Results of Test Engine Installation and Commissioning at TIAX

In the initial tasks of the project, the demonstration engine/ generator was to have been installed at the host site, and an initial set of scoping tests completed to supply data to the process modeling and development effort. The authors had hoped to have scheduled the delivery of the engine/ generator to the host site during May 2003, but continuing delays in obtaining the needed data and interconnection drawings for the engine/ generator system to support the preparation of the applications for permits required for site installation significantly delayed this effort.

Once the engine/ generator had been installed and operational at the site, an initial series of scoping tests were planned as noted above. However, given continuing delays in getting the necessary air district and utility approvals to install and operate a grid connected generator at the site, it became clear that this initial set of tests would not be possible at the site for an extended period. Thus, it was decided to complete the initial tests at the engine testing facilities at the TIAX pilot plant laboratory in Cambridge, Massachusetts. The approved test plan was revised to reflect this change in initial scoping test location, and was approved by the energy commission. A timeline showing the reasons for the delays is provided in Appendix A.

The test engine/ generator was shipped to the TIAX engine laboratories in Cambridge in early October 2003, and installed in one of the TIAX test stands. TIAX staff in Cambridge subsequently completed a number of engine modifications needed to allow the planned scoping tests to take place. All these modifications were completed during August 2004, and the engine was successfully started and run for several hours using bottled natural gas fuel on September 3, 2004.

Connecting the generator to the Cambridge grid required many months due to a series of problems and setbacks. Most of the delays were associated with getting electrical installation specifications for the local grid interconnection from NSTAR, the local electric and gas utility. During April 2005 the local grid connection was complete. Specifically, the last requirement to establish the generator grid connection was to have an NSTAR representative inspect the installation and approve it. This inspection was completed in April 2005, and approval to bring the generator online was granted. Until then, the engine could only be run at idle. With NSTAR's final installation approval, the engine/generator could then be operated powering a grid load.

Additional shakedown problems were discovered and resolved while attempting to operate the engine at full load, as follows:

- Fan selection for engine cooling: Due to the installation of the shaft encoder, a substitute fan used in automotive (not stationary engine) applications was installed on the engine. During initial operation, it was found that this fan provided inadequate cooling. The original Hess

Microgen fan was reinstalled, along with a more slender version of the shaft encoder which fit around the fan.

- Lube oil overheating: The turbocharger that was installed was providing just enough additional heat to the lube oil that standard cooling was not sufficient. An oil/air heat exchanger was installed to solve the lube oil overheating problem.
- The turbocharger outlet was installed incorrectly by an outside vendor. To correct this vendor mistake, the exhaust piping plumbing was modified to allow the wastegate to fully open.
- The exhaust piping was installed (by the outside vendor) very close to the engine coolant lines without adequate shielding, so appropriate shielding was added.
- One of the cylinder's spark drivers was found to be damaged; this was replaced, along with some coils.
- A replacement flue with a higher temperature rating was installed in the side of the engine laboratory building.

With all these problems resolved, continuous operation of the engine/generator at rated power became possible. The completion of Task 2.1 required operating the engine and verifying acceptable operation for at least six hours. Seven hours of successful operation were completed on May 4, 2005, thereby completing Task 2.1 of the project. Figures 4-1 and 4-2 illustrate the engine operating condition data for this initial engine/ generator operating period. These figures indicate that most of the initial operation was conducted at full engine/ generator load, although operation at 25%, 35%, and 20% load was also established. Figures 4-3, 4-4, and 4-5 show various illustrations of the synthetic landfill-gas mixing system. Also shown are the right and left sides of the installed engine/ generator in the TIAX Cambridge engine laboratory.

**Bio-HALO Task 2.1 Initial Shakedown Run, Spark Timing 25 degrees BTDC,
90°C Coolant, 100°C lube oil, Wastegate Fully Open**




Figure 4-1. Engine exhaust temperature and load for the initial engine/generator operating period

**Bio-HALO Task 2.1 Initial Shakedown Run, Spark Timing 25 degrees BTDC,
90°C Coolant, 100°C lube oil, Wastegate Fully Open**




Figure 4-2. Generator electrical power output for the initial engine/generator operating period




Figure 4-3. View of the synthetic landfill gas mixing system

Photo Credit: TIAX LLC



Figure 4-4. View of the right side of the test engine/generator

Photo Credit: TIAX LLC




Figure 4-5. View of the left side of the engine/generator showing the oil cooler installed

Photo Credit: TIAX LLC

The authors began preparing a detailed schedule for completing the engine/ generator installation, and completing the initial scoping tests and subsequent verification tests during September 2004.

5.0 Results of BioHALO Scoping Tests (Task 2.2)

5.1 Summary of Scoping Test Results

Task 2.2 of the project consisted of scoping tests using synthetic reformat on an instrumented 75 kW landfill gas engine at the TIAX engine test laboratory. In this initial phase of the development effort, engine operation and emissions performance data needed to be developed with the eventual demonstration engine/ generator fueled with synthetic LFG combined with synthetic reformat having a composition similar to that expected to be produced by the eventual ATR placed at the site. Using a mixture of 57% natural gas, 23% CO₂, and 22% N₂ as the synthetic reformat, the leanest point the baseline engine could be operated was 4.2% O₂ in the exhaust, after which the combustion stability deteriorated. At this point, the engine-out humidity corrected NO_x was 440 ppm, which corresponds to 1.8 g/ihp-hr NO_x (2.2 g/bhp-hr NO_x).

The next set of tests were designed to determine the effect of adding synthetic reformat, which was 52% H₂ and 48% CO. Adding this synthetic reformat mixture allowed the engine to have stable combustion out to ~8% O₂ in the exhaust at a minimum addition rate of 6% H₂/CH₄ (on a LHV basis). Addition of further hydrogen increased the combustion stability marginally, but it still did not allow the engine operating limit to be extended beyond 8% O₂ in the exhaust. At this operating condition, humidity corrected NO_x was 20 ppm, which corresponds to 0.12 g/ihp-hr NO_x (0.15 g/bhp-hr), a reduction of over 93% compared to the baseline case.

This represented a significant reduction over the best LFG fired lean-burn prechamber engines, whose levels are 0.4 g/bhp-hr, but still did not meet the proposal target of 0.032 g/bhp-hr NO_x. Because a 93% reduction in engine-out NO_x had been demonstrated and that concurrent TIAX research had shown the ability to go beyond the perceived stability barrier at 8% exhaust O₂, it was recommended that further scoping be completed to reach the 0.032 g/bhp-hr goal. TIAX recommended testing (based upon highest probability of success) of an in-line turbulent mixer first to see if the stability barrier could be broken. If this improved the lean limit, but there was still not enough NO_x reduction, EGR, water injection, a high energy ignition system, and finally a combination of all of these were recommended to be attempted. It is believed that a combination of these methods would reduce the NO_x to the desired goal if the turbulent mixer does not extend the lean limit to the desired degree. (Note: These additional tests were successfully carried out in Task 2.3, and the results are provided in Section 6.3 below)

5.2 Scoping Test Program Overview

5.2.1. Rationale for Testing

These initial scoping tests were needed for two reasons. The first was to establish the feasibility of the BioHALO process with an LFG-fueled engine. Second, preliminary emission reduction performance and the envelope of engine operating conditions were determined.

5.2.2. Test Objectives

The objective of these initial scoping tests with synthetic reformat was to establish the performance and emissions of the engine over an operational envelope and to establish the operational limits of the engine with and without reformat addition to the LFG fuel. The performance and operational data developed in these tests was to be used as the design basis for the emission reduction technology that was to be demonstrated at the landfill site. Tests were performed to benchmark the engine operating on LFG alone, and then those tests were repeated with synthetic reformat (H_2 and CO) added to the LFG fuel.

5.3 Engine Description

The test engine/ generator was a Hess Microgen generator set comprised of a Ford Power Products Model WSG-1068 V10 engine powering an induction generator with switchgear allowing interconnection to the grid. According to the project plan, it was intended that this engine eventually be installed at a landfill site and grid connected in parallel with the site electrical load. The engine was a 6.8 L natural gas-fueled engine rated at 78 kW (105 hp) at 1,800 rpm using natural gas. It was modified to allow for the full range of scoping testing by the addition of an aftermarket Engine Control Unit (ECU) as well as addition of Ford 1998 MY Crown Victoria CNG fuel injectors. A photograph of the ECU and controls hardware is provided in Figure 5-1. In the figure the ECU is the gold-colored box in the upper right hand corner of the photograph. For these tests, the ECU was connected to a laptop computer, which allowed the on-line adjustment of spark timing, fuel injection timing, and other engine control parameters.




Figure 5-1. Engine Control Hardware
Photo Credit: TIAX LLC

A turbocharger was installed on the engine to allow boosting during the lean operation of the engine to ensure adequate power output. The turbocharger was waste-gated, which allows the

boost pressure to be controlled via a valve that allows a controllable quantity of exhaust gases to bypass the turbine. Specifications for the engine are given in Table 5-1.

Table 5-1. Ford Power Products WSG-1068 Specifications

Specification	
Engine type	V10
Bore and Stroke, mm (in)	90.2 x 105.8 (3.55 x 4.17)
Displacement, L (CID)	6.8 (415)
Compression ratio	9:1
Net weight, kg (lb)	290 (640)
Ignition system	Coil on Plug
Rating on NG	78 kW (105 HP) @ 1800 RPM

This specific power engine was chosen from among the Hess Microgen offerings for two main reasons. First, its power output closely matched the desired power output of 70-80 kW for the project (as specified in the TIAX proposal that resulted in this Grant Agreement). Second, this engine was a gasoline engine converted to natural gas operation instead of being a converted diesel engine. Being an original gasoline engine design, the in-cylinder air flow is less turbulent than that for a typical diesel design. This will reduce the tendency for early flame quenching, which can limit the lean ignitability of a lean mixture using a spark ignition system.

A photograph of the engine and generator is shown in Figure 5-2.



Figure 5-2. Side View of Engine/Generator
Photo Credit: TIAX LLC

5.4 Test Plan

5.4.1. Test Procedures

This scoping test program was performed in the TIAX engine laboratory facilities in Cambridge. The engine/ generator, after retrofitting with a turbocharger, was shipped to the TIAX engine laboratory and connected to the local Cambridge grid after installing new protective relaying and obtaining a new cogeneration permit. The engine fuel for all tests was synthetic LFG prepared by mixing nitrogen and carbon dioxide with bottled natural gas fuel to a composition that simulates the diluted fuel present in typical landfill gas. This composition is given in Table 5-2. The heating value of the synthetic LFG blend was 550 BTU/ft³, which is at the high end of the range for LFG fuels. Oxygen, present in landfill gas in very small concentrations, was not used in preparing the synthetic LFG. The N₂ and CO₂ for preparing the synthetic LFG was supplied from liquid N₂ and CO₂ dewars in the engine laboratory. The liquid gases were evaporated, brought to ambient temperature, and metered at appropriate flowrates into the engine to form the synthetic LFG.

A photograph of the LFG mixing system is shown below in Figure 5-3. The mass flow meters are shown in the right of the photograph; these allow measurement of the flow rates of the CO₂ and N₂. The actual flowrates of the gases were controlled via a needle valve before being

metered into the engine. The three panels in the middle of the photograph are the regulators and switchover systems for the gases, and the dewars may be seen behind the regulator rack.



Figure 5-3. Synthetic LFG Mixing System with Mass Flow Meters

Photo Credit: TIAX LLC

A schematic of the BioHALO experimental setup is included in Figure 5-4.




Figure 5-4. BioHALO Schematic.

The goal of the reformat mixing was not to duplicate a specific landfill gas composition, but provide a representative dilute fuel mixture to the engine to adequately determine performance of the BioHALO system.

Table 5-2. Average Synthetic LFG Composition Ranges Over Test Matrix

Component	Concentration, %vol dry
Natural Gas	57 ± 3
CO ₂	21 ± 2
N ₂	22 ± 2
Heating Value	550 BTU/ft ³

The natural gas used during testing was supplied in 2200 cubic feet six packs of bottled gas. The composition of the natural gas is given in Table 5-3.

Table 5-3. Natural Gas Composition

Component	Concentration	Component	Concentration
Methane	93 %	Ethane	2.4 %
N ₂	3 %	Propane	0.5 %
CO	1 %	N-Butane	0.1 %

Table 5-4 provides a summary of the matrix of the scoping test conditions. The following paragraphs provide discussion of this test matrix.

Table 5-4. Test Matrix

Test Set	Description
1	Baseline Test using LFG. Engine operating at rated speed of 1,800 rpm with fixed generator load at engine wide open throttle, standard spark timing
2	Air/fuel Ratio Scoping using LFG. Engine operating at rated speed of 1,800 rpm. Vary exhaust O ₂ from 4% to the lean limit of stable operation in 2% increments. Maintain IMEP at the same level as the baseline test.
3	Synthetic Reformate Testing using LFG and Reformate. Engine operating at rated speed of 1,800 RPM. Vary reformate addition rate from 2% of the LHV of the engine fuel to 10% of the LHV in 2% LHV increments. At each addition rate, vary exhaust O ₂ from 4% to the lean limit of stable combustion in 2% increments. Maintain IMEP at the same level as the baseline test.

Test Set 1 was carried out to establish the baseline for the engine at the rated standard design operating conditions using LFG. This test data provided insight into the allowable combustion stability criteria for the engine. The baseline operating condition for this particular engine corresponded to air/fuel ratio of 1.15, very close to stoichiometric (15% excess air). Specifically, the objective of the BioHALO process is to maintain or improve the combustion stability of the engine compared to baseline engine operation. This baseline engine operating condition was repeated at the beginning of each test day to ensure the integrity and consistency of the experimental setup, instrumentation, and engine performance.

Test Set 2 defined the lean limit of stable combustion in the standard engine configuration using LFG. In this set, the exhaust O₂ was varied from 4% to the lean stability limit in increments of 2% O₂. The engine indicated mean effective pressure (IMEP) was kept constant (within the accuracy of the experimental configuration) at the level for the baseline test by varying the discharge pressure of the turbocharger. Because combustion phasing affects engine NO_x production, fixed combustion phasing, as determined by the location (crank angle) of peak cylinder pressure, was employed to normalize the test data. Exhaust O₂ concentration was used as the test variable to avoid confusion regarding the definition of relative air/fuel ratio when hydrogen is added to the ingested mixture.

Test Set 3 established the extent that the lean limit of combustion can be extended by adding hydrogen rich reformat to the engine's LFG fuel. Reformat addition rate was varied from a value corresponding to a H₂ flow of 2% of the lower heating value (LHV) of the fuel feed to the engine (LFG/ reformat mixture) to 10% of the fuel LHV. At each reformat addition rate, the excess air supplied to the engine was increased incrementally using the turbocharger. Thus engine exhaust O₂ was increased systematically to a point where combustion was no longer stable. Previous modeling showed that adding reformat at 6.75% of the fuel LHV is near the optimum condition for NO_x emissions reduction at acceptable engine operation. This condition was bracketed by sweeping from 2% to 10% in logical increments. Similar to Test Set 2, IMEP was kept fixed at the level for the baseline test by varying the discharge pressure of the turbocharger. Also similar to Test Set 2, fixed combustion cylinder peak pressure phasing was employed to normalize the test data.

The composition of the synthetic reformat is given in Table 5-5 and compared to an actual reformer output. This composition is that predicted by Unitel as being the output of its autothermal reformer when fed by LFG with the composition given in Table 5-2. As noted above, the synthetic reformat was prepared to the composition given in Table 5-5 by mixing bottled gases.

Table 5-5. Synthetic Reformate Composition from Reformer

Component	Actual Unitel Reformer Output Concentration, %vol	Reformate Composition Used in the Testing Reported Here, % vol
H ₂	14.1	52
CO	13.2	48
CO ₂	9.6	Omitted because simple diluents
N ₂	46.8	
H ₂ O	16.3	

For reference, a photograph of the reformate injection system is shown in Figure 5-5. The air intake is the large black tube that runs diagonally across the photograph. Synthetic reformate was injected into the engine prior to the compressor as shown. For this phase of testing, only pre-turbocharger injection was done.




Figure 5-5. Photograph of the Reformate Injection System
Photo Credit: TIAX LLC

The actual reformate mixture injected into the engine was composed only of the fuel components of the reformate, as these are the only components that will extend the stable operating limit of the engine. The CO₂, H₂O, and N₂ normally present in the Unitel reformer output simply dilute the mixture. The resulting in-cylinder mole fractions of CO₂, H₂O and N₂

were not significantly impacted. This was done to maximize testing effectiveness for gas consumption as well as for experimental convenience.

5.4.2. Test Measurements

The engine operating parameters that were measured for each test, along with the instrumentation used to measure these, are listed in Table 5-6. The output from each measurement instrument was recorded in data acquisition computers. The cylinder pressure was recorded with high-speed equipment with 1 degree crank angle resolution, while the other parameters listed in Table 5-5 were recorded at a maximum of 1 Hz, as this was all the resolution that was necessary. “Adapt CAS,” a commercially available heat release and engine combustion analysis software, allowed tracking the variation of cylinder pressure with engine crank angle for each cycle and calculating the IMEP for each cycle based on these data. The software also performed statistical analyses to calculate the coefficient of variance (COV) of the IMEP and the lowest normalized value (LNV) of the IMEP over a number of engine cycles. These measures were used to identify when engine combustion began to become unstable as the lean limit of combustion was approached. The software also identified the location (crank angle) of the peak cylinder pressure, the location of the 50% combustion completeness point, and the crank angle range of 10 to 90% combustion completeness. These were also indicators of combustion stability or incipient instability.

Table 5-6. Measured Engine Operating Parameters

Parameter	Measurement Method
Cylinder pressure versus time	Kistler 6117 Spark Plug/Transducer
Engine crank angle versus time	BEI HS35 Shaft encoder
Manifold air pressure (MAP)	Delco boost pressure transducer
Engine speed	BEI HS35 Shaft encoder
Engine power output	Measured using Hess monitoring software
Generator power output	Hess monitoring software
Turbocharger intake temperature	Thermocouple in tap in engine intake
Manifold charge temperature	Thermocouple in tap in intake manifold
Exhaust temperatures	Thermocouples in tap in engine exhaust
LFG fuel flowrate	Omega Industrial Rotameter
Reformate flowrate	Mass flow meter in reformate feed line
Combustion air flowrate	SuperFlow flow turbine in air intake
Exhaust O ₂ concentration	Horiba MEXA 7500D

For all tests, engine exhaust concentrations of CO₂, CO, NO_x, and total hydrocarbon (THC) were also continuously monitored in addition to the oxygen concentration. The engine test facility at the TIAX Cambridge laboratories is equipped with a Horiba MEXA 7500 dual channel continuous emission monitoring system that was used to continuously monitor engine exhaust.

This system includes a paramagnetic O₂ analyzer, non-dispersive infrared (NDIR) CO and CO₂ monitors, a heated chemiluminescence NO_x monitor, and a flame ionization detector (FID) THC monitor. Special care was taken when calibrating the O₂ analyzer. A 16% O₂ concentration was used to calibrate the O₂ analyzer so that the lean operating conditions could be adequately captured.

Mass flowmeters, pressure transducers, and thermocouples were calibrated before installation on the engine and held calibration throughout the project. Before testing began, linearization of the Horiba Continuous Emission Monitors (CEM) was done to ensure measurement accuracy down to the lowest levels of desired measurements. The CEMs were calibrated using zero and span gas at the beginning and end of each test day. Zero and span drift were calculated and compared to reference method specifications.

Ambient temperature, barometric pressure, and relative humidity were recorded hourly during each test day. These measurements were used to correct all affected engine operating parameters including indicated torque, indicated power, IMEP, specific fuel consumption, and fuel conversion efficiency.

5.4.3. Data Analysis Procedures

The TIAX heat release and engine combustion analysis software was used to analyze test data obtained. In addition to the IMEP and combustion completion calculations generated by the Adapt CAS system discussed above, this software allowed calculating, evaluating, and plotting a variety of engine operation and emissions parameters such as relative air/fuel ratio (λ) without hydrogen introduction, specific fuel consumption (g/kWh, dry basis), specific emissions (g/kWh, dry basis), the in-cylinder burn rate, the indicated fuel conversion efficiency, and the volumetric efficiency. Of particular importance for Task 2.3 were the NO_x measurements and the instruments were calibrated for ultra-low NO_x (0-10 ppm). Because IMEP is a measure of normalized engine torque, the engine power output and fuel conversion efficiency are reported as indicated values (i.e., based on measured in-cylinder pressure, not on engine net brake torque).

5.4.4. Quality Assurance Procedures Followed

During test setup and engine testing, a bound laboratory notebook was kept. In this notebook each test's setup was documented using photographs, technical drawings, and text that describes the setup with sufficient completeness that a given test could be duplicated in the future. During testing, daily entries were made that described each test's objective and each test's observations with time stamps associated with each observation. Any abnormal or unexpected events were also noted, with possible explanations and expected effects on the test data or the achievement of test objectives.

In any experimental program there will always be test-to-test variations in the measurement results obtained from repeated tests at the same test conditions. Naturally, it is preferable to minimize this variability. In well-controlled laboratory engine test facilities, it is usually possible to achieve test-to-test repeatability of key performance parameters to within 1%. Nevertheless, it is important to measure the day-to-day variability in key performance

parameters over time and use these measurements as a quality check threshold to verify the integrity and consistency of the engine setup and the testing hardware and instrumentation. To this end, the baseline test (Test 1) was performed at the beginning of each test day, as noted above. The combustion stability for this condition, as determined by COV and the LNV of the IMEP, was compared to that for previous test days. If the difference exceeded the quality check threshold, a cause for the difference was sought and corrective action taken. The initial quality check threshold was 3% difference.

The Cambridge office of TIAX is ISO 9001 certified, and certification of the Cupertino office is underway. The TIAX ISO 9001 laboratory and testing procedures with regard to data acquisition, storage, backup, and evaluation were followed throughout the testing.

5.5 Test Results and Discussion

The test plan for Task 2.2 was successfully followed and completed, and the results are presented below. All data shown is an average over 500 engine cycles (i.e., 500 sequences of intake, compression, combustion, expansion, and exhaust for all 10 cylinders). The baseline test results (Test Set 1) are summarized in Table 5-7 below:

Table 5-7. Baseline Test Results Summary

Parameter	Result
Engine IMEP (bar)	8.3
LFG (% Natural Gas, % N ₂ , % CO ₂) composition	57± 3, 21 ± 1, 22± 2
Location of Peak Pressure (deg ATDC)	20
IMEP COV (%)	1
IMEP LNV (%)	96
Spark Timing (deg BTDC)	25 deg BTDC
Average Exhaust Temperature (°C)	512
Exhaust O ₂ Concentration (%)	2.5
Calculated Relative Air/Fuel Ratio (-)	1.14
Engine Out humidity-corrected NOx (ppm)	2722
Engine Out humidity-corrected NOx (g/bhp-hr)	12

Table 5-8 shows the results of the stability scoping without the addition of synthetic reformat (Test Set 2).

Table 5-8. Stability Scoping Testing Summary—No Reformat

Parameter	Test Point 1	Test Point 2	Test Point 3
Engine IMEP (bar)	8.3	7.9	7.9
LFG (% Natural Gas, % N ₂ , % CO ₂) Average Composition	57± 3, 21 ± 1, 22± 2		

Parameter	Test Point 1	Test Point 2	Test Point 3
Location of Peak Pressure (deg BTDC)	20	24	18
IMEP COV (%)	1	5	15
IMEP LNV (%)	96	83	-2
Exhaust O ₂ Concentration (%)	2.5	4.2	5.5
Calculated Relative Air/Fuel Ratio*	1.14	1.24	1.31
Engine-out humidity-corrected NO _x (ppm)	2722	298	436
Engine out humidity-corrected NO _x (g/bhp-hr)	12	1.53	2.2

*see Appendix A, Air/Fuel Ratio Calculations

Combustion stability drops off very quickly as the air/fuel ratio is increased beyond 1.24 (24% excess air). For discriminating between stable and unstable combustion, a threshold of 10% COV and/or 75% LNV is typically used, so Test Point 3 would not be acceptable for power production. The excess air at this point, however, does lower the in-cylinder temperatures and thus the thermal NO_x production. The volume concentration of NO_x for the final point is higher than Test Point 2 even though the exhaust O₂ concentration is higher because of the poor combustion that occurred during Test Point 3 (evidenced by the high IMEP COV and low IMEP LNV).

5.5.1. LFG/Reformate Test Results

For these scoping tests, manual adjustments were made to regulate engine operation conditions (engine load and boost, fueling rate) as well as synthetic reformate composition. According to the program plan, electronic closed-loop controls of these parameters would be employed later in the demonstration phase of the program. The manual adjustment process involved an iterative process. First, the engine was brought to the lean operating condition near Test Point 3 in Table 5-8 using LFG alone, which caused poor combustion stability and low engine power output. Then, a predetermined fixed concentration (based upon an initial fuel flow measurement) of the simulated reformate composed of hydrogen and carbon monoxide was slowly added to the engine. This addition of the hydrogen caused the engine combustion to stabilize and the engine power output to increase. Following that, the desired IMEP and exhaust O₂ concentration was obtained by adjusting the fuel mixture and wastegate position to control the boost of the turbocharger. The manual adjustment nature of this process accounted for the minor variabilities between test points. IMEP was held close to 8 bar in all tests, with lower IMEPs occurring where there was significant combustion instability.

Figure 5-6 is a plot of all the data taken for the LFG/Reformate scoping tests. As may be seen from the graph, the NO_x drops dramatically with the increase in excess air (as expected for the thermal NO_x mechanism). The exhaust percentile O₂% is used as the abscissa to avoid any possible confusion of the definition of air/fuel ratio once hydrogen is introduced. The ordinate is shown on a logarithmic scale to because of the large range of values. The lowest values obtained were 4 to 10 ppm humidity corrected NO_x, corresponding to 0.03 to 0.06 g/ihp-hr (0.06

to 0.08 g/bhp-hr) NOx emissions. However, combustion stability and power output were not acceptable at these points, as will be shown shortly.




Figure 5-6. NOx Emissions as a Function of O₂ in the Exhaust

Figure 5-6 shows an overall view of the NOx reduction potential of the running the engine at ultra-lean operating conditions. However, more insight may be gained by focusing on the leanest conditions (6% exhaust O₂ or greater) that produce the lowest NOx emissions. This view is shown in Figure 5-7, where values below 160 ppm are shown. Figure 5-9 shows the same NOx results with ppm now in g/bhp-hr. Significant reductions in NOx are shown, with over 99% reduction being accomplished (2450 to below 24 ppm) over the leanest baseline condition. This point is achieved using a reformat addition level of 10% LHV H₂/CH₄. However, even though the NOx at this point is quite low, the combustion stability was not acceptable. This may be seen from Figures 5-8 and 5-9 and the discussion that follows.




Figure 5-7. NO_x as a Function of O₂, with Reformate Levels Identified




Figure 5-8. NO_x as a Function of O₂, with Reformate Levels Identified in g/bhp-hr




Figure 5-9. IMEP COV as a Function of Exhaust O₂ Concentration

Even with hydrogen addition up to the levels tested here, the lean stability limit is reached at or close to 8% exhaust O₂ (which roughly corresponds to a relative air-to-fuel ratio of 1.6). At even leaner operation (O₂ > 8%), the combustion stability no longer can be held at acceptable levels, even with the addition of additional hydrogen up to the level tested here. This same point may be seen in Figure 5-10, which shows the IMEP LNV.




Figure 5-10. IMEP LNV as a Function of Exhaust O₂ Concentration

Applying the filter on the data of a maximum of 10% IMEP COV, the points shown in Figure 5-11 are allowed:




Figure 5-11. NO_x as a Function of Exhaust O₂, Data Points Where IMEP COV Was Less Than 10%

The data in Figures 5-11 and 5-12 indicate that humidity corrected NO_x emissions levels of 20 ppm (corresponding to 0.12 g/iHP-hr NO_x, or 0.15 g/bHP-hr) can be achieved by adding reformat at a level of 6% or higher and operating the engine ultra lean (7.5% to 8% oxygen in the exhaust). Compared to baseline engine operation, this corresponds to >98% reduction in engine out NO_x (see test point 1 in Table 5-8) on a g/bHP-hr basis.




Figure 5-12. NO_x as a Function of Exhaust O₂, Data Points Where IMEP COV Was Less Than 10%

5.6 Conclusions and Recommendations From Scoping Tests

This series of scoping tests had shown the ability to achieve a significant 93% reduction in the NO_x emissions levels using reformat, when compared to the NO_x at the leanest operating condition without reformat addition. However, the project target of 0.032 g/bhp-hr NO_x (sub 10 ppm) was not met, and reaching this target would require an additional 75% NO_x reduction. In the tests so far, the lean limit of operation reached was 8% O₂, and the engine would not run at acceptable COV at the lean conditions (beyond 8% O₂ in the exhaust) needed to reach the sub 10 ppm NO_x level. Even though the mixture at the best test point was highly dilute due to the presence of N₂ and CO₂ from the synthetic LFG, this dilution is not sufficient to reduce the NO_x levels down to the sub-10 ppm level.

In forming a recommendation, the authors noted that achieving an additional 75% NO_x reduction is actually not that challenging because of the exponential dependence of NO_x formation rate on flame temperature. The rule of thumb is each 20°C drop in flame temperature produces a 50% drop in NO_x formation (rate). In other words, engine operation was within feasible striking distance, and all that was needed was a practical means to achieve a flame temperature suppression of about 40°C on average. Four alternatives were examined as explained below, and some of these appeared feasible to pursue and promising.

The first alternative examined was whether cylinder-to-cylinder mixture differences or even unmixed pockets within a cylinder were preventing very lean operation. Such pockets can produce high NO_x as is well documented. If this is the case then simply making a homogeneous air-fuel mixture can lower the NO_x dramatically. In a separate study on hydrogen supplementation of natural gas engines, TIAX was able (with hydrogen supplementation) to extend the operating limit beyond 8% exhaust O₂. This is shown in Figure 5-13. As may be seen, with 10% hydrogen supplementation, the engine could stably operate at exhaust oxygen

concentrations of 9.5%. The constituents entering the cylinder for the results shown in the figure were natural gas, hydrogen, and air.




Figure 5-13. Data from TIAX Hydrogen Supplemented NG Engine Work²¹

Comparing Figure 5-13 (HALO) to the comparable shown in Figure 5-9 (BioHALO) suggests that in the BioHALO project, the cylinder constituents of natural gas, hydrogen, carbon monoxide, nitrogen, carbon dioxide, and air *had not been homogeneously mixed*. Therefore it was seen to be possible to obtain stable combustion beyond 8% exhaust O₂ with LFG fuel, and thus lower NO_x. The logical next step would be to ensure cylinder charge uniformity by using an in-line turbulent mixer.

Additional methods to aid in reducing NO_x include:

- **Further extension of the lean limit with greater hydrogen supplementation.** The addition of more hydrogen could increase the probability of mixture ignitability. Greater than 10% of the fuel LHV would be required. (Of course, here there is a practical constraint with a reformer being able to produce a sufficiently concentrated hydrogen-containing reformat).
- **Increase in ignition energy supplied.** The tests so far were run with the standard stoichiometric engine ignition system as supplied by Hess Microgen. Lean burn engines typically have higher energy ignition systems than the one supplied with the engine used in this testing. Under hydrogen supplementation at ultra-lean conditions, there is an ignitability limit in the mixture that a *high energy ignition system could possibly overcome, thus reducing NO_x*.

²¹ Smutzer, Chad. *Application of Hydrogen Assisted Lean Operation to Natural Gas-Fueled Reciprocating Engines (HALO)* DOE Final Scientific/Technical Report. January 2006.

- ***Swirl/Tumble Modification.*** This would affect the behavior of the constituents in the combustion chamber, allowing the fuel and air to mix at the spark plug more easily at leaner conditions and thereby reduce NO_x.
- ***Exhaust Gas Recirculation (EGR).*** Exhaust Gas Recirculation has the effect of *reducing the peak in-cylinder temperatures and thus reducing NO_x* by the addition of the high specific heat components of exhaust gas.
- ***Water Spray.*** Water sprayed into the cylinder either directly or as another component of the intake air has a similar effect to that of EGR, *reducing flame temperatures and NO_x emissions.*

Since a 93% reduction in engine-out NO_x had been demonstrated and that concurrent TIAX research has shown the ability to go beyond the perceived stability barrier at 8% exhaust O₂, *it was recommended that further scoping tests be completed to attempt reach the 0.032 g/bhp-hr goal.* TIAX recommended testing various measures in the order of expected probability of impact on NO_x, as follows:

First an in-line turbulent mixer would be installed to see if the stability lean limit barrier could be broken. If this improved the lean limit, but there was still not enough reduction, then *EGR, water injection, a high energy ignition system in that order would be tested.* These are all relatively low-cost tests.

Finally testing a combination of all of these was recommended. It was believed that a combination of these methods will reduce the NO_x to the desired goal if the turbulent mixer did not extend the lean limit to the desired degree.

6.0 Results of Conceptual BioHALO Process Optimization

6.1 Task 2.3 Summary

Based upon the recommendations from the Task 2.2 test report, a series of tests was conducted in Task 2.3, which was successful in improving the emissions performance of the engine. A modified intake system with improved mixing, improved air delivery, higher hydrogen supplementation, EGR, and water injection were all tried in a series of tests. The best points achieved ranged from 0.035 to 0.047 g/bhp-hr NO_x (15% O₂ corrected) with acceptable combustion stability. These points were achieved separately with better mixing, higher hydrogen supplementation, and EGR. However, emissions levels were still slightly above the proposed goals. Following is a list of the conclusions and recommendations from this round of testing:

- The improved mixing provided by the intake redesign proved effective in improving the engine performance.
- The ignition system, when switched to high-energy options, did not show a particular improvement in performance or emissions. Of some concern with the higher energy ignition, is that even though the ignition was achieved of the mixture, the burn times are slightly longer than desirable.
- Water injection was interesting that it allowed for lower NO_x emissions when compared to a standard point of similar dilution, but did not improve the emissions to the point beyond emissions targets.
- Because this was a test plan designed to encompass a range of operating conditions, each point was operated for a short duration to finish all of the testing required in the amount of time. To prove the value of the system, it would be desirable to run for a longer period.
- Although targets were not quite met, the results show an impressive emissions reduction from the baseline reciprocating engine technology, resulting in lower *engine-out* emissions than post-aftertreatment for a comparable natural gas-fueled engine.

6.2 Task 2.3 Approach

The best results from Task 2.2 represented a significant reduction over the best LFG fired lean-burn prechamber engines, whose levels are 0.4 g/bhp-hr but still did not meet the proposal target of 0.032 g/bhp-hr NO_x. Because a 93% reduction in engine-out NO_x had been demonstrated and that concurrent TIAX research has shown the ability to go beyond the perceived stability barrier at 8% exhaust O₂, it was recommended that further scoping tests to be completed in Task 2.3 to reach the 0.032 g/bhp-hr goal. TIAX recommended testing (based

upon highest probability of success) of an in-line turbulent mixer first to see if the stability barrier may be broken coupled with increased hydrogen supplementation. If this improved the lean limit, but there was still not enough reduction, EGR, water injection, a high energy ignition system, and finally a combination of all of these were recommended to be attempted. It was believed that a combination of these methods would reduce the NO_x to the desired goal if the turbulent mixer did not extend the lean limit to the desired degree.

6.3 Task 2.3 Test Program Overview

6.3.1. Engine Description

As in Task 2.2, the test engine/ generator was the same Hess Microgen generator set is composed of a Ford Power Products Model WSG-1068 V10 engine powering a 78 kW induction generator with switchgear allowing interconnection to the grid. The engine was a 6.8 L natural gas-fueled engine rated at 78 kW (105 hp) at 1,800 rpm. It was modified to fire synthetic landfill gas fuel and retrofitted with a turbocharger and intercooler. Specifications for the engine are given in Table 6-1.

Table 6-1. Ford Power Products WSG-1068 Specifications

Specification	
Engine type	V10
Bore and Stroke, mm (in)	90.2 x 105.8 (3.55 x 4.17)
Displacement, L (CID)	6.8 (415)
Compression ratio	9:1
Net weight, kg (lb)	290 (640)
Ignition system	Coil on Plug

This engine was chosen from among the Hess Microgen offerings for two main reasons. First, its power output closely matches the desired power output for the project as specified in the TIAX proposal that resulted in this grant agreement. Second, this engine is a gasoline engine converted to natural gas operation instead of being a converted diesel engine. Being an original gasoline engine design, the in-cylinder air flow will be less turbulent than that for a typical diesel design. This will reduce the likelihood of early flame quenching, which can limit the lean ignitability capability of a spark ignition system.

6.3.2. Task 2.3 Test Objectives

The objective of these Task 2.3 Process Optimization tests with synthetic reformat was to establish the optimum NO_x emissions of the engine over an operational envelope, and to establish the operational limits of the engine with and without reformat addition to the LFG fuel. This set of tests had the objective of decreasing the NO_x emissions further to meet BACT goals.

6.4 Task 2.3 Test Plan Description

6.4.1. Test Procedures

This test program for process optimization was performed in the engine laboratory facilities of TIAX in Cambridge. The engine/ generator, after retrofitting with a turbocharger, was located at the TIAX engine laboratory and connected to the local Cambridge grid under the existing TIAX cogeneration permit. The engine fuel for all tests was synthetic LFG prepared by mixing nitrogen and carbon dioxide with the natural gas fuel available. This composition is given in Table 6-2. Oxygen, present in some landfills at only 0.5% concentration, was not considered in preparing the synthetic LFG. The N₂ and CO₂ for preparing the synthetic LFG were supplied from liquid N₂ and CO₂ dewars in the engine laboratory. The liquid gases were evaporated, brought to ambient temperature, and metered at appropriate flowrates into the natural gas fuel supply to form the synthetic LFG.

Table 6-2. Average Synthetic LFG Composition Ranges Over Test Matrix

Component	Concentration, %vol dry
Natural Gas	57 ± 3
CO ₂	21 ± 2
N ₂	22 ± 2
Heating Value	550 BTU/ft ³

Table 6-3 provides a summary of the matrix of the performed process optimization tests. The following paragraphs discuss this test matrix.

Table 6-3. Test Matrix

Test Set	Description
1	Higher Hydrogen Supplementation/Improved Setup. Additional hydrogen supplementation (than prior testing) to be supplied to determine if leaner operation could be achieved. During this task, the intake and boost system were improved.
2	Baseline with Higher Ignition Energy. Engine operating at rated speed of 1,800 rpm. Vary exhaust O ₂ from 4% to the lean limit of stable operation in 2% increments. Maintain IMEP at the same level as the baseline test. Determine lean limit as compared to prior testing.
3	Synthetic Reformate Testing with Higher ignition energy. Engine operating at rated speed of 1,800 rpm. Vary reformate addition rate from 2% of the LHV of the engine fuel to 10% of the LHV in 2% LHV increments. At each addition rate, vary exhaust O ₂ from 4% to the lean limit of stable combustion in 2% increments. Maintain IMEP at the same level as the baseline test.
4	Synthetic Reformate Testing with EGR/Mixing System. Engine operating at rated speed of 1,800 rpm. At fixed reformate addition rate, vary EGR rate at fixed exhaust oxygen concentration until lean stability limit. A static mixer may also be inserted to ensure a homogeneous mixture of fuel, air, and diluents entering the cylinder.

Test Set	Description
5	Synthetic Reformate Testing with Water Injection. Engine operating at rated speed of 1,800 rpm. At fixed reformate addition rate, vary water injection rate at fixed exhaust oxygen concentration until lean stability limit.

Test Set 1, which was higher hydrogen supplementation and an improved intake setup from prior testing, was based on conversations with reformer suppliers that show that the reformer set up could supply a higher amount of hydrogen. Also, the intake was designed for improved mixing. This additional hydrogen had the benefit of allowing leaner operation, which allows more dilutes operation. Additionally in the following test sets, hydrogen supplementation was higher than that of the prior tests in Task 2.2.

Test Set 2 defined the lean limit of stable combustion in the standard engine configuration with higher ignition energy. This test allowed comparison of the BioHALO system with the higher ignition energy system, as well as determine the optimum spark profile (as this is a parameter that may be changed with the ignition system). In this set, the exhaust O₂ was varied from 4% to the lean stability limit in increments. The engine indicated mean effective pressure (IMEP) was improved to close to the level for the baseline test by increasing the discharge pressure of the turbocharger. Exhaust O₂ concentration was used as the test variable to avoid confusion regarding the definition of relative air/fuel ratio.

Test Set 3 established the extent that the lean limit of combustion can be extended by adding hydrogen-rich reformate to the engine's LFG fuel with higher ignition energy. Based upon Test Set 2, the authors selected the optimum ignition profile (the ignition profile was found to not affect COV, so the manufacturer baseline profile was used). Reformate addition rate was varied from 8% to 16%. Similar to Test Set 2, IMEP will be improved to offset the high dilution by varying the discharge pressure of the turbocharger.

Test Set 4 explored the addition of adding EGR/mixing to the intake system to further reduce the NO_x emissions. EGR had the potential benefit over pure air dilution of containing water vapor as well as CO₂, which has a higher heat capacity than air. A mixing system downstream of the EGR introduction point ensured that the charge was well-mixed going into the engine cylinder. Tests were run at a range of EGR rates, from 5 to 30%.

Test Set 5 (water injection) was carried out because the prior tests did not show the desired NO_x reduction. Water injection is a method that lowers the in-cylinder temperatures during combustion, reducing the NO_x output from the engine. Testing was done to explore the amount of water that can be feasibly added to aid in NO_x reduction. The composition of the reformate from a typical autothermal reformer is given in Table 6-4.

Table 6-4. Synthetic Reformate Composition From Reformer

Component	Representative Reformer Output Concentration, % vol
H ₂	14.1
CO	13.2
CO ₂	9.6
N ₂	46.8
H ₂ O	16.3

The primary component of the reformate that will affect the in-cylinder combustion is the hydrogen (due to its high flame speed and easy ignitability), so hydrogen alone was added to the simulated landfill gas mixture. Diluents and CO would also be part of the reformate mixture if an actual reformer were used (the impact on gas mixture composition in the cylinder was not significant).

6.4.2. Test Measurements

The engine operating parameters that were measured for each test, along with the instrumentation used to measure these, are described in Section 5.4.2 above. For EGR, a three-way valve was used to sample inlet air to measure CO₂ intake.

6.4.3. Data Analysis Procedures

The data analysis procedures for Task 2.3 were the same as for Task 2.2 and are described in Section 5.4.3 above.

6.4.4. Data Analysis Procedures

The quality assurance procedures for Task 2.3 were the same as for Task 2.2 and are described in Section 5.4.4 above.

6.5 Test Results of Task 2.3

During testing, TIAX tried a series of configurations to meet the program goals as well as explore a variety of options for each of the proposed methods of NO_x reduction. Also, as expected with any experimental program, there were difficulties with the experimental setup that had to be overcome to proceed with testing. A timeline of the testing that this report covers is shown below in Figure 6-2. Prior to the dates shown on the timeline TIAX was re-commissioning the BioHALO system, as it had been idle for a period of time.

During testing, there were two failures: the VimX ignition system and an intercooler failure. In the initial VimX system received from the manufacturer, the MOTEC system would supply a signal to the VimX ignition system but did so after the signal went through high-voltage igniters. The VimX modules would occasionally misinterpret this high-voltage signal, resulting in a false signal sent to the ignition coil on the engine. Because of this problem, repeatable testing could not be done. To allow for continued testing, TIAX switched back to the Motec ignition system and began a dialogue with the manufacturer. In speaking to the manufacturer, it was determined that the best way to use the modules was to bypass the high voltage igniters.

This required a change in the modules, and TIAX performed that change and reinstalled the system. The other hardware failure that was encountered during testing was the Spearco intercooler developed the leak, allowing water to leak into the air stream. Thus, the intercooler was removed and replaced by the “block intercooler.”




Figure 6-1. Timeline Covered by Report

TIAX systematically changed components so as to improve system performance as well as address failures. The setups for the testing are identified below in Table 6-6. Photographs of the various components will be shown in the results section for each aspect of the test plan.

Table 6-5. Summary of BioHALO Setups for Task 2.3

Setup Variables	Setup A	Setup B	Setup C	Setup D	Setup E	Setup F
Ignition System	VimX	MOTEC	MOTEC	MOTEC	VimX	Smartfire
Turbocharger	GT20	GT20	GT32	GT32	GT32	GT32
EGR System/Intake	Venturi with long intake	Venturi with long intake	Venturi with long intake	Shorter intake/ EGR pre-compressor	Shorter intake/ EGR pre-compressor	Shorter intake/ EGR pre-compressor
Intercooler	Spearco	Spearco	Spearco	Block	Block	Block

The Task 2.3 testing was divided into four areas (based upon recommendations from the Task 2.2 Report) that were explored to determine the effect on the combustion and emissions of the engine: additional hydrogen supplementation, higher ignition energy, higher dilution in the form of EGR and better mixing, and water injection.

The object of these tests was to sweep over a wide variety of points to determine the optimum point, so each test point was relatively short to allow for all of the tests to be accomplished. A typical test day would proceed with the following procedure:

- The engine would be started and idled until the coolant temperature reached approximately 50°C.
- The generator would then be connected up to the electrical grid, bringing the engine speed to 1800 rpm.
- The throttle would be opened, and fuel would automatically be added by the Motec system until a point of about 40 kW was reached. The engine would be kept at this point until the oil and coolant temperatures reached the appropriate operating levels. During this time, the carbon dioxide and nitrogen would be added to simulate the landfill gas.
- At this point, hydrogen would be added to the appropriate level, boost adjusted accordingly, and the desired operating point would be set.
- Once the point reached steady-state, as evidenced by the emissions and the combustion stability, data would be taken for 60 seconds. This time period was chosen to correlate with the fairly standard practice²² of using 500 cycles of engine combustion data to determine combustion stability, and thus the emissions data would line up with the combustion stability data.

Since there were three systems taking data, (emissions data, the combustion data, and the temperatures and flow rates), the engine would be at each point for a range of 5 to 15 minutes. Some test points would be much shorter because changes between each test point were relatively minor, such as increasing hydrogen flow rate, as stabilization would quickly occur, while at some test points the engine would run for an extended length of time.

6.5.1. Results of Higher Hydrogen Supplementation/Improved Engine Setup

The early stages of this task involved improving the intake system to allow for better mixing, allowing for EGR introduction, in addition to examining the effects of increasing the amount of hydrogen provided to the engine. This setup is shown in the photograph below. In this photograph, the EGR system is not complete yet, but the intake system can be seen. The length of the intake system does lead to a pressure drop, lowering the available boost, but due to the engine geometry this was the only feasible way to include the mixer and the Venturi. Also as mentioned in the timeline, a different turbocharger was installed to improve the airflow rate into the engine. The first turbocharger was a Garret GT -- 20 and had a maximum flow rate of about 120 g per second of air. The second turbocharger tried was a Garret GT -- 32, into this allowed flow rates up to 160 g per second of air. This increase in the airflow rate improved the power density of the engine.

²² Heywood, John B. *Internal Combustion Engine Fundamentals*. McGraw-Hill, New York, 1988. p 418




Figure 6-2. Photograph of Intake System
Photo Credit: TIAX LLC

As detailed in the earlier timeline, improvements were made to the intake system to allow for better mixing. The improved mixing allowed a more homogeneous mixture to enter the cylinder, promoting improved combustion. This is evidenced by examining the data and comparing it to the prior runs. As may be seen in Figure 6-3, there is a shift of the lean limit.




Figure 6-3. Comparison of Task 2.2 data to improved setup and higher hydrogen supplementation

This shift in the allowable operating condition had an effect on the measured NO_x. The greater dilution provided by the excess air lowered the peak in-cylinder flame temperatures, reducing the thermal NO_x formation. This may be seen in the results, as shown in Figure 6-4.




Figure 6-4. Comparison of NO_x values for the additional hydrogen supplementation/improved intake
 A summary of the points where combustion stability was excellent is shown below in Table 6-6. As may be seen on the amount of hydrogen added, it appears that the main benefit comes from the better mixing of the intake system, although the two best points did have hydrogen supplementation in excess of 10%.

Table 6-6. Summary of points where IMEP COV < 11%

IMEP (bar)	IMEP COV (%)	NO _x (Corrected to 15 % O ₂) [ppm]	NO _x (g/bhp hr, 15% O ₂)	NO _x (lb/MW hr)	H ₂ LHV/CH ₄ LHV
5.4	8.1	5	0.035	0.10	13.5%
7.1	4.7	31	0.190	0.56	9.5%
7.5	1.7	46	0.247	0.73	9.5%
6.9	11.0	7	0.044	0.13	11.4%
6.9	4.2	20	0.123	0.36	9.1%
6.8	4.0	32	0.186	0.55	9.0%
7.1	5.3	30	0.166	0.49	8.9%
6.6	8.7	10	0.071	0.21	7.5%

6.5.2. Higher Ignition Energy Test Results

This next section summarizes the results from the higher energy ignition scoping tests. Two commercially available separate ignition systems were tried: 1. Woodward Smartfire Ignition System, and 2. VimX Ignition system. The specifications for the Smartfire system are shown in Table 6-7. Typical stock coils provide 90-120 mJ to the spark plug.

Table 6-7. Smartfire Ignition System Specifications

	Specification
Ignition Type	Capacitive Discharge
Cylinder capability	1-12
Software Control	Windows-based Winfire
Combustion Feedback	Ion current sensing
Coil Type	Custom pencil coils
Spark Plug	Standard J-type
Estimated Spark Energy delivered to plug	151 mJ

The Smartfire system works by discharging a 600 volt capacitor into a coil, which steps up the voltage up to several thousand volts within one microsecond. This large voltage jumps the gap and ignites the combustible mixture in the cylinder. The spark reaches 1 amp and then decays for the order of 40 microseconds. The Smartfire system also has the ability to detect combustion, as highlighted in Table 6-7. Combustion feedback is achieved using ion-current feedback. After the initial spark, a second capacitor is charged, which applies a constant voltage to the plug gap. Combustion, which is occurring as this constant voltage is applied, produces ions. These ions induce a trickle current, which is measured and processed. If combustion does not occur, then there will be no ion current produced, and this will be detected by the Winfire software.

A photograph of the installed Smartfire system is shown in Figure 6-5.




Figure 6-5. Smartfire system installed on BioHALO engine
Photo Credit: TIAX LLC

A schematic of the Smartfire ignition system is shown in Figure 6-6.




Figure 6-6. Smartfire schematic

The other alternative ignition system also tried during the set of experiments was the VimX system. The specifications of this high energy system are shown in Table 6-8.

Table 6-8. VimX Ignition System Specifications

	Specification
Ignition Type	Capacitive Discharge
Cylinder capability	1-12
Software Control	Windows-based Monitoring
Combustion Feedback	None
Spark Plug	Standard J-type
Coil Type	Standard Coil-over-plug
Claimed Spark Energy delivered to plug	500 mJ

A photograph of the VimX system is shown below in Figure 6-7.




Figure 6-7. Labeled VimX Ignition System
Photo Credit: TIAX LLC

The VimX system is run as a slave to the Motec system, as discussed earlier. The Motec would supply the trigger signals to the VimX and, using the supplied software, the spark timing as well as the spark durations and profiles could be altered. A screenshot of the VimX ignition control software is shown below.




Figure 6-8. Screenshot of VimX Ignition System

Two systems were chosen to show a robust comparison. The Smartfire system was used and purchased for another project but proved to be useful during this test. One caveat with the Smartfire system was that the pencil coil design prohibited the use of the pressure-sensing spark plug, so power output was used as a means to determine combustion reliability (as may be seen from Figure 6-9).



Smartfire Coil



Standard Ford Coil

Figure 6-9. Comparison of Smartfire Coil to Ford Coil

Using this test setup, a series of tests were run to explore the effect of the higher energy ignition systems. The theory behind using higher energy ignition systems is that, even though the supplemental hydrogen greatly increases the ignitability of the mixture in the cylinder, the high dilution still present difficulties for ignition. A higher energy ignition system has the potential to overcome this difficulty, allowing leaner and more dilute mixtures, thus reducing the thermal NOx production. The effect of these systems are shown below.




Figure 6-10. Comparison of VimX Ignition System with Standard

As may be seen from the green triangles in Figure 6-10, the high-energy VimX ignition system does not appear to have a beneficial effect on the IMEP COV for lean operation. Even though the system supplies additional energy, most of the data points fall right into the data scatter of the standard system, and some VimX data points on IMEP COV (%) are higher. The Smartfire system is left out of this graph because the pencil coils did not allow the measurement of in-cylinder pressure due to their design interfering with the spark plug pressure transducer. The Smartfire effects (or lack thereof) may be seen when the emissions data is taken into account. This is shown in the following figure (Figure 6-11).




Figure 6-11. Effect of High Energy Ignition System on NO_x Emissions

A similar effect is seen when both the VimX and the Smartfire ignition points are plotted with respect to their and NO_x reduction capabilities. From Figure 6-11, the green triangles, which represent the higher energy ignition systems, fall among the data from the prior exploration, suggesting that the increase in ignition energy provided by these systems does not alter the cycle variability for extremely lean mixtures, and thus not allowing further NO_x reductions.

Table 6-9. Summary of Lowest NO_x Results for Higher Ignition Energy Tests

IMEP (bar)	IMEP COV (%)	NO _x (Corrected to 15 % O ₂) [ppm]	NO _x (g/bhp hr, 15% O ₂)	NO _x (lb/MW hr)	H ₂ LHV/CH ₄ LHV
4.5	80.2	9	0.270	0.80	7.8%
6.8	34.9	19	0.334	0.99	13.1%
3.6	76.0	4	0.119	0.35	14.1%
6.2	27.8	7	0.122	0.36	14.4%
6.8	12.4	9	0.144	0.43	14.7%
6.2	25.3	6	0.104	0.31	14.7%
4.0	81.4	7	0.195	0.58	9.6%
N/A	N/A	7	0.110	0.33	11.0%
N/A	N/A	4	0.089	0.26	13.5%
N/A	N/A	4	0.076	0.22	14.2%

As may be seen from Table 6-10, the results from the high-energy ignition systems are not very impressive. Although some points have very low NO_x omissions, the combustion stability is

unacceptable. Thus, it appears that the high-energy ignition systems did not have the desired effect on the system.

6.5.3. EGR Systems Test Results

This section will deal with exhaust gas recirculation and how that affected the NO_x emissions. EGR has a marked effect on the in-cylinder temperatures because the water and the carbon dioxide present in the engine exhaust both have high specific heat, and the water will vaporize, further decreasing the cylinder temperature. A caution with EGR is that because it is from the engine exhaust, it is high temperature, which could have the opposite of the desired effect on the NO_x production. Thus, for the EGR set up in this project, the commercially available EGR cooler was used from the Ford Powerstroke diesel. The cooling medium for this cooler was engine coolant. This cooler was used in both of the EGR systems tested. The first EGR system tested was in the high-pressure loop of the system, meaning that the EGR induction point was after the compressor of the turbocharger. Since EGR is driven by a pressure differential, it was necessary to introduce a Venturi to drop the intake pressure enough to allow the exhaust gas to flow from the exhaust manifold into the intake manifold through the EGR cooler. For the sizing of a Venturi, values were used from the literature for the optimum ratio of the throat diameter to the pipe diameter. To verify the selection, a computational fluid dynamics model was made of the Venturi to assure that the pressure drop from the exhaust manifold to the throat of the Venturi would be adequate to allow enough EGR to circulate into the engine intake.

The results of the CFD simulation are shown below in

Figure 6-12.




Figure 6-12. Pressure Contours for the Selected Venturi




Figure 6-13. Close Up of Venturi Throat

As can be seen from the figure, the pressure drop across the entire Venturi was minimal. This case was run for a typical case where the engine flow rate was 120 g/s of air and the boost pressure was 130 kPa. A close-up of the throat of the Venturi, shown in Figure 6-13, shows that the pressure in the throat was right around atmospheric, which was adequate pressure to allow for the EGR to flow from the exhaust system, which is typically at 30 kPa above atmospheric when the waste gate of the turbocharger is fully closed.

A photograph of this setup is shown below.




Figure 6-14. Photograph of High-Pressure Loop EGR System
Photo Credit: TIAX LLC

The inlet to the EGR cooler was tapped right into the exhaust manifold prior to the turbine of the turbocharger. The exhaust then flows to the cooler, where it was regulated by a ball valve before being introduced circumferentially into the throat of the Venturi. The advantage of introducing the EGR in this method was that the compressor of the turbocharger did not have to do work on the exhaust gases.

In addition to this method, an alternate method was used where the EGR was introduced before the turbocharger. This method was attempted for the maximum EGR rate. A photograph of the engine with this setup is shown below in Figure 6-15.




Figure 6-15. Photograph of second EGR setup
 Photo Credit: TIAX LLC

In this setup, the same EGR cooler was used, but the outlet of the EGR cooler went directly to the engine intake, as may be seen from the photograph. The intake in this setup was much shorter because of the direct geometry, but had the disadvantage of having to compress the EGR as well as the air in the turbocharger. Since both systems resulted in EGR been introduced into the engine, no distinction was made between the two systems in the results analysis.

The effectiveness of the EGR cooler is shown below. During these tests the coolant was at an average of 80°C. It can be seen that, for the lower flow rates of EGR, the exhaust gas came close to the coolant temperature, but for the higher floor rates of EGR, it did not get cooled down as much. However, a significant temperature drop was observed through the EGR cooler, which was beneficial to the combustion.




Figure 6-16. EGR Cooler Effectiveness

EGR had an interesting effect on the NO_x emissions. This effect is shown in the context of the other explorations in Figure 6-17.




Figure 6-17. Effect of EGR on NO_x

At lower oxygen concentrations, the EGR greatly reduced the thermal NO_x formation, as the EGR points (represented as circles) are below the other points. However, at the higher exhaust

oxygen concentrations, the EGR points fell right in among the excess air points. Thus, it appeared at extremely high levels of dilution with excess air, the NO_x production was equivalently low to that of EGR supplementation. The best results are summarized below.

Table 6-10. Summary of Lowest NO_x Points for EGR Tests

IMEP (bar)	IMEP COV (%)	NO _x (Corrected to 15 % O ₂) [ppm]	NO _x (g/bhp hr, 15% O ₂)	NO _x (lb/MW hr)	H ₂ LHV/CH ₄ LHV	EGR (%)
6.1	8.7	8	0.044	0.13	10.7%	14%
5.9	5.1	19	0.122	0.36	15.5%	8%
5.9	3.7	7	0.047	0.36	14.7%	9%
5.96	1.7	16	0.100	0.14	14.7%	31%
7.7	16.4	24	0.191	0.30	10.5%	9%
N/A	N/A	7	0.089	0.56	10.6%	12%
N/A	N/A	22	0.114	0.26	13.5%	18%

The lowest NO_x points are summarized in Table 6-10. It may be seen that the EGR did better than the higher energy ignition systems. Multiple points in the table contain excellent NO_x readings as well as acceptable combustion stability.

6.5.4. Water Injection Test Results

Briefly examined in these tests was the effect of injecting water. Water was injected into the system prior to the throttle body using a misting nozzle. A photograph of the water spray is shown below.



Figure 6-18. Photograph of Water Spray
Photo Credit: TIAX LLC

The photograph was taken, for ease of experimentation, in a room environment (standard temperature and pressure). It can be seen that the spray breaks up into droplets extremely well. Inserting this nozzle into the engine would have the effect of narrowing the spray cone as air rushes by the nozzle. Since the manufacturer claims to have droplet sizes smaller than 30 µm, it

is assumed that the majority of the droplets are entrained into the air stream and carried into the cylinders.

Plotting the water points on the graph with the rest of the data, the following figure is observed.




Figure 6-19. All corrected NOx data, including water injection points, as function of Exhaust O₂

The water points (shown as large blue circles) fall on top of the other points indicating that there was not a significant advantage to the injection of water, compared to other means of dilution. However, for a given dilution, the water did reduce the NOx emissions with minimal penalty.

Table 6-11. Summary of Water Injection Test Points

IMEP (bar)	IMEP COV (%)	NOx (Corrected to 15 % O ₂) [ppm]	NOx (g/bhp hr, 15% O ₂)	NOx (lb/MW hr)	H ₂ LHV/CH ₄ LHV	Water Flow (g/s)
7.1	5.3	30	0.338	1.00	8.9%	3
6.0	17.3	7	0.101	0.30	8.5%	1
6.6	8.7	10	0.142	0.42	7.5%	1

Despite the slight benefit, the water did not drop the NOx emissions enough to meet project goals.

6.5.5. Conceptual Process Optimization Overview

This report has detailed the results from a series of five experimental setups trying a range of four methods to reduce NOx emissions from an engine fueled with synthetic landfill gas. This

section will endeavor to step back and look at the results as a whole from the series of tests over the experimental setups.

It is interesting to see the effect of hydrogen on NO_x production. This is an indirect effect because hydrogen allows more dilution, but still is telling as to the results. Plotting a range of test points selected from all of the experiments during the conceptual process optimization results in the graph below.




Figure 6-20. Comparison of all results showing effect of hydrogen addition

The higher amounts of hydrogen concentration are shown as the blue circles. At the higher exhaust oxygen concentrations (9-10% O₂), where dilution is the highest and hydrogen is necessary for combustion to occur, are where the most points with higher hydrogen supplementation are located. Thus, from the standpoint of pure dilution and hydrogen supplementation, it appears from this result that the higher hydrogen supplementation is most useful in obtaining the lower NO_x emissions.

An important issue to take note of with high dilution engines is not only the ignition in combustion stability, but also the burn durations. As more and more dilution is added to the cylinder, the flame front will have difficulty propagating, especially when the dilution products are not an oxidizer such as air. Hydrogen does much to counteract this because of its extremely high flame speed. The parameter to examine to determine burn time is the 10 to 90% duration, which is a measure which the combustion analysis program calculates to determine the time in crank angle degrees it takes for the combustion to proceed from 10% mass fraction burned to 90% mass fraction burned. The results of this are plotted as a function of oxygen concentration.




Figure 6-21. Burn Time as a Function of Exhaust Concentration

For a typical stoichiometric engine, the burn times are between 17 and 25 crank angle degrees. As the burn time increases, the flame stretch as it moves across the cylinder can become an issue. For engines that operate with more dilution, burn times less than 35 crank angle degrees are typical. However, it may be seen from this data that even though more hydrogen (thus increasing the flame speed) is added, the trend is still upward with respect to burn time increasing with increasing in-cylinder dilution. This suggests that even though the mixture can be ignited, more hydrogen may be necessary to decrease the burn time. This decrease in burn time will also lead to an increase in combustion stability as well as a decrease in cycle-to-cycle emissions variability.

Looking at the approaches as a whole, most of the approaches were effective in reducing the NO_x production, even though the higher ignition energy systems did not improve the ignitability of the mixtures. A summary of all the points that show acceptable combustion stability or acceptable power output (in the case of the Smartfire system where combustion stability measurements were not taken) is shown below.




Figure 6-22. Summary of points with acceptable combustion stability

As may be seen from the above figure, the variety of approaches allowed for significant NO_x reduction. The most effective method is the addition of more hydrogen, which allowed for the introduction of EGR or operating with more air dilution.

A summary of the lowest NO_x points that still provided acceptable combustion stability is shown below in Table 6-12.

Table 6-12. Summary of low NO_x points with acceptable combustion stability

IMEP (bar)	IMEP COV (%)	NO _x (Corrected to 15 % O ₂) [ppm]	NO _x (g/bhp hr, 15% O ₂)	H ₂ LHV/CH ₄ LHV	NO _x (lb/MW hr), 15 % O ₂
5.4	8.1	5	0.035	13.5%	0.10
6.9	11.0	7	0.044	11.4%	0.13
6.6	8.7	10	0.071	7.5%	0.21
6.8	12.4	9	0.078	14.7%	0.23
N/A	N/A	4	0.043	14.2%	0.13
6.1	8.7	8	0.044	10.7%	0.13
5.9	3.7	7	0.047	14.7%	0.14
6.6	8.7	10	0.071	7.5%	0.21

The NO_x results as summarized in the above table show a significant reduction when compared to the results obtained in Task 2.2, so the methods of further NO_x reduction suggested in the

task 2.2 test report were effective. The results do come close to the project goals 0.032 g/bhp-hr or 0.07 lb/MW-hr but are still above those goals.

6.5.6. *Extended Period Test Run*

The extended period test run was carried out to examine the long-term stability of the process. The extended run highlights the need for closed-loop feedback for the engine control. Any time there is a NO_x excursion, the cause can be easily correlated to the air/fuel ratio. The main reason for the air/fuel ratio excursions was the fuel supply, which was bottled natural gas stored in six packs of 300 ft³ bottles. The bottles are supplied at about 2000 psi pressure and are regulated down to 50 psi through a series of regulators at a high flowrate to supply the engine with fuel. Because of the Joule Thompson effect, as the gas is expanded, it cools. The supply gas temperature ranged from -60 to -40 deg Fahrenheit during the testing. For shorter test runs, this temperature (and thus the natural gas pressure/state) was steady, but over the longer test runs, the effect had to be manually compensated and caused the drift seen in the air/fuel ratio, leading to the drift seen in the NO_x emissions.

The NO_x emissions can be seen as a function of time over the extended run test in Figure 6-3. The variations, as mentioned earlier, are a function of the air/fuel ratio. Setup F was used during this test run. The test was done in the typical manner, and throughout testing the bottled gasses were switched as needed.




Figure 6-23. NO_x Emissions and Excess Air During the Extended Test Run

Even though there are fluctuations, the histogram of the above data clearly shows that the excursions do not reflect the majority of the NO_x emissions.




Figure 6-24. Histogram of NOx Data During Extended Time Test

As shown in the figure, the majority of test points were in the 6-8 ppm range, with the next highest amount in the 8-10 ppm range. The average over the entire test was 6 ppm, which corresponds to 0.042 g/bhp hr NOx, validating prior work.




Figure 6-25. NOx Emissions Dependence on Exhaust O₂

Shown in the figure is the band of NOx emissions as a function of exhaust oxygen concentration. As the air/fuel ratio becomes leaner, the in-cylinder combustion temperature drops, lowering the thermal NOx production. This highlights the importance of excellent air/fuel ratio control, especially at these extremely lean air/fuel ratios. A summary of the entire test run is given below.

Table 6-13. Summary of Extended Test Run

Average Engine Power (kW)	Average O ₂ (%)	Average T. HC, CO, CO ₂	NOx (Corrected to 15 % O ₂) [ppm]	NOx (g/bhp hr, 15% O ₂)	NOx (lb/MW hr)	H ₂ LHV/CH ₄ LHV
55	9.4	1900 ppm, 0.06%, 6.9%	6	0.042	0.12	12%

6.6 Reformer and Heat Exchanger System Optimization

The test program was designed in such a way that the reformer/heat exchanger system design was optimized in parallel to the engine setup optimization, as the feedgas requirements of the hydrogen into the engine directly impact the required reformer performance.

One key issue for the reformer is the temperature of the reformed gases entering the engine, as that has a direct correlation to engine emissions. Shown below is a plot of intake temperature as a function of boost.




Figure 6-26. Intake Temperature as a Function of Boost

As may be seen from the above graph, which shows the temperature of the intake after the intercooler, the majority of points fall around 60°C. However, the hotter EGR points do raise the intake temperature to around 90°C. How this affects NO_x production is shown in the figure below.




Figure 6-28. The Impact of Hydrogen Supplementation

Looking at the points from the low NO_x runs in Figure 6-28, it may be seen that in the data scatter it appears that increasing the hydrogen supplementation above 10% does not improve the NO_x reduction significantly, while the cost and size of the reformer and heat exchangers scales with hydrogen. Therefore, the recommended hydrogen supplementation rate is 10% H₂/CH₄ LHV.

Thus, from the BioHALO system perspective, the minimum reformer specifications are summarized below as based upon the results of Task 2.3:

Table 6-14. Summary of Acceptable Reformer Parameters

Parameter	Value
Total Reformer Flow Rate for this engine power rating	900-1000 SCFH
Acceptable reformat/air post-intercooler temperature	60 deg C or less
Necessary H ₂ concentration in reformat	28 %
System Pressure	Atmospheric
Duty Cycle	Reformer must follow engine load to maintain 10 % LHV H ₂ /CH ₄ up to 100% load

6.7 Results and Recommendations based on Task 2.3 Test Results

Based upon the recommendations from the Task 2.2 test report, this series of tests in Task 2.3 have been successful in improving the emissions performance of the engine. However, emissions levels are still slightly above the proposed goals. Following is a list of the conclusions and recommendations from this round of testing:

- The improved mixing provided by the intake redesign in addition to the higher amounts of hydrogen supplementation proved effective in reducing the engine emissions.
- The ignition system, when switched to high-energy options, did not show a particular improvement in performance or emissions. A further concern noted during this Task was that even though ignition was achieved of the mixture, the burn times are slightly longer than desirable, leading to cycle-to-cycle variability.
- Water injection was interesting in that it allowed for lower NO_x emissions when compared to a standard point of similar dilution but did not improve the emissions to the point beyond emissions targets.
- Because this was a test plan designed to encompass a range of operating conditions, each point was short to finish all of the testing required in the given amount of time. To prove the value of the system, it would be desirable to run for a much longer period.
- Although NO_x targets were not met, the results show an impressive emissions reduction for a reciprocating engine technology. For example, BACT for a Hess Microgen stoichiometric natural gas engine with a three way catalyst is 0.07 g/bhp-hr, and this project demonstrated multiple points 50-67% of this value *engine out*.
- It would be interesting to explore using hydrogen supplementation as an enabler for high load/high dilution pre-mixed charge ignition concepts. The hydrogen supplementation was able to light off, but work could be done to improve its combustion stability as well as improve burn durations. Using a high-energy micro-pilot or compression ignition might answer the two concerns raised in this task and provide the dilution necessary for even lower NO_x.

7.0 Results of BioHALO System Conceptual and Detailed Design

Task 2.4 of the project covered the Conceptual Design of a generic BioHALO system, which includes a LFG “slipstream” reformer feeding hydrogen-rich reformat fuel gas (blended with the balance of the LFG) to the engine. The design is based on the most promising configuration of BioHALO determined from the Task 2.3 optimization tests.

Key features of the system for successful efficient low-NO_x operation include (a) energy management of the reformer using heat exchangers and (b) lean-burn set-up of the engine (excess air, boost, high energy spark, and low manifold air temperature).

This section is organized as follows: *Section 7.1* includes a discussion of the design basis and discussion of evaluations and tradeoffs considered. *Section 7.2* is a summary of the system specifications for the BioHALO based on Task 2.3 optimization studies. These specifications will address the following:

- IC engine
 - Target A/F ratio
 - Required reformat mix ratio
 - Spark timing and type of ignition system
 - Intake manifold temperature
 - Intake manifold pressure and type of turbocharger
- BioHALO reformer
 - Required total flowrate
 - Acceptable reformat temperature range
 - Needed reformat hydrogen concentration
 - System pressure
 - Duty cycle
 - Recommended heat exchangers to avoid excess fuel use or electric power
- Exhaust oxidation catalyst (if required to meet targets for CO and VOC engine-out emissions)
 - Engine exhaust temperature range
 - Engine exhaust flow rate

- Engine exhaust CO and VOC concentration
- Conversion efficiency needed
- Durability expectations including siloxane tolerance
- Controls
 - Control algorithm type
 - Number of control outputs and sensor inputs needed
 - Sensor requirements

Section 7.3 describes the detailed heat and mass balances for BioHALO including chemical reactions of the hydrogen generator (reformer) and the heat exchangers. *Section 7.4* presents the package of schematic drawings, diagrams, and parts lists as follows:

- Process flow diagrams
- P&IDs
- Controls schematics
- Equipment and layout sketches
- Preliminary equipment lists

Section 7.5 of this Conceptual Design section includes a discussion of operating strategies to employ and resulting performance expectations. The Conceptual Design Report is intended to be used as a foundation for specific detailed designs of BioHALO systems for various power levels depending on the anticipated LFG volume flow rate.

7.1 Design Basis of BioHALO System

7.1.1. Engine Operating Parameters for Optimization of NO_x

Scoping tests were conducted using synthetic reformat on an instrumented landfill gas engine rated at 75 kW at the TIAX engine test laboratory. Most runs were carried out with the engine operated at 45-55 kW to operate sufficiently lean to achieve low NO_x with H₂ addition. In this initial phase of the development effort, engine operation and emissions performance data needed to be developed with the eventual demonstration engine/ generator fueled with synthetic LFG combined with synthetic reformat having a composition similar to that expected to be produced by the eventual ATR placed at the site. Using a mixture of 57% natural gas, 23% CO₂, and 22% N₂ as the synthetic LFG reformat, the leanest point the baseline engine could be operated at was 4.2% O₂ in the exhaust (*without hydrogen*), after which the combustion stability deteriorated. This corresponded to about 25% excess air. At this point, the engine-out humidity corrected NO_x was 440 ppm, which corresponds to 1.8 g/ihp-hr NO_x (2.2 g/bhp-hr NO_x or 6.9 lb/MW-hr).

The next set of tests (Task 2.2) was designed to determine the effect of adding synthetic reformat, which was 52% H₂ and 48% CO. Adding this synthetic reformat mixture allowed the engine to have stable combustion out to ~8 % O₂ in the exhaust at a minimum addition rate of **6% H₂/CH₄** (on a LHV basis). This corresponded to 62% excess air. Addition of further hydrogen increased the combustion stability marginally, but it still did not allow the engine operating limit to be extended beyond 8% O₂ in the exhaust. At this operating condition, humidity corrected **NO_x was 20 ppm**, which corresponds to 0.12 g/ihp-hr NO_x (0.15 g/bhp-hr or 0.47 lb/MW-hr), a reduction of over 93% compared to the baseline case.

The next set of tests (Task 2.3) were designed to use high energy spark and EGR to optimize the excess air to minimize NO_x by adding even higher levels of hydrogen (synthetic reformat). Adding this level of hydrogen (10-14% by energy) allowed the engine to have stable combustion out to ~10-11% O₂ in the exhaust at a minimum addition rate of **10% H₂/CH₄** (on a LHV basis). This corresponded to 100% excess air. Addition of further hydrogen increased the combustion stability marginally, but it still did not allow the engine operating limit to be extended beyond 10-11% O₂ in the exhaust. At this operating condition, humidity-corrected **NO_x was 7-8 ppm (4-5 ppm NO_x corrected to 15% O₂)**, which corresponds to 0.05 g/ihp-hr NO_x (**0.055 g/bhp-hr or 0.17 lb/MW-hr**), a reduction of over 97% compared to the baseline case. *This represents a significant reduction over the best LFG fired lean-burn prechamber engines, whose levels are 0.4 g/bhp-hr*, but still was 25% above the proposal target of 0.032 g/bhp-hr NO_x (0.10 lb/MW-hr). The 98% reduction in engine-out NO_x has been demonstrated using an in-line turbulent mixer and high-energy spark system.

7.1.2. Design Basis for BioHALO System

Based on the test program summarized above, the key BioHALO process parameters are as follows:

- LFG Engine operated at 100% excess air (10% O₂ in exhaust) with high energy ignition system
- Engine turbocharged to at least 0.5 bar intake manifold above atmospheric, and aftercooled to maximum intake manifold temperature 40°C.
- Landfill gas reformer sized to supply hydrogen at 10% of the methane flow rate by energy (33% by volume H₂ in total H₂ plus CH₄). This implies that approximately 15% of the LFG flow is diverted to the reformer to produce hydrogen. (The reformer also produces CO fuel value at 22% volume CO per volume of hydrogen; therefore the fuel value of the CO adds 26% to the H₂ fuel value).
- NO_x emissions controlled to 0.032 g/bhp-hr (0.10 lb/MW-hr) by virtue of specifications 1, 2, 3 above.
- System efficiency accounting for reformer thermal management must be within 2% of baseline without BioHALO.

- Ability to follow variable load same as conventional LFG engine while maintaining 10% O₂ in the exhaust and proportional hydrogen flow from reformer at 10% of methane flow rate by energy.
- Oxidation catalyst reduces engine-out UHC and CO emissions to under 10 ppm.

The BioHALO system schematic is shown in Figure 7-1 below.




Figure 7-1. Schematic of BioHALO System

Reformer operating conditions: Not shown in this figure is the type of reformer or operating conditions such as air-fuel ratio or light-off temperature. After considering several types of reformers (partial oxidation, steam reforming, etc) we selected the auto-thermal reformer operating at equivalence ratio 3:1 (200% excess fuel). This reformer can be designed around a low cost catalyst similar to an automotive three-way catalyst, and is slightly exothermic (adiabatic temperature rise of about 200°C between inlet and outlet). For catalyst light off, the inlet gases must be at 600°C. The reason that the authors avoided steam reforming is that the addition of a small steam generator (boiler) was seen to be problematic in terms of maintenance, plugging and fouling, etc.

Need to cool down the reformate fuel gases: The reformate gas (H₂, CO and inerts) exits the reformer at about 800°C and must be cooled down to at least 140°C before remixing with the 85% main stream of LFG fuel. Otherwise air breathing would be impacted and engine power would suffer.

Need for preheat and sources of preheat: Three gas inlet streams must be preheated to enter the reformer at 600°C (about 1100°F); the LFG itself, the water vapor (steam) required, and the air supply to the reformer. Even at only 15% of the LFG flowrate, the LFG-slipstream preheat represents a significant heat demand. The design calls for using two sources of heat:

- The exhaust gas exits the turbocharger intercooler at about 550°F (250°C) and still contains about 14% of the original fuel energy. Therefore exhaust gas can be used to (a) preheat water to 100°C before creating steam for the reformer, (b) partially preheat the air to the reformer, say up to 200°C, and (c) preheat the LFG slipstream up to 200°C .
- Hot reformat gas must be cooled and over 25,000 BTU/hr is available. The design assumes that we run a counter-flow heat exchanger to further preheat the LFG slipstream from 200°C to 600°C (this absorbs 4300 BTU/hr), to further preheat air from 200°C to 600°C (this absorbs 5900 BTU/hr), and to vaporize water and raise the steam to 600°C (this absorbs 12,500 BTU/hr).

Need LFG Burner for start up: Since start up of the reformer with the above two sources of heat is not feasible, a small burner was included to provide steam and to preheat the reformer catalyst to light-off temperature. About 100 BTU/hr LFG input rate or 10% of the engine fuel input is sufficient for an 80 kW engine generator, according to the calculations (see below).

The heat exchangers must be designed for low pressure drop so as to not reduce engine efficiency.

Need oxidation catalyst.

7.2 System Specifications of BioHALO system

Based on the design considerations outlined above, system specifications were developed for the BioHALO system. The specifications are as follows:

1. IC engine

- Target A/F ratio: 100% excess air.
- Required reformat mix ratio: 10% hydrogen to methane by heating value.
- Spark timing and type of ignition: High energy ignition 20° BTC.
- Intake manifold temperature: Maximum 60°C.
- Intake manifold pressure and type of turbocharger: 0.5 bar boost, Garrett.

2. BioHALO reformer

- Required total flow rate: 900-1000 SCFH for 80 kW.
- Acceptable reformat temperature range 700-900°C at outlet.
- Needed reformat hydrogen concentration 28% minimum by volume.
- System pressure: Atmospheric.
- Duty cycle: 100% operation following engine load.

- Requires heat exchangers to preheat feed streams to 600°C; this avoids excess fuel use or electric power.
- Inlet levels of sulfur-containing gas below 10 ppB to avoid poisoning; requires activated carbon trap or sulfur tolerant catalyst.

3. Nitrogen Oxide Emissions

- As a result of specifications #1 and #2 above, the NO_x emissions will be 0.032 g/bhp-hr (0.10 lb/MW-hr).

4. Exhaust oxidation catalyst (required to meet targets for CO and VOC engine-out emissions).

- Engine exhaust temperature 280°C and flow rate 200 SCFH per kW rated power.
- Engine out exhaust CO 1000 ppm and VOC concentration 100 ppm.
- Conversion efficiency 99% or better.
- Durability 4,000 hours (replace cartridge).

5. Controls

- Control algorithm type: Feedback control off H₂ concentration sensor and exhaust gas oxygen sensor.
- Control outputs for feed stream flow rates and mix of LFG, air and steam to the reformer. Sensor inputs needed include exhaust oxygen, hydrogen content of reformat, total reformat gas flow rate.
- Sensor requirements: flow meters, thermocouples, species concentration.

7.3 Heat and Mass Balance for BioHALO system

In this section the authors describe the detailed heat and mass balances for BioHALO including chemical reactions of the hydrogen generator (reformer) and the heat exchangers. The generic LFG engine generator is assumed to be rated at 80 kW with a heat rate of 10,000 BTU/kWh, which corresponds to 34.1% efficiency. The landfill gas is assumed to consist of 55% methane, 22.5% carbon dioxide, and 22.5% nitrogen for simplicity.

The LFG input stream is split 15% LFG to the reformer and 85% LFG to the main engine (after it is remixed with reformat). The reformer is fed by steam, LFG, and air at stoichiometric ratio corresponding to 200% excess air. All feed streams must be preheated to 600°C and the energy transfers to accomplish this are developed in Table 1. The exhaust gas of the engine post-turbocharger is assumed to be at 280°C and is used to preheat all feed streams to 200°C using a two-stage heat exchanger. The reformat gas exits the autothermal reformer at 800°C and is used to further heat all feed streams to 600°C using the same two-stage counterflow heat

exchanger. The design basis for this is that (a) this design avoids auxiliary heating with a burner or electricity, and (b) a total of 28,000 BTU/hr is available to perform a total of 25,000 BTU/hr of preheat requirements. Only 14% of the available exhaust gas heat is used.

Table 7-1 presents the heat and mass balances. Figure 7-2 shows the two-stage heat exchanger concept (left side is heated by hot reformat; right side is heated by exhaust from engine).




Figure 7-2. Two-Stage Heat Exchanger Concept

Table 7-1. Heat and Mass Balances

Heat and Mass Balance BioHALO 80kW System at 10% hydrogen by energy

Engine	engine power	80 kW					
	efficiency	34.1%					
	Heat rate	10000 BTU/kWh					
	BTU/hr input	800000 BTU/hr					
	CH4 flowrate norm:	877.2 SCF/hr					
	LFG flowrate norm:	1594.9 SCF/hr					
	Air flowrate lean	16736.8 SCF/hr	Assume 2X stoich air				
	Exhaust heat avail	140589.5 BTU/hr	post turbo	550F	288C	0.3 BTU/lbF	
Bypass Reformer	CH4 % bypass	84.9%					
	CH4 bypass	679405.0 BTU/hr	Density lb/SCF				
	CH4 flowrate	745.0 SCF/hr	0.041	30.5 CH4	CO2	N2	
	CO2 flowrate	304.8 SCF/hr	0.112	34.1	55.0%	22.5%	22.5
	N2 flowrate	304.8 SCF/hr	0.072	21.9			
	LFG input	1354.5 SCF/hr	86.6 lb/hr				
	Hydrogen	hydrogen %input	10.0%				
hydrogen input		80000 BTU/hr					
hydrogen flow rate		290.9 SCF/hr					
Reformer Output (ATR)	Equivalence ratio	3.0	Input				
	Temperature input	600 C	output				
	H2	290.9 SCF/hr	O2/CH4	H2O/CH4	CO/CH4	CO2/CH4	H2/CH4
	CO	66.1 SCF/hr	0.667	1.5	0.5	0.5	2
	CO2	120.2 SCF/hr	Density lb/SCF				
	H2O	171.9 SCF/hr	0.005	1.45	3.47 BTU/lbF		
	N2	386.6 SCF/hr	0.072	4.76			
	Total output flow	1035.7 SCF/hr	0.112	13.46	0.3 BTU/lbF		
	Reform heat availal	25229.1 BTU/hr	0.046	7.91			
			0.072	27.83			
			55.42 lb/hr				
			Need to cool 800C to 140C				
Reformer input	CH4	132.2 SCF/hr	31.17 lb/hr air				
	H2O	198.3 SCF/hr					
	O2	88.2 SCF/hr					
	N2 in air	332.5 SCF/hr					
	N2 in LFG	54.1 SCF/hr					
	CO2 in LFG	54.1 SCF/hr					
	Total	859.4 SCF/hr					
			Preheat w/ Exhaust Hot reformat				
Preheat Required	H2O to steam 600C	14188 BTU/hr	1500				
	Air preheat 600C	8462 BTU/hr	2538				
	LFG preheat 600C	6216 BTU/hr	1865				
	Total preheat req	28865 BTU/hr	5903 22962				
LFG Start up Burner Input	CH4	99.2 SCF/hr	4% of avail exhaust heat				
	CO2 In LFG	40.6 SCF/hr	91% of avail reformat heat				
	N2 in LFG	40.6 SCF/hr	11.3% (energy penalty to preheat steam)				
	N2 in air	747.8 SCF/hr					
	O2	198.3 SCF/hr					
	Total	1126.4 SCF/hr					
LFG Burner Output	CO2	99.2 SCF/hr	Note: Add Air at 420 SCFH; add LFG at 24 (During start up)				
	N2	788.3 SCF/hr					
	H2O	198.3 SCF/hr					
	Total	1085.9 SCF/hr					

Schematic drawings and Equipment List for BioHALO system

7.3.1. Schematic and P&IDs

The schematic for the BioHALO conceptual design is provided below as Figure 7-3.




Figure 7-3. Schematic for the BioHALO Conceptual Design

7.3.2. Equipment List

The key components are listed in Table 7-2 below.

Table 7-2. Key Components

Component	Description; typical suppliers
Engine 50kW to 500kW	Ford, Gauscor, Deere, Waukesha landfill gas engine; turbocharged; high-energy spark for lean operation
Generator, Enclosure and Controls	LFG packager
Autothermal Reformer with subsystem sensors and controls	1000 SCFH input for 80 kW power; capable of 200% excess fuel operation; Unitel or equivalent
Special Two-Stage Heat exchanger	Gas-to-gas counterflow 20°C to 800°C
LFG Burner with air blower and flame sensors for start up	North American, other
In-line gas mixing plenum	LFG packager
Sulfur adsorption trap	Activated carbon or equivalent
Oxidation catalyst	Gas engine oxidation catalyst typical of industrial or off-road usage; Donaldson or equivalent.
Water pump and injector spray nozzles for steam	

Example of LFG Engine Gen Set: A typical 78 kW engine/ generator is the Hess Microgen generator set comprised of a Ford Power Products Model WSG-1068 V10 engine powering an induction generator with switchgear allowing interconnection to the grid. This set is designed to be installed at a landfill site and grid connected in parallel with the site electrical load. The engine was a 6.8 L natural gas fueled engine rated at 78 kW (105 hp) at 1,800 rpm using natural gas. A photograph of the side view of the LFG package with side door removed is provided in Figure 7-4. Table 7-3 gives the specifications.



Figure 7-4. Side View of Engine/Generator
Photo Credit: TIAX LLC

Table 7-3. Ford Power Products WSG-1068 Specifications

Specification	
Engine type	V10
Bore and Stroke, mm (in)	90.2 x 105.8 (3.55 x 4.17)
Displacement, L (CID)	6.8 (415)
Compression ratio	9:1
Net weight, kg (lb)	290 (640)
Ignition system	Coil on Plug
Rating on NG	78 kW (105 HP) @ 1800 RPM

7.4 Start-up and Operating Strategies for BioHALO System

A typical start up would proceed with the following steps:

1. The engine would be started and idled until the coolant temperature reached approximately 50°C.

2. The generator would then be connected up to the electrical grid, bringing the engine speed to 1800 rpm (at rated speed, no load).
3. The throttle would be opened, and fuel would automatically be added by the Motec system until a point of about 50% power was reached. The engine would be kept at this point until the oil and coolant temperatures reached the appropriate operating levels. During this time, the engine would be operated on 100% landfill gas.
4. The first step to starting hydrogen flow is to start the burner to preheat the reformer. About 10% LFG flow is turned on with stoichiometric air, and ignition is activated. The hot products heat the reformer catalyst.
5. When the reformer reaches 600°C, the engine power is raised to 100% to provide exhaust heat, and the LFG supply to the reformer is opened with the air flow corresponding to 200% excess fuel.
6. The water flow for steam is initiated to the heat exchangers, and when the steam pressure builds up, the reformer output gases are monitored for temperature and hydrogen content. The flows are adjusted to the correct mixture.
7. At this point, hydrogen would be added to the engine at the appropriate level by remixing reformat and LFG, and boost air is adjusted with the waste gate to lean out the mixture to 100% excess air. The desired operating point is now set.

Once the BioHALO system reaches steady-state, as evidenced by the emissions and the combustion stability, operation can commence at low NO_x.

Auxiliary active thermal control (if needed): Clearly during the reformer start up (steps 4, 5, 6), the correct temperatures must be reached at the reformer inlet and exit, while sufficient cooling must be applied to keep fuel/air mixture at 40°C in the inlet manifold. Provision for auxiliary heating of the reformer is made by using a small gas-fired burner.

The burner can be used on unusually cold days or during temperature upsets to control the process.

7.5 Detailed Design of BioHALO System

7.5.1 Assembly Drawing of BioHALO Engine-Generator Reformer System

Figure 7-5 provides the assembly drawing of the BioHALO system based on a typical 75 kW engine/ generator, the Hess Microgen generator set, composed of a Ford Power Products Model WSG-1068 V10 engine powering an induction generator with switchgear allowing interconnection to the grid. This set is designed to be installed at a landfill site and grid connected in parallel with the site electrical load. The engine was a 6.8 L natural gas-fueled engine rated at 78 kW (105 hp) at 1,800 rpm using natural gas. A photograph of the side view of the LFG package with side door removed is provided in Figure 2.




Figure 7-5. Assembly Drawing of BioHALO System

7.5.2. Illustration of Reformers (Commercially Available)

Figure 7-6 shows two commercially available reformers (Intelligent Energy and Aspen Products Group), both in the 5-10 kW size range suitable for BioHALO. The detailed drawings for these are proprietary. These two reformer products are stand-alone systems designed to produce ultra-high purity hydrogen for fuel cells from various fuels. The BioHALO application calls for a much simpler reformer resembling an automotive three-way catalyst, since (a) the raw reformat gas can be used directly by the engine without CO removal or other post-treatment, and (b) the feed gas is mainly methane and inerts (LFG). Therefore, either of these commercially available reformers could be simplified and adapted for the specified BioHALO autothermal process, which operates at equivalence ratio 3:1. Both illustrations include sulfur removal traps and extensive plumbing, not all of which may be necessary.



Figure 7-6. Commercially Available Reformers From Aspen Products Group (left) and Intelligent Energy (right)

Photo Credit: TIAX LLC

7.5.3. Heat Exchanger Subsystem Drawing

The hot reformat gas section of the heat exchanger module for an 80 kW BioHALO system is shown schematically below in. This unit is sized at 12 inches length by 16 square inches. Insulation must be added.




Figure 7-7. Heat Exchanger Module - Hot Section

The exhaust gas section of the heat exchanger module is sized at approximately 4 inches square by 18 inches long for both air preheat and LFG preheat. This section also vaporizes water into steam. The tube-in-shell cross-flow design is specified as shown below in Figure 7-8.





Figure 7-8. Heat Exchanger Module- Exhaust Section

Photo Credit: TIAX LLC

These two units are packaged together in the heat exchanger module 36 inches long and 12 inches wide, including insulation.

7.5.4. Engine Installation Drawing

The typical engine for an 80 kW BioHALO system is a Ford V-10 natural gas engine converted for landfill gas operation. Figure 7-9 shown below is the installation drawing for the LFG engine.



7.5.5. Turbocharger Drawing

The typical turbocharger for an 80 kW BioHALO system is a Garrett model GT-32 shown below in Figure 7-10. The compressor map showing air flow and pressure ratio (and efficiency) is shown in Figure 7-11.




Figure 7-10. Turbocharger




Figure 7-11. Compressor Map for Turbocharger for 80 kW BioHALO

7.5.6. Illustration of Oxidation Catalyst (Commercially Available)

In Figure 7-12 we show a commercially available oxidation catalyst (available from Miretek, Johnson-Matthey, and others) in the 50-100 kW engine size range suitable for BioHALO. The detailed drawings for this are proprietary.



Figure 7-12. Oxidation Catalyst

8.0 Equipment and Purchased Component Specifications

Based on the Conceptual Design reported as Task 2.4, the authors developed detailed specifications for the equipment and purchased components. The specifications are as follows:

8.1 Engine Generator Set

The generic LFG engine generator is assumed to be rated at 50 to 500 kW (80 kW is typical) with a heat rate of 10,000 BTU/kWh, which corresponds to 34.1% efficiency. The landfill gas is assumed to consist of 55% methane, 22.5% carbon dioxide, and 22.5% nitrogen or equivalent heating value. Table 8-1 lists the specifications.

- Target A/F ratio: 100% excess air.
- Required reformat mix ratio: 10% hydrogen to methane by heating value.
- Spark timing and type of ignition: High energy ignition 20° BTC.
- Intake manifold temperature: Maximum 60°C.

Table 8-1. Ford Power Products WSG-1068 Specifications

Specification	
Engine type	V10
Bore and Stroke, mm (in)	90.2 x 105.8 (3.55 x 4.17)
Displacement, L (CID)	6.8 (415)
Compression ratio	9:1
Net weight, kg (lb)	290 (640)
Ignition system	Coil on Plug
Rating on NG	78 kW (105 HP) @ 1800 RPM

8.2 Turbocharger and Other Engine Modifications for Lean Burn Operation on LFG

The standard engine must be modified to run at 100% excess air. This includes a turbocharger (Garrett GT32 or similar) to raise intake manifold pressure to 0.5 bar boost. Also the authors specify a high-energy spark system for lean operation. Finally, the air-fuel ratio must be the same for all cylinders within 1% to allow lean burn operation at low emissions. Therefore, a gas fuel port injection system is preferred for ultralean operation (the system must allow individual

cylinder A/F ratio adjustment). If a carburetor is used, the intake manifold mixing must provide for the 1% maximum variation specified above.

8.3 Auto-Thermal Reformer

The auto-thermal reformer must be capable of operating at equivalence ratio 3:1 (200% excess fuel). This reformer can be designed around a low-cost catalyst similar to an automotive three-way catalyst and is slightly exothermic (adiabatic temperature rise of about 200°C between inlet and outlet). For catalyst light off, the inlet gases must be at 600°C.

- Required total flow rate: 900-1000 SCFH for 80kW.
- Acceptable reformat temperature range 700-900°C.
- Needed reformat hydrogen concentration 28% minimum.
- System pressure: Atmospheric.
- Duty cycle: 100% operation following engine load.
- Inlet levels of sulfur-containing gas below 10 ppB to avoid poisoning; requires activated carbon trap or similar.

8.4 Heat Exchanger Module

The BioHALO system requires a heat exchanger module to preheat both air and LFG going to the reformer to 600°C. Three gas inlet streams must be preheated to enter the reformer at 600°C (about 1100°F); the LFG itself, the water vapor (steam) required, and the air supply to the reformer. The module must be designed to extract heat from two sources of hot gas (sequentially):

In the first section, the heat exchanger module uses exhaust gas that exits the turbocharger intercooler at about 550°F (250°C). The exhaust gas section of the module (a) preheats water to 100°C before creating steam for the reformer, (b) partially preheats the air to the reformer up to 200°C, and (c) preheats the LFG slipstream up to 200°C.

In the second section, hot reformat gas is run **through** a counter-flow heat exchanger to further preheat the LFG slipstream from 200°C to 600°C, to further preheat air from 200°C to 600°C, and to vaporize water and raise the steam to 600°C.

The heat exchanger module is a custom design but uses conventional off-the-shelf materials as shown above in Figures 4 and 5.

8.5 Mixing Plenum, Air Blower, and Burner for Start-Up

For startup, a small burner is required to provide steam and to preheat the reformer catalyst to light-off temperature. About 100,000 BTU/hr LFG input rate or 10% of the engine fuel input is

sufficient to start up the reformer system for an 80 kW engine generator. A mixing plenum tolerant of 600°C operation is provided because the three input streams to the reformer must be premixed (steam, air, and LFG). Also the air blower driving the air supply to the reformer is specified at 1000 SCF/hr and 8 inch water pressure.

8.6 Exhaust Oxidation Catalyst (Required to Meet Targets for CO and VOC Engine-Out Emissions)

The oxidation catalyst is a conventional off-the-shelf automotive or industrial unit with the following specifications:

- Engine exhaust temperature 280°C and flow rate 200 SCFH per kW rated power.
- Engine out exhaust THC 2000 ppm and CO concentration 700 ppm.
- Conversion efficiency 99% or better.
- Durability 4,000 hours (replace cartridge).
- Pressure drop 1 inch water maximum.

8.7 Controls

The control system is specified to follow engine load while controlling engine excess air and adjusting LFG slipstream flow rate to produce reformat flow at 10% hydrogen ratio by energy. The PID control loop holds the oxygen mole fraction at 10% plus or minus 0.2%. The system has the following additional specifications:

- Control algorithm type: based off H₂ concentration sensor and exhaust gas oxygen sensor.
- Control outputs and sensors and actuators are specified in Table 8-3 below.
- Response time (from 10% to 90% load) must be less than 30 engine cycles corresponding to 2 seconds at 1800 RPM.
- Reformer outlet temperature is set at maximum 850°C with shutoff of LFG slipstream if that temperature is exceeded for 5 seconds.
- If oil temperature exceeds 98°C, the LFG is shut off, and the engine is brought to idle for 5 minutes, then shut down and generate error message.
- If cooling water temperature exceeds 95°C same procedure.
- Emergency stops are provided to shut down LFG fuel valve and ignition system.
- System must be capable of data logging all key parameters for 200 hours at 5 minute intervals; with fast mode to capture shutdown record at 1 second intervals.
- System must have Ethernet protocol for remote access .

- If engine speed exceeds 1850 RPM, then shut off fuel valve.
- System must have capability for standard values input for PID control loop.

8.8 Bill of Materials

Table 8-2 provides a bill of materials of all critical purchased subsystems.

Table 8-2. Bill of Materials

Component	Description / Typical Suppliers	Estimated Cost, 80 kW system
Engine generator 50kW to 500kW, with enclosure and controls	LFG Packager such as Gauscor, Waukesha, Deutz or Caterpillar. Includes natural gas engine capable of operation on LFG. Cost estimate based on \$540/kW without installation	\$43,000
Turbocharger and other engine conversion components for lean burn LFG operation	Garrett model GT32 turbocharger or similar at \$11 per kW.	\$900
	High-energy spark system for lean operation.	\$2000
	Gas fuel port injection system preferred for ultralean operation (allows individual cylinder A/F ratio adjustment). IMPCO or Woodward carburetor valve is an option if uniform cylinder mix is feasible.	\$4000
Autothermal reformer with subsystem sensors and controls	1000 SCFH input for 80 kW power; capable of 200% excess fuel operation; Intelligent Energy, Aspen or equivalent	\$8000
Special two-stage heat exchanger	Gas-to-gas counterflow 20°C to 800°C according to drawing in this report	\$2000
LFG Burner 100,000 BTU/hr with 1000 SCFH air blower at 8 in. wc and mixing plenum	Coen, North American, or equivalent.	\$1000
	Blower	\$500
	Mixing Plenum, 600°C tolerant	\$500
Sulfur and siloxane adsorption trap	Activated carbon or equivalent	\$2000
Oxidation catalyst	Gas engine oxidation catalyst typical of industrial or off-road usage; suppliers include Johnson-Matthey, Donaldson or equivalent.	\$500
Water pump and injector spray nozzles for steam		\$200
Solenoid valves (2)	Asco or equivalent	\$400
Ethernet connection and data logging		\$500
Piping and fittings		\$100

8.9 Description of Start-Up and Operating Controls Functions

8.9.1 Start-Up Control Sequence

The standard controls (sensors, actuators, and control logic) shown in the P&ID schematic (see below) will be used to replicate electronically the following steps for start up and control:

1. The engine would be started (relay to starter solenoid opened until RPM reaches 300) and idled until the coolant temperature reached approximately 50°C.
2. The generator would then be connected to the electrical grid (contactor closed), bringing the engine speed to 1800 rpm (at rated speed, no load).
3. The throttle would be opened, and fuel would automatically be added by the IMPCO fuel valve actuator until a point of about 50% power was reached. The engine would be kept at this point until the oil and coolant temperatures reached the appropriate operating levels. During this time, the engine would be operated on 100% landfill gas.
4. The first step to starting hydrogen flow is to start the burner to preheat the reformer. (The LFG reformat valve is opened, and the blower relay activated). About 10% LFG flow is turned on with stoichiometric air, and ignition is activated. The hot products heat the reformer catalyst.
5. When the reformer reaches 600°C, the engine power is raised to 100% (throttle opened to “wide open”) to provide exhaust heat and the LFG supply to the reformer is opened and the air flow corresponding to 200% excess fuel.
6. The water flow for steam is initiated (water pump relay activated) to the heat exchangers, and when the steam pressure builds up, the reformer output gases are monitored for temperature and hydrogen content. The flows are adjusted using the LFG reformat control valve to the correct mixture.
7. At this point, hydrogen would be added to the engine at the appropriate level, and the waste gate valve at the turbocharger is adjusted to initiate boost and lean out the mixture to 100% excess air. The desired operating point is now set.

Table 8-3 provides a list of the critical sensors, actuators and controls needed for BioHALO. These sensors are shown in the P&ID schematic in Figure 10.

Table 8-3. BioHALO Control System Specifications

Sensor or Component	Input / Output Mode	Comments
Hall Effect Camshaft Sensor	TTL input	Reference signal for engine control, provides engine speed
Hall Effect Crankshaft Sensor	TTL input	Timing signal for engine control
Universal Exhaust Gas Oxygen Sensor (UEGO)	Analog voltage input	Allows for closed loop fuel control
Coils (x 10)	TTL output	Spark signal to coil igniter
Line Voltage (x3)	Analog voltage input	Monitors electrical grid connection
Line Current (x 3)	Analog voltage input	Monitors electrical grid connection
Line Phase (x 3)	Analog voltage input	Monitors electrical grid connection
Generator Power	Analog voltage input	Monitors electrical grid connection
Emergency Stop	Digital output	Shuts down system
LFG Supply Solenoid	Digital output	Fuel Supply Valve
Generator T/C	Analog voltage input	Monitors Generator temperature

Sensor or Component	Input / Output Mode	Comments
Waste Gate Actuator	PWM signal	Adjusts turbocharger Wastegate
LFG Flowmeter and Valve	0-10 V Analog voltage input and PWM	Monitor and adjust LFG flow rate
Reformate LFG Flowmeter	0-10 V analog voltage input	Monitor LFG flow to reformer
Activated Carbon Trap Differential Pressure Sensor	0-10 V analog voltage input	Monitors clogging of LFG filter
Fuel Valve (x 10)	TTL output	Send signal to fuel valve
Manifold Absolute Pressure Sensor	0-5 V analog voltage input	Boost pressure input for engine control
Reformer T/c	0-5 V analog voltage input	Temperature monitoring o reformer
H ₂ Sensor	0-5 V analog voltage input	Output monitoring of reformer
Oil Pressure Sensor	0-5 V Analog voltage input	Monitors engine oil pressure
Oil Temperature Sensor	RRTD input	Monitors engine coolant pressure
Water Tank Level Sensor	0-10 V analog voltage input	Monitors level of water
System T/C (x 6)	Analog voltage input	Process flow temperature monitoring
Blower Power	TTL output	Activates relay to turn blower on/of
Water Pump Power	TTL output	Activates relay to turn water pump on/off
Coolant Temperature Sensor	0-5 V analog voltage input	Monitors engine coolant temperature
Throttle Position sensor	PWM signal	Position of engine throttle

8.10

8.11 Mechanical, Piping, and Electrical Connections

The drawing packages for the mechanical, piping, and electrical grid connections are provided below.



CERTIFICATION DATA SHEET

CUSTOMER: Hess

CUSTOMER P.O.

MODEL NO: 365TTDS4641

MEMO ORDER NO:

CONN. DIAGRAM:

ADAPTION #:

OUTLINE:

WK²: 15.5 lb-ft²

WINDING: T3654166

TYPICAL MACHINE DATA

KW	SYNC RPM	FL RPM	FRAME	ENCLOS	OVERSPEED RPM	HIGH VOLT RESISTANCE
80	1800	1830	365	ODP	2250	0.105 ohm

PH	HZ	VOLTS	FL AMPS	Magnetizing (NL) AMPS @ Hi Volts	DUTY	INSUL	S.F.	AMB (°C)
3	60	208-240 / 416-480	270-232 / 135-116	27 - 33	CONT	F	1.0	40

NOMINAL EFF (%)			POWER FACTOR (%)			TQ @ FULL VOLTS (LB-FT)		
FL	3/4 LD	1/2 LD	FL	3/4 LD	1/2 LD	FL	LR	BREAKAWAY
92.4	93.0	93.6	83.0	81.5	76.5	333	540	1000

EQUIVALENT CIRCUIT REACTANCES (PER UNIT) $Z_{ref} = 2.662$ ohms

Stator Resistance R1	Rotor Resistance R2	Stator Reactance X1	Rotor Reactance X2	Magnetizing Reactance Xm	Transient Reactance X'd	Sub-Transient (short ckt) Reactance X''d
0.030	.0155	0.110	.142	3.039	0.250	0.140

FAULT CURRENT, TIME CONSTANTS (SECOND)


Fault Current AMPS	SHORT CKT T'd (sec)	OPEN CKT T'do (sec)
650	0.545	.022

SUPPLEMENTAL INFORMATION

1) 26 KVAR's at No Load; 53.5 KVAR's at 80 KW Load

CERTIFIED BY: Earl Babbitts

DATE: 21-AUGUST-03



MoTeC

Title **M800 Wiring Loom (REV B)**

Date 02/09/2002

Drawn ST

App AD

Products ECU

Sheet No

1 of 1

Drawing No

L07

M-3410 Typical Connection Diagram




Figure 6 Typical Three-Line Diagram—Intertie Protection

M-3410 Intertie/Generator Protection Relay

External Connections

M-3410 external connection points are illustrated in Figure 1, External Connections, below.

Specification is subject to change without notice.




Figure 1 External Connections

M-3410 Intertie/Generator Protection Relay




Figure 2 Mounting Dimensions

M-3410 Intertie/Generator Protection Relay

M-3410 Typical Connection Diagram




Figure 3 Typical One-Line Diagram-Generator Protection

M-3410 Typical Connection Diagram




Figure 4 Typical One-Line Diagram—Intertie Protection

M-3410 Typical Connection Diagram






Figure 5 Typical Three-Line Diagram—Generator Protection




REVISIONS	
1	"
2	"

- [illegible]

SCALE: 1/4" = 1'-0"	 13 INDUSTRIAL PARKWAY CHANDLER CITY, INDIANA 46501 (773) 884-1000 (773) 884-5177 FAX www.hessmicrogen.com	DESIGNED BY: Herb Clowers	DATE: 8-14-03	INDUCTION METHANE 80KW COGEN 1603 HWY. 20 MARYSVILLE, CA. 95901	ELECTRICAL GENERAL NOTES	1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81 82 83 84 85 86 87 88 89 90 91 92 93 94 95 96 97 98 99 100 101 102 103 104 105 106 107 108 109 110 111 112 113 114 115 116 117 118 119 120 121 122 123 124 125 126 127 128 129 130 131 132 133 134 135 136 137 138 139 140 141 142 143 144 145 146 147 148 149 150 151 152 153 154 155 156 157 158 159 160 161 162 163 164 165 166 167 168 169 170 171 172 173 174 175 176 177 178 179 180 181 182 183 184 185 186 187 188 189 190 191 192 193 194 195 196 197 198 199 200 201 202 203 204 205 206 207 208 209 210 211 212 213 214 215 216 217 218 219 220 221 222 223 224 225 226 227 228 229 230 231 232 233 234 235 236 237 238 239 240 241 242 243 244 245 246 247 248 249 250 251 252 253 254 255 256 257 258 259 260 261 262 263 264 265 266 267 268 269 270 271 272 273 274 275 276 277 278 279 280 281 282 283 284 285 286 287 288 289 290 291 292 293 294 295 296 297 298 299 300 301 302 303 304 305 306 307 308 309 310 311 312 313 314 315 316 317 318 319 320 321 322 323 324 325 326 327 328 329 330 331 332 333 334 335 336 337 338 339 340 341 342 343 344 345 346 347 348 349 350 351 352 353 354 355 356 357 358 359 360 361 362 363 364 365 366 367 368 369 370 371 372 373 374 375 376 377 378 379 380 381 382 383 384 385 386 387 388 389 390 391 392 393 394 395 396 397 398 399 400 401 402 403 404 405 406 407 408 409 410 411 412 413 414 415 416 417 418 419 420 421 422 423 424 425 426 427 428 429 430 431 432 433 434 435 436 437 438 439 440 441 442 443 444 445 446 447 448 449 450 451 452 453 454 455 456 457 458 459 460 461 462 463 464 465 466 467 468 469 470 471 472 473 474 475 476 477 478 479 480 481 482 483 484 485 486 487 488 489 490 491 492 493 494 495 496 497 498 499 500 501 502 503 504 505 506 507 508 509 510 511 512 513 514 515 516 517 518 519 520 521 522 523 524 525 526 527 528 529 530 531 532 533 534 535 536 537 538 539 540 541 542 543 544 545 546 547 548 549 550 551 552 553 554 555 556 557 558 559 560 561 562 563 564 565 566 567 568 569 570 571 572 573 574 575 576 577 578 579 580 581 582 583 584 585 586 587 588 589 590 591 592 593 594 595 596 597 598 599 600 601 602 603 604 605 606 607 608 609 610 611 612 613 614 615 616 617 618 619 620 621 622 623 624 625 626 627 628 629 630 631 632 633 634 635 636 637 638 639 640 641 642 643 644 645 646 647 648 649 650 651 652 653 654 655 656 657 658 659 660 661 662 663 664 665 666 667 668 669 670 671 672 673 674 675 676 677 678 679 680 681 682 683 684 685 686 687 688 689 690 691 692 693 694 695 696 697 698 699 700 701 702 703 704 705 706 707 708 709 710 711 712 713 714 715 716 717 718 719 720 721 722 723 724 725 726 727 728 729 730 731 732 733 734 735 736 737 738 739 740 741 742 743 744 745 746 747 748 749 750 751 752 753 754 755 756 757 758 759 760 761 762 763 764 765 766 767 768 769 770 771 772 773 774 775 776 777 778 779 780 781 782 783 784 785 786 787 788 789 790 791 792 793 794 795 796 797 798 799 800 801 802 803 804 805 806 807 808 809 810 811 812 813 814 815 816 817 818 819 820 821 822 823 824 825 826 827 828 829 830 831 832 833 834 835 836 837 838 839 840 841 842 843 844 845 846 847 848 849 850 851 852 853 854 855 856 857 858 859 860 861 862 863 864 865 866 867 868 869 870 871 872 873 874 875 876 877 878 879 880 881 882 883 884 885 886 887 888 889 890 891 892 893 894 895 896 897 898 899 900 901 902 903 904 905 906 907 908 909 910 911 912 913 914 915 916 917 918 919 920 921 922 923 924 925 926 927 928 929 930 931 932 933 934 935 936 937 938 939 940 941 942 943 944 945 946 947 948 949 950 951 952 953 954 955 956 957 958 959 960 961 962 963 964 965 966 967 968 969 970 971 972 973 974 975 976 977 978 979 980 981 982 983 984 985 986 987 988 989 990 991 992 993 994 995 996 997 998 999 1000 1001 1002 1003 1004 1005 1006 1007 1008 1009 1010 1011 1012 1013 1014 1015 1016 1017 1018 1019 1020 1021 1022 1023 1024 1025 1026 1027 1028 1029 1030 1031 1032 1033 1034 1035 1036 1037 1038 1039 1040 1041 1042 1043 1044 1045 1046 1047 1048 1049 1050 1051 1052 1053 1054 1055 1056 1057 1058 1059 1060 1061 1062 1063 1064 1065 1066 1067 1068 1069 1070 1071 1072 1073 1074 1075 1076 1077 1078 1079 1080 1081 1082 1083 1084 1085 1086 1087 1088 1089 1090 1091 1092 1093 1094 1095 1096 1097 1098 1099 1100 1101 1102 1103 1104 1105 1106 1107 1108 1109 1110 1111 1112 1113 1114 1115 1116 1117 1118 1119 1120 1121 1122 1123 1124 1125 1126 1127 1128 1129 1130 1131 1132 1133 1134 1135 1136 1137 1138 1139 1140 1141 1142 1143 1144 1145 1146 1147 1148 1149 1150 1151 1152 1153 1154 1155 1156 1157 1158 1159 1160 1161 1162 1163 1164 1165 1166 1167 1168 1169 1170 1171 1172 1173 1174 1175 1176 1177 1178 1179 1180 1181 1182 1183 1184 1185 1186 1187 1188 1189 1190 1191 1192 1193 1194 1195 1196 1197 1198 1199 1200 1201 1202 1203 1204 1205 1206 1207 1208 1209 1210 1211 1212 1213 1214 1215 1216 1217 1218 1219 1220 1221 1222 1223 1224 1225 1226 1227 1228 1229 1230 1231 1232 1233 1234 1235 1236 1237 1238 1239 1240 1241 1242 1243 1244 1245 1246 1247 1248 1249 1250 1251 1252 1253 1254 1255 1256 1257 1258 1259 1260 1261 1262 1263 1264 1265 1266 1267 1268 1269 1270 1271 1272 1273 1274 1275 1276 1277 1278 1279 1280 1281 1282 1283 1284 1285 1286 1287 1288 1289 1290 1291 1292 1293 1294 1295 1296 1297 1298 1299 1300 1301 1302 1303 1304 1305 1306 1307 1308 1309 1310 1311 1312 1313 1314 1315 1316 1317 1318 1319 1320 1321 1322 1323 1324 1325 1326 1327 1328 1329 1330 1331 1332 1333 1334 1335 1336 1337 1338 1339 1340 1341 1342 1343 1344 1345 1346 1347 1348 1349 1350 1351 1352 1353 1354 1355 1356 1357 1358 1359 1360 1361 1362 1363 1364 1365 1366 1367 1368 1369 1370 1371 1372 1373 1374 1375 1376 1377 1378 1379 1380 1381 1382 1383 1384 1385 1386 1387 1388 1389 1390 1391 1392 1393 1394 1395 1396 1397 1398 1399 1400 1401 1402 1403 1404 1405 1406 1407 1408 1409 1410 1411 1412 1413 1414 1415 1416 1417 1418 1419 1420 1421 1422 1423 1424 1425 1426 1427 1428 1429 1430 1431 1432 1433 1434 1435 1436 1437 1438 1439 1440 1441 1442 1443 1444 1445 1446 1447 1448 1449 1450 1451 1452 1453 1454 1455 1456 1457 1458 1459 1460 1461 1462 1463 1464 1465 1466 1467 1468 1469 1470 1471 1472 1473 1474 1475 1476 1477 1478 1479 1480 1481 1482 1483 1484 1485 1486 1487 1488 1489 1490 1491 1492 1493 1494 1495 1496 1497 1498 1499 1500 1501 1502 1503 1504 1505 1506 1507 1508 1509 1510 1511 1512 1513 1514 1515 1516 1517 1518 1519 1520 1521 1522 1523 1524 1525 1526 1527 1528 1529 1530 1531 1532 1533 1534 1535 1536 1537 1538 1539 1540 1541 1542 1543 1544 1545 1546 1547 1548 1549 1550 1551 1552 1553 1554 1555 1556 1557 1558 1559 1560 1561 1562 1563 1564 1565 1566 1567 1568 1569 1570 1571 1572 1573 1574 1575 1576 1577 1578 1579 1580 1581 1582 1583 1584 1585 1586 1587 1588 1589 1590 1591 1592 1593 1594 1595 1596 1597 1598 1599 1600 1601 1602 1603 1604 1605 1606 1607 1608 1609 1610 1611 1612 1613 1614 1615 1616 1617 1618 1619 1620 1621 1622 1623 1624 1625 1626 1627 1628 1629 1630 1631 1632 1633 1634 1635 1636 1637 1638 1639 1640 1641 1642 1643 1644 1645 1646 1647 1648 1649 1650 1651 1652 1653 1654 1655 1656 1657 1658 1659 1660 1661 1662 1663 1664 1665 1666 1667 1668 1669 1670 1671 1672 1673 1674 1675 1676 1677 1678 1679 1680 1681 1682 1683 1684 1685 1686 1687 1688 1689 1690 1691 1692 1693 1694 1695 1696 1697 1698 1699 1700 1701 1702 1703 1704 1705 1706 1707 1708 1709 1710 1711 1712 1713 1714 1715 1716 1717 1718 1719 1720 1721 1722 1723 1724 1725 1726 1727 1728 1729 1730 1731 1732 1733 1734 1735 1736 1737 1738 1739 1740 1741 1742 1743 1744 1745 1746 1747 1748 1749 1750 1751 1752 1753 1754 1755 1756 1757 1758 1759 1760 1761 1762 1763 1764 1765 1766 1767 1768 1769 1770 1771 1772 1773 1774 1775 1776 1777 1778 1779 1780 1781 1782 1783 1784 1785 1786 1787 1788 1789 1790 1791 1792 1793 1794 1795 1796 1797 1798 1799 1800 1801 1802 1803 1804 1805 1806 1807 1808 1809 1810 1811 1812 1813 1814 1815 1816 1817 1818 1819 1820 1821 1822 1823 1824 1825 1826 1827 1828 1829 1830 1831 1832 1833 1834 1835 1836 1837 1838 1839 1840 1841 1842 1843 1844 1845 1846 1847 1848 1849 1850 1851 1852 1853 1854 1855 1856 1857 1858 1859 1860 1861 1862 1863 1864 1865 1866 1867 1868 1869 1870 1871 1872 1873 1874 1875 1876 1877 1878 1879 1880 1881 1882 1883 1884 1885 1886 1887 1888 1889 1890 1891 1892 1893 1894 1895 1896 1897 1898 1899 1900 1901 1902 1903 1904 1905 1906 1907 1908 1909 1910 1911 1912 1913 1914 1915 1916 1917 1918 1919 1920 1921 1922 1923 1924 1925 1926 1927 1928 1929 1930 1931 1932 1933 1934 1935 1936 1937 1938 1939 1940 1941 1942 1943 1944 1945 1946 1947 1948 1949 1950 1951 1952 1953 1954 1955 1956 1957 1958 1959 1960 1961 1962 1963 1964 1965 1966 1967 1968 1969 1970 1971 1972 1973 1974 1975 1976 1977 1978 1979 1980 1981 1982 1983 1984 1985 1986 1987 1988 1989 1990 1991 1992 1993 1994 1995 1996 1997 1998 1999 2000 2001 2002 2003 2004 2005 2006 2007 2008 2009 2010 2011 2012 2013 2014 2015 2016 2017 2018 2019 2020 2021 2022 2023 2024 2025 2026 2027 2028 2029 2030 2031 2032 2033 2034 2035 2036 2037 2038 2039 2040 2041 2042 2043 2044 2045 2046 2047 2048 2049 2050 2051 2052 2053 2054 2055 2056 2057 2058 2059 2060 2061 2062 2063 2064 2065 2066 2067 2068 2069 2070 2071 2072 2073 2074 2075 2076 2077 2078 2079 2080 2081 2082 2083 2084 2085 2086 2087 2088 2089 2090 2091 2092 2093 2094 2095 2096 2097 2098 2099 2100 2101 2102 2103 2104 2105 2106 2107 2108 2109 2110 2111 2112 2113 2114 2115 2116 2117 2118 2119 2120 2121 2122 2123 2124 2125 2126 2127 2128 2129 2130 2131 2132 2133 2134 2135 2136 2137 2138 2139 2140 2141 2142 2143 2144 2145 2146 2147 2148 2149 2150 2151 2152 2153 2154 2155 2156 2157 2158 2159 2160 2161 2162 2163 2164 2165 2166 2167 2168 2169 2170 2171 2172 2173 2174 2175 2176 2177 2178 2179 2180 2181 2182 2183 2184 2185 2186 2187 2188 2189 2190 2191 2192 2193 2194 2195 2196 2197 2198 2199 2200 2201 2202 2203 2204 2205 2206 2207 2208 2209 2210 2211 221
---------------------	--	---------------------------	---------------	---	-----------------------------	--

Hess 250/375



Right Side


Front

Left Side

Rear

Top

Hess 140/200



MATERIAL:

FINISH:

UNSPECIFIED TOLERANCES	
± .03	FRAC
± .015	CHK
± .010	APP
± .3°	ANGLE
BREAK ALL SHARP EDGES	

ENG. DWG

DATE

PART NO.

SCALE: 72:1

SHEET 1 OF 1

SIZE A

REV

TITLE: 140/200/250/375 Cabinet Layout



12 Industrial Parkway
Corson City, NV 89706
(775)864-1000
(775)864-3417 FAX
www.hessmicrogen.com

9.0 Commercialization Outlook and Technology Transfer Activities

9.1 Technical and Performance Attributes of BioHALO

As can be seen from Table 9-1, the BioHALO technology converts the least expensive, most efficient, and widely accepted prime mover for LFG to energy applications, and, with the addition of a reformer, makes it environmentally superior to today's microturbine. Meeting these goals and commercializing BioHALO will have a large environmental impact. Table 9-1 presents the annual emissions from a landfill under three operating scenarios. Scenario A is an uncontrolled landfill venting all the landfill gas and purchasing 71 kW of power from a BACT-equipped central station power plant. Scenario B has the landfill flaring its LFG and purchasing 71 kW of power. In Scenario C, the landfill has installed the BioHALO IC engine system. In Scenarios A and B, the LFG (vented or flared) emissions assume an amount of LFG equivalent to what would be consumed by a 71 kW BioHALO IC engine. Installing a 71 kW BioHALO IC engine at an uncontrolled landfill could eliminate 2,700 tons of greenhouse gas (GHG) emissions each year with only a 25 lb/yr increase in NO_x. Diverting enough flared LFG to power a 71 kW BioHALO IC engine eliminates 263 tons/yr of GHG and reduces NO_x emissions by 212 lb/yr. If 200 kW engines were installed at 100 landfills, the impact on GHG and criteria pollutant emissions would be significant.

Table 9-1. Emission Benefit of the BioHALO IC Engine for LFG to Electricity Applications

	tons/yr			lb/yr		
	CH ₄	CO ₂	GHG ^a	NO _x	VOC	CO
Landfill Scenario A ^b						
Vent LFG	135	614	3,444			
Purchase 71 kW		239	239	37	12	56
Total	135	853	3,683	37	12	56
Landfill Scenario B ^c						
Flared Landfill Gas	1	981	1,009	236	44	933
Purchase 71 kW	0	239	239	37	12	56
Total	1	1,220	1,248	274	56	989
Landfill Scenario C ^d						
71 kW HALO IC Engine	0	985	985	62	44	560

^a Greenhouse Gas equal to CO₂ plus 21•CH₄ (CH₄ GWP = 21; 21 times as effective at trapping heat than CO₂).

^b Landfill vents an amount of LFG equal to what could power a 71 kW BioHALO IC engine and purchases 71 kW from a BACT power plant.

^c Landfill flares the same LFG as case b and purchases 71 kW from a BACT plant.

^d Landfill installs 71 kW BioHALO IC Engine.

9.2 Economics of BioHALO

A second barrier to landfill gas to electricity projects is economics. Existing air quality regulations do not mandate conversion of the landfill gas to electricity; it simply must be combusted. For a landfill operator to undertake a landfill gas to electricity project, the avoided cost of purchased power must at least offset the cost of the annualized cost of the equipment. The simple payback period should be less than five years. Absent a mandate to install a prime mover, if it is less expensive to flare the gas, the gas will be flared. If the proposed project is successful, the installed cost for a reformer/IC engine system is estimated to be \$895 per kW. This assumes limited production of the reformer system (100 units per year). The simple payback period is estimated at 2.1 years. Table 9-2 provides estimates for the annualized costs of BioHALO IC engine system and compares these to those for a commercial microturbine system. The BioHALO IC engine system has the clear cost and NO_x emission advantage.

More and more landfills will be required to collect and process their gases over the next 10 years. These landfills and others that are currently flaring this resource could be enticed to convert it to electricity if the economics are attractive and the project is permissible. Successful demonstration of the authors' proposed technology will provide a low-cost, environmentally acceptable landfill gas to electricity technology option. Availability of this technology in the near term will minimize wasteful flaring of landfill gas, augment California's installed generating capacity, and reduce emissions of greenhouse gases without increasing criteria pollutant emissions. If successful demonstration of this technology does not occur within the

next two to three years, the gas will continue to be flared and/or conventional lean burn IC engines will be installed.

Table 9-2. Estimated Costs for Typical LFG to Electricity Projects

71 kW LFG to Electricity Project	Units	BioHALO IC Engine	Commercial Microturbine
Total Installed Cost ^{a,b}	\$	63,510	138,428
	\$/kW	895	1,950
Assumptions			
Lifetime	yrs	10	10
Interest Rate	\$	8	8
Annual Capital Cost	\$/yr	9,465	20,630
Avoided Cost of Power			
Purchase Price ^c	\$/kWh	0.081	0.081
Capacity Factor	%	80	80
kWh Generated	kWh	497,568	497,568
Cost Savings	\$/yr	40,303	40,303
Affordability	\$/kWh	0.0190	0.0415
Net Benefit	\$/yr	30,838	19,673
Simple Payback	yrs	2.1	7.0
NO _x Emissions	lb/MWh	0.100	1.72
	g/bhp-hr	0.032	x
	ppm (15% O ₂)	x	25
	lb/MMBtu	0.01	0.116

^a IC engine gen set capital cost = \$500/kW; Reformer = \$300 per kW H₂+CO generated plus \$1,000 for controls. Includes modules listed in the bill of materials (see Table 8-2 above), including activated carbon trap for removal of sulfur and siloxane contaminants upstream of reformer. Assume installation is 50% of capital cost.

^b SCAQMD purchased and installed 53 Capstone 60 kW units for \$6.2 million.

^c From PG&E medium size business tariff.

9.3 Addressable Market for BioHALO

The proposed BioHALO process development and demonstration offers California a robust near-term technology that addresses an immediate market and has ultimate addressable market potential well in excess of the longer-term, higher risk, alternative technologies. In comparison to turbine technologies, the integrated BioHALO system offers comparable emissions but at lower cost, enhanced load-following capability and improved tolerance to fuel contaminants. Compared to fuel cells, the BioHALO system offers immediate commercialization, lower risk, improved load following characteristics, and broader fuel flexibility.

It is especially important that the resultant commercialization package is a near-term, integrated and robust system because many landfills in the addressable market have been closed and are managing a gradual decline in LFG capacity. It is essential that California penetrate this market with low-cost, reliable, but clean systems before the capacity is lost.

The market will be primarily new gen-sets equipped with the BioHALO technology. The integrated package will be offered commercially by LFG engine packagers such as Gauscor, Deutz, Caterpillar, and Waukesha. They will have full responsibility for a turnkey system, including engineering, procurement, system integration, and installation. The packager will procure the autothermal reformer from Intelligent Energy or Aspen Products Group for hydrogen generation. The CHP feature, generating hot water from the waste heat, will be offered as an option. The packagers have an existing network of sales representatives and field engineers that will be mobilized for this new offering upon satisfactory demonstration of the results from the first demonstration site. This use of existing commercialization infrastructure will greatly facilitate the market penetration, reduce entry time and overhead costs, and will rely on established relationships with suppliers and customers. For the smaller retrofit market, the BioHALO configuration retrofit requirements will be highly site-specific. In these cases, the packager will sell the package through the existing sales network. The packager will perform the engineering and installation of the autothermal reformer system and will subcontract the engine modifications to the engineer/supplier for the current engine.

The BioHALO technology addresses the majority of landfill gas-to-energy opportunities identified in the 1999 EPA inventory (EPA 430-K-99-004). Specifically, landfill opportunities addressed include:

- Retrofits to current projects to reduce emissions or expand capacity (estimate addressable market at 9 sites, 77 MW).
- New BioHALO gen-set installations at candidate sites for power or CHP generation (addressable: 14 sites, 78 MW).
- Reactivation of units at shutdown sites with sustained LFG generation (addressable: 3 sites, 8 MW).
- New BioHALO gen-sets at other sites (addressable: 35 sites, 15 MW).
- New BioHALO gen-sets or retrofit to existing units at “unknown WIP” sites (addressable: 39 gen-sets, 20 MW).

The total addressable market size is 100 sites adaptable to the BioHALO technology with an aggregate generating capacity potential of 198 MW. The total capital installed cost for the addressable market is \$177 million. For 20 percent capture of the addressable market and 10 percent margin, the earnings back to the BioHALO packager would be about \$3.5 million.

The public benefits include:

- Displacement of central station power, or creation of new generating capacity at lower cost: Annual public savings of \$12M in power costs (based on a cost savings of \$0.06/kW-hr).
- Reduction in total greenhouse gas loading to the state of 0.9 million tons/ yr of CO₂ equivalent. Annual cost equivalent (at \$25/ton GHG) of \$22M.

- Reduction in NO_x for landfills previously using higher emission IC engines or turbines, or using flaring.

Clearly, the development of the BioHALO technology shows strong commercial prospects with strong public and private benefits justifying the investment. Annual public benefits from deployment of the technology up to approximately 6 percent of the total market will exceed \$30M, justifying the PIER investment. Total private earnings over the market life cycle are \$3.5M, justifying the BioHALO packager investment in launching the commercial offering at the conclusion of this project and an initial field demonstration.

The emission reduction potential with BioHALO technology fully complies with the form and intent of SB 1298, and the implementation of that legislation could promote the commercial prospects of the BioHALO offering. Upon successful demonstration of the technology, the BACT for NO_x from landfill and other waste gas firing will be lowered to the same level as central station NO_x, rather than necessitating the higher levels accorded presently. The lower BACT level with the BioHALO technology, coupled with the lower cost and robust design, will stimulate the market for the integrated package.

10.0 Conclusions and Recommendations

A biogas-fueled engine project was undertaken to demonstrate a new hydrogen-assisted operation technology that offers significant economic and environmental advantages over conventional low-NO_x engines for landfill gas to electricity applications. This innovative technology enables use of hydrogen-enriched landfill gas, produced on-site, to shift the operating point of gas engines to low NO_x regimes that are otherwise not feasible. Using this technology, there is no need for a selective reduction catalyst (SCR) system, which can be quite costly and subject to siloxane poisoning. The gas engines are conventional modern engines in many respects, except they are specially fitted with an upstream fuel reformer, which produces up to 10% hydrogen in the modified landfill gas fuel mixture.

Conclusions:

- A conventional 75 kW, 10-cylinder Ford gas engine was successfully modified to operate on hydrogen-enriched landfill gas at high levels of excess air at the TIAX engine test facility, in preparation for the demonstration test. (Special engine parts and subsystems were fabricated, which made the engine hydrogen-assist ready).
- A significant number of technical advances were made, and these are summarized in this report for the benefit of future landfill gas engine development teams that undertake the commercialization of low-NO_x systems for landfill-gas power production.
- Testing was conducted to optimize the BioHALO operating configuration for this engine using synthetic landfill gas and reformat gas mixed from gas cylinders,. The key conclusion is that an NO_x level of 0.11 lb per megawatt-hour could be achieved with BioHALO (see summary of test points below).
- A reformer subsystem was designed to produce hydrogen from landfill gas with required heat exchangers and process controls. The design includes parts list and estimated component costs.
- The interface of the reformer to the gas engine was separately designed with required start up sequencing.
- Extended duration tests at the low NO_x operating point at the TIAX test facility were conducted at energy commission request to demonstrate sustained operation,
- A path to market to commercialize the BioHALO technology was outlined, and there are no fundamental barriers perceived.

The following target performance specifications of the mature commercial embodiment of the hydrogen-assisted engine will make this technology quite competitive:

- 34-38% efficiency
- \$1000/kW installed cost

- Emission levels controlled to 0.1 lb per megawatt-hour NO_x
- No requirement for SCR

Based upon scoping tests in Task 2.2 and the concept optimization tests in Task 2.3, the BioHALO technology was demonstrated in the TIAX engine facility to be successful in improving the emissions performance of the engine. NO_x levels of 0.11 lb per megawatt-hour were measured in sustained operation with hydrogen addition allowing 100% excess air (10% oxygen in exhaust). However, emissions levels are still slightly above the proposed goals. Following is a list of the conclusions and recommendations from the testing:

- The improved mixing provided by the intake redesign in addition to the higher amounts of hydrogen supplementation proved effective in reducing the engine emissions.
- The ignition system, when switched to high-energy options, did not show a particular improvement in performance or emissions. A further concern noted during this task was that even though ignition was achieved of the mixture, the burn times are slightly longer than desirable, leading to cycle-to-cycle variability.
- Water injection was interesting in that it allowed for lower NO_x emissions when compared to a standard point of similar dilution but did not improve the emissions to the point beyond emissions targets.
- Although NO_x targets were not met, the results show an impressive emissions reduction for a reciprocating engine technology. For example, BACT for a Hess Microgen stoichiometric natural gas engine with a three -way catalyst is 0.07 g/bhp-hr, and this project demonstrated multiple points 50-67% of this value *engine out*.

The Task 2.2 scoping tests showed the ability of BioHALO technology to achieve a significant 93% reduction in the NO_x emissions levels using reformat, when compared to the NO_x at the leanest operating condition without reformat addition. However, the project target of 0.032 g/bhp-hr NO_x (0.1 lb per megawatt-hour) was not met, and reaching this target would require an additional 75% NO_x reduction. In the Task 2.2 tests, the lean limit of operation reached was 8% O₂ and the engine would not run at acceptable COV at the lean conditions (beyond 8% O₂ in the exhaust) needed to reach the 0.1 lb per megawatt-hour NO_x level.

A summary of the lowest NO_x points obtained in Task 2.3, which still provided acceptable combustion stability is shown below in Table 10-1 .

Table 10-1. Summary of low NOx points with acceptable combustion stability

IMEP (bar)	IMEP COV (%)	NOx (Corrected to 15 % O ₂) [ppm]	NOx (g/bhp hr, 15% O ₂)	H ₂ LHV/CH ₄ LHV	NOx (lb/MW hr), 15 % O ₂
5.4	8.1	5	0.035	13.5%	0.10
6.9	11.0	7	0.044	11.4%	0.13
6.6	8.7	10	0.071	7.5%	0.21
6.8	12.4	9	0.078	14.7%	0.23
N/A	N/A	4	0.043	14.2%	0.13
6.1	8.7	8	0.044	10.7%	0.13
5.9	3.7	7	0.047	14.7%	0.14
6.6	8.7	10	0.071	7.5%	0.21

The NOx results as summarized in the above table show a significant reduction when compared to the results obtained in Task 2.2; so the methods of further NOx reduction suggested in the Task 2.2 test report were effective. The results do come close to the project goals 0.032 g/bhp-hr or 0.07 lb/MW-hr but are still above those goals.

Recommendations:

- It would be interesting to explore using hydrogen supplementation as an enabler for high load/high dilution pre-mixed charge ignition concepts. The hydrogen supplementation was able to light off, but work could be done to improve its combustion stability as well as improve burn durations. Using a high-energy micro-pilot or compression ignition might answer the two concerns raised in this task and provide the dilution necessary for even lower NOx.
- Because this was a test plan designed to encompass a range of operating conditions, each point was short to finish all of the testing required in the given amount of time. To prove the value of the system, it would be desirable to run for a much longer period.
- A commercial partner should be identified to provide needed matching funds (and host landfill gas site) to build the field installation and to operate the landfill gas engine facility on actual landfill gas as opposed to synthetic simulated gas.
- An actual reformer should be fabricated and demonstrated as part of BioHALO rather than use synthetic bottled gas reformat as was done here.

11.0 Glossary

A	Humidity coefficient
ATR	Auto-thermal reformer
B	Temperature coefficient
BioHALO	Biogas Hydrogen-Assisted Lean Operation
C	Carbon
CEM	Continuous Emissions Monitoring
CID	Cubic inches of displacement
CO	Carbon monoxide
CO ₂	Carbon dioxide
COV	Coefficient of variation
ECU	Engine control unit
EGR	Exhaust gas recirculation
Fb	Spindt constant
Fc	Spindt fuel constant
H	Specific humidity
H(2)	Hydrogen
IC(E)	Internal combustion (engine)
IMEP	Indicated mean effective pressure
K	Dimensionless correction factor
LFG	Landfill gas
LHV	Lower heating value
LVN	Least normalized value
O ₂	Oxygen
Pb	Barometric pressure
Pv	Partial pressure of water
PWM	Pulse width modulated
Q	O ₂ /CO ₂ ratio
R	CO/CO ₂ ratio
RH	Relative humidity
RPM	Revolutions per minute
T	Temperature
T/C	Thermocouple
TTL	Transistor type logic
Y	H/C mass fraction
NO _x	Oxides of nitrogen
η_{fi}	Indicated fuel conversion efficiency

APPENDIX A. COMPLETE DATA SET

Equations Used FOR Emissions Data Conversion

Since NO_x formation is affected by humidity at the test site, a correction will be made using the following expression [1]:

$$NO_{xcorr} = \frac{NO_x}{K} \quad (A1)$$

NO_x has units of ppm, and K (a dimensionless correction factor) is defined as follows:

$$K = 1 + 7 * A(H - 10.714) + 1.8B(T - 29.44) \quad (A2)$$

A in the above equation is:

$$A = 0.044 \left(\frac{Fuel}{Air} \right) - 0.0038 \quad (A3)$$

The fuel-air-ratio is on a dry mass basis, and is dimensionless for both equations A3 and A4:

The variable B from equation A2 is:

$$B = -0.116 \left(\frac{Fuel}{Air} \right) + 0.0053 \quad (A4)$$

T is the intake temperature in deg C, and H is defined as:

$$H = \frac{621.98P_v}{P_b - P_v} \quad (A5)$$

P_v is the partial pressure of the water vapor in in Hg, and P_b is the barometric pressure in in Hg. Since during the test dry bulb temperature and relative humidity (in percent) were recorded, P_v may be calculated from equation A6:

$$P_v = RH(P_d) \quad (A6)$$

P_d is calculated from the following equation:

$$P_d = -4.14438 \times 10^{-3} + 5.76645 \times 10^{-3}T - 6.32788 \times 10^{-5}T^2 + 2.12294 \times 10^{-6}T^3 - 7.85415 \times 10^{-9}T^4 + 6.55263 \times 10^{-11}T^5 \quad (A7)$$

Where T is Temperature in deg F, and the equation is valid from 20 to 110°F.

The relative air/fuel ratio is calculated using the well-accepted Spindt method from the engine exhaust constituents as measured by the emissions bench. The Spindt equation is shown below [2]:

$$F_b * (11.492 * F_c * ((1 + 0.5 * R + Q)/(1 + R))) + ((120 * (1 - F_c))/(3.5 + R)) \quad (A8)$$

F_b is defined as:

$$(CO_2 + CO)/(CO_2 + CO + (0.001 * THC)) \quad (A9)$$

Where CO₂ and CO are in volume percent, and THC is in ppm.

F_c is defined as:

$$12.01/(12.01 + 1.008 * Y) \quad (A10)$$

Where Y is the H/C mass ratio of the fuel being used during the test. R is the ratio of CO to CO₂, and Q is the ratio of O₂ to CO₂, all on a dry volume basis.

Indicated Power in kW was calculated from the IMEP (kPa) by the following expression:

$$P = \frac{IMEP(V_d)(N)}{1000 n_r} \quad (A11)$$

Where V_d is the engine displaced volume in dm³, N is the number of revolution per second, and n_r is 2 for a four-stroke engine.

Brake Power was calculated given the electrical power output and the generator efficiency as shown on the Marathon generator specification sheet. Table A-1 shows the Marathon generator efficiency:

Table A-1. Marathon Generator Conversion Efficiency

Electrical Power (kW)	Efficiency
40	94%
60	93%
80	92%

The indicated specific fuel consumption is calculated by dividing the fuel flowrate by the indicated power.

The fuel conversion efficiency is calculated as:

$$\eta_{fi} = \frac{P}{m_f Q_{LHV}} \quad (A12)$$

Where P is the power as calculated above in Watts, m_f is the fuel flow rate in kg/s, and Q_{LHV} is the Lower Heating Value of the fuel in J/kg. For the fuel conversion efficiencies shown here, hydrogen was included as a fuel, with a LHV = 120 MJ/kg, and natural gas with a LHV = 45 MJ/kg.

The specific emissions were calculated using the following formula:

$$\left[\frac{g}{kW-hr} \right] = \frac{0.062(exh)(NO_x)}{P} \quad (A13)$$

Where *exh* is the exhaust mass flow rate in kg/min, NO_x has units of ppm, and Power is in kW, and due to the conservation of mass, includes the air, fuel, CO₂, N₂, and reformat ingested into the engine [1].

NO_x is corrected to 15% O₂ in the exhaust using the following expression:


$$NO_x (15\% O_2) = \frac{5.9}{20.9 - O_2} NO_x \quad (A14)$$

Where O_2 is the measured dry concentration of oxygen in percent, and NO_x is the dry measured concentration of NO_x in ppm [3].


References:

1. SAE J177 Jun95: "Measurement of Carbon Dioxide, Carbon Monoxide, and Oxides of Nitrogen in Diesel Exhaust."
2. Spindt, R.S., 1965, "Air-Fuel Ratios from Exhaust Gas Analyzer," SAE Paper No. 650507.
3. Method 20: Determination of Nitrogen Oxides, Sulfur Dioxide and Diluent Emissions from Stationary Gas Turbines. State of California Air Resources Board. Adopted: March 28, 1986 Amended: July 1, 1999.

Complete Data Set and Supplemental Data



The above graph shows a sweep of IMEP while holding a fixed air/fuel ratio and LPP. The lower in-cylinder temperatures at the lower IMEP lead to less NOx production.



*

This Figure shows the effect of spark retard on NO_x production. Spark retard lowers the in-cylinder temperature, but there is a fuel economy loss, as shown by the ISFC values.

Table A-2: Summary of Test Results

Date	Indicated Power (kW)	isfc (g/kW hr)	isfc (lbm/hp hr)	Indicated Fuel Conv. Eff.	IMEP (bar)	COV %	LVN %	LPP (deg)	1090 (deg)	FFR (g/s)	%O2	Hum. corr Nox	NOx g/ ihp-hour	NOx g/bhp hour	NOx lb/MW hr	15% O2 Corr. Nox
5-Aug-05	85	228	0.37	35%	8.3	1.4	95.8	20	29.75	5.36	2.5	2722	9.47	11.67	34.50	903
5-Aug-05	81	262	0.43	30%	7.9	4.5	82.6	24	38.00	5.88	4.2	298	1.23	1.53	4.52	112
5-Aug-05	81	212	0.35	38%	7.9	15.4	-1.7	18	37.00	4.77	5.5	436	1.78	2.21	6.53	182
6-Sep-05	79	220	0.36	36%	7.8	1.5	94.3	19.74	32.92	4.84	1.6	2457	8.29	10.31	30.48	767
6-Sep-05	71	203	0.33	39%	7.0	7.1	64.7	18.32	39.85	4.01	7.3	48	0.25	0.31	.92	23
5-Aug-05	79	235	0.39	34%	7.7	5.1	78.0	21	39.00	5.11	5.8	102	0.49	0.61	1.80	44
5-Aug-05	86	200	0.33	39%	8.5	1.9	92.8	23	33.00	4.76	3.1	728	2.67	3.28	9.70	252
5-Aug-05	80	230	0.38	34%	7.8	4.5	79.0	23	37.00	5.06	7.4	110	0.53	0.66	1.95	55
5-Aug-05	78	215	0.35	37%	7.7	3.1	86.7	25	36.00	4.64	3.5	352	1.34	1.68	4.97	125
5-Aug-05	65	255	0.42	31%	6.4	38.0	-2.4	14	41.00	4.59	7.9	69	0.37	0.48	1.42	36
5-Aug-05	82	210	0.35	37%	8.1	2.1	91.0	23	33.00	4.72	5.1	307	1.26	1.56	4.61	124
5-Aug-05	75	213	0.35	36%	7.4	3.6	87.0	23	37.00	4.35	6.7	62	0.28	0.36	1.06	29
5-Aug-05	61	263	0.43	30%	6.0	18.0	1.2	4.85	49.00	4.35	8.1	21	0.12	0.16	.47	11
9-Aug-05	52	294	0.48	26%	5.1	62.0	-2.4	10.12	41.22	4.20	8.5	81	0.58	0.78	2.31	45
5-Aug-05	68	261	0.43	30%	6.7	12.3	9.8	1.7	47.00	4.85	7.2	23	0.15	0.20	.59	11
5-Aug-05	70	247	0.41	31%	6.9	8.2	64.0	2.8	45.00	4.70	7.6	20	0.12	0.15	.44	10
9-Aug-05	67	240	0.39	32%	6.6	30.4	-1.6	13.34	43.88	4.36	8.2	48	0.29	0.38	1.12	26
5-Aug-05	83	201	0.33	38%	8.1	1.7	94.0	22	31.00	4.52	5.3	280	1.14	1.41	4.17	115
6-Sep-05	87	231	0.38	33%	8.6	2.6	89.3	24.85	32.34	5.45	3.3	569	2.35	2.88	8.51	200
5-Aug-05	70	203	0.33	38%	6.8	4.8	57.0	21	39.00	3.83	7.6	31	0.15	0.19	.56	16
9-Aug-05	83	189	0.31	40%	8.2	3.0	84.7	18.59	33.35	4.23	7.3	133	0.65	0.81	2.39	65
9-Aug-05	78	196	0.32	39%	7.6	2.6	89.4	23.03	33.52	4.08	6.3	99	0.49	0.61	1.80	44
9-Aug-05	73	204	0.34	37%	7.1	6.3	35.8	20.08	38.74	3.97	7.8	34	0.16	0.20	.59	17
6-Sep-05	75	193	0.32	39%	7.3	4.3	86.6	22.09	35.36	3.85	7.2	63	0.30	0.38	1.12	31
6-Sep-05	33	397	0.65	19%	3.3	50.4	-4.6	1.07	58.16	3.50	11.1	4	0.04	0.06	.18	3
6-Sep-05	71	184	0.30	41%	7.0	2.3	86.2	22.91	32.79	3.47	6.2	113	0.52	0.66	1.95	50
6-Sep-05	47	210	0.35	35%	4.6	28.7	-1.9	5.67	53.21	2.62	8.9	10	0.06	0.09	.27	6
6-Sep-05	43	290	0.48	26%	4.2	45.6	-3.4	2.73	53.05	3.29	9.5	7	0.05	0.08	.24	4

Task 2.3 Conceptual Process Optimization Data Points

date	time	Test Set	Water flow (g/s) or EGR Value	Intake Air Temperature (deg C)	Brake Power (kW)	Air (kg/s)	MAP (kPa)	CH4 flow (kg/s)	IMEP (bar)	IMEP COV (%)	10-90 burn (CAD)	Humidity Corr NOx (ppm)	NOx (15% O2)	NOx (g/bhp hr @ 15%)	THC (ppm)	Dry CO2 (%)	Dry O2 (%)	Dry CO (%)	NOx COV (%)	H2 Suppl. (%LHV)	Brake Efficiency	NOx (lb/MW- hour)
18-Jan-07	11:42	2		60	41	0.10	110	0.003	5.4	8.1	46.74	8	5	0.035	6922	6.1	10.9	0.01	2.70	13.5%	30%	0.10
24-Jan-07	16:31	2		58	48	0.13	110	0.004	6.2	27.0	44.67	11	6	0.048	1895	7.5	9.7	0.06	14.30	11.3%	26%	0.14
24-Jan-07	16:35	2		55	46	0.14	110	0.004	5.9	39.0	44.86	8	5	0.044	4158	7.0	10.5	0.07	29.70	12.5%	25%	0.13
25-Jan-07	13:56	2		59	57	0.11	117	0.004	7.1	4.7	35.08	68	31	0.190	613	8.7	8.1	0.04	41.70	9.5%	32%	0.56
25-Jan-07	14:05	2		62	61	0.11	121	0.004	7.5	1.7	31.08	94	46	0.247	526	6.1	8.8	0.03	7.90	9.5%	36%	0.73
25-Jan-07	14:18	2		69	56	0.11	121	0.004	6.9	11.0		14	7	0.044	1002	7.2	9.2	0.05	3.20	11.4%	33%	0.13
25-Jan-07	14:23	2		66	36	0.12	125	0.003	4.9	15.8	51.55	8	4	0.040	1086	7.3	9.2	0.05	6.00	12.1%	22%	0.12
25-Jan-07	15:56	2		59	55	0.11	116	0.004	6.9	4.2	35.98	42	20	0.123	761	8.0	8.7	0.04	9.10	9.1%	34%	0.36
25-Jan-07	15:59	2		60	43	0.11	115	0.003	5.6	18.3	46.48	13	7	0.051	2052	9.2	9.1	0.06	11.70	9.2%	27%	0.15
25-Jan-07	16:02	2		61	54	0.11	113	0.003	6.8	4.0	33.69	65	32	0.186	648	5.9	9.1	0.04	23.70	9.0%	34%	0.55
25-Jan-07	16:04	2		61	57	0.11	113	0.003	7.1	5.3	33.28	61	30	0.166	709	6.0	8.9	0.04	46.00	8.9%	36%	0.49
25-Jan-07	16:08	2		64	47	0.12	125	0.004	6.0	17.3	45.04	14	7	0.053	1655	5.6	9.7	0.06	11.10	8.4%	28%	0.16
25-Jan-07	16:21	2		67	53	0.12	130	0.004	6.6	8.7	42.87	21	10	0.071	1064	6.1	9.1	0.05	15.00	7.5%	29%	0.21
31-Jan-07	15:48	2		54	45	0.13	105	0.004	5.8	40.0	39.7	99	33	0.277	1285	9.1	4.7	0.04	17.40	0.0%	24%	0.00
31-Jan-07	15:45	3		53	62	0.12	100	0.004	7.6	12.8	30.38	824	279	1.583	327	10.2	3.5	0.03	6.80	0.0%	31%	4.68
31-Jan-07	16:10	3		50	55	0.12	100	0.004	6.8	16.6	32.02	137	60	0.387	719	8.6	7.3	0.03	11.40	7.4%	31%	1.14
31-Jan-07	16:15	3		53	64	0.13	110	0.004	7.8	10.3	29.92	257	109	0.684	549	8.7	7.0	0.03	18.32	8.5%	34%	2.02
31-Jan-07	16:19	3		53	33	0.17	130	0.004	4.5	80.2	33.1	18	9	0.139	4598	7.3	9.4	0.06	11.37	7.8%	17%	0.41
31-Jan-07	16:28	3		54	70	0.16	130	0.004	8.5	14.2	29.95	111	53	0.354	919	8.1	8.5	0.03	13.60	11.0%	38%	1.05
31-Jan-07	16:33	3		53	55	0.16	128	0.003	6.8	34.9	35.79	39	19	0.169	2341	7.8	9.2	0.05	22.08	13.1%	37%	0.50
31-Jan-07	17:46	3		52	24	0.16	123	0.004	3.6	76.0	39	6	4	0.071	6420	6.3	11.0	0.12	6.70	14.1%	14%	0.21
31-Jan-07	17:49	3		53	49	0.16	123	0.004	6.2	27.8	40.27	13	7	0.066	2399	7.0	10.0	0.08	10.70	14.4%	29%	0.20
31-Jan-07	17:52	3		53	55	0.15	121	0.004	6.8	12.4	37.65	18	9	0.078	1890	7.0	10.0	0.06	5.90	14.7%	33%	0.23
31-Jan-07	17:55	3		53	49	0.15	123	0.004	6.2	25.3	39.99	11	6	0.058	2792	6.8	10.3	0.08	4.70	14.7%	30%	0.17
1-Feb-07	11:05	3		49	61	0.11	100	0.004	7.5	1.6	25.8	535	229	1.288	474	8.5	7.1	0.03	19.70	11.8%	35%	3.81
1-Feb-07	11:11	3		51	28	0.16	126	0.004	4.0	81.4	36.7	12	7	0.111	7721	6.4	10.5	0.09	7.90	9.6%	15%	0.33
1-Feb-07	11:16	3		53	64	0.17	130	0.004	7.8	24.8	34.2	65	31	0.235	1295	7.8	8.4	0.04	23.00	10.3%	33%	0.69
27-Feb-07	10:48	3		N/A	54	0.09	105	0.004	N/A	N/A	N/A	3707	1265	6.217	262	9.7	3.6	0.04	1.10	0.0%	30%	18.38
27-Feb-07	10:52	3		N/A	52	0.09	105	0.004	N/A	N/A	N/A	636	238	1.297	462	10.2	5.1	0.03	14.70	0.0%	29%	3.84
27-Feb-07	10:56	3		N/A	59	0.11	105	0.003	N/A	N/A	N/A	181	78	0.448	497	8.4	7.3	0.03	17.80	9.0%	36%	1.32
27-Feb-07	10:58	3		N/A	40	0.11	105	0.003	N/A	N/A	N/A	13	7	0.058	4074	7.0	9.7	0.07	13.50	11.0%	25%	0.17
27-Feb-07	11:01	3		N/A	36	0.15	105	0.003	N/A	N/A	N/A	7	4	0.053	8651	6.0	11.1	0.10	6.50	13.5%	22%	0.16
27-Feb-07	11:03	3		N/A	46	0.15	105	0.003	N/A	N/A	N/A	8	4	0.043	5291	6.4	10.4	0.09	8.20	14.2%	28%	0.13
10-Jan-07	14:49	4	8%	70	59	0.09	105	0.004	7.3	5.8	32.4	36		0.000	838	4.2	16.3	0.01	9.50	8.9%	36%	0.00
16-Jan-07	15:55	4		49	48	0.09	108	0.003	6.1	8.7	37.13	15	8	0.044	2267	7.8	9.5	0.07	29.00	10.7%	32%	0.13
16-Jan-07	16:02	4	8%	87	46	0.10	110	0.003	5.9	5.1	37.55	41	19	0.122	1059	8.1	8.1	0.05	53.00	15.5%	35%	0.36
16-Jan-07	16:13	4	9%	58	46	0.10	110	0.003	5.9	3.7	37.42	14	7	0.047	1337	7.2	9.7	0.06	22.10	14.7%	36%	0.14
18-Jan-07	11:33	4	31%	86	46	0.10	110	0.003	5.96	1.7	35.42	34	16	0.100	2007	7.8	8.0	0.05	88.00	14.7%	36%	0.30
30-Jan-07	15:52	4		90	54	0.15	123	0.004	6.8	13.5	39.86	36	16	0.130	1537	8.7	7.6	0.04	6.20	9.4%	28%	0.39
1-Feb-07	14:36	4	9%	56	63	0.17	120	0.004	7.7	16.4	35.3	56	24	0.191	1094	9.5	7.4	0.04	14.70	10.5%	33%	0.56
1-Feb-07	14:44	4	12%	55	40	0.17	125	0.004	0.0	7080.7	3.6	13	7	0.089	10721	7.2	10.2	0.07	12.20	10.6%	21%	0.26
14-Feb-07	14:12	4		55	56	0.09	96	0.003	N/A	N/A	N/A	56	25	0.133	N/A	8.2	8.0	0.03	11.40	13.5%	34%	0.39
14-Feb-07	14:24	4	18%	105	52	0.08	94	0.003	N/A	N/A	N/A	57	22	0.114	N/A	9.7	5.8	0.03	23.60	13.5%	34%	0.34
27-Feb-07	11:12	4	8%	N/A	45	0.15	105	0.004	N/A	N/A	N/A	317	122	1.232	365	9.5	5.6	0.03	5.00	9.7%	26%	3.64
27-Feb-07	11:16	4	14%	N/A	63	0.10	105	0.004	N/A	N/A	N/A	299	105	0.503	367	10.4	4.1	0.03	6.70	9.7%	37%	1.49
27-Feb-07	11:20	4	23%	N/A	49	0.14	105	0.004	N/A	N/A	N/A	42	13	0.118	2171	11.4	2.5	0.14	5.00	9.7%	29%	0.35
25-Jan-07	16:04:00	5	3	61	57	0.11	113	0.003	7.1	5.3	33.3	61	30	0.166	709	6.0	8.9	0.04	46	8.9%	36%	0.49
25-Jan-07	16:08:00	5	1	61	47	0.12	125	0.003	6.0	17.3	45.0	14	7	0.053	1655	5.6	9.7	0.06	11.1	8.5%	29%	0.16
25-Jan-07	16:21:00	5	1	67	53	0.12	130	0.004	6.6	8.7	42.9	21	10	0.071	1064	6.1	9.0	0.05	15.1%	7.5%	29%	0.21
Extended Run				N/A	55	0.12	120	0.003	N/A	N/A	N/A	10.6	6	.042	1900	6.9	9.4	0.06	23%	12%	31%	0.12

bioHALO Electrical Connection Timeline

